

PROFESSIONAL HANDBOOK

# AI for Utility-Scale Solar & BESS Project Development

## VOLUME 1

AI Foundations & Professional Workflows

SolarDev AI

Edition v1.1 | 2026



PROFESSIONAL HANDBOOK

# AI for Utility-Scale Solar & BESS Project Development

---

## VOLUME 1

AI Foundations & Professional Workflows

SolarDev AI

Edition v1.1 | 2026

# Copyright and Professional Disclaimer

Copyright © 2026 SolarDev AI All rights reserved.

No part of this publication may be reproduced, distributed or transmitted in any form or by any means without prior written permission from the copyright holder, except for brief quotations used in reviews, professional commentary or other uses permitted by law.

This handbook is provided for educational and professional reference. It does not constitute project-specific engineering, legal, environmental, commercial, tax, financial or investment advice. Utility-scale Solar PV and Battery Energy Storage System projects must be assessed by qualified professionals using current project information, applicable legislation, grid codes, standards, contracts and authority requirements.

Artificial Intelligence outputs may be incomplete, inaccurate or unsuitable for a specific project. AI must not be treated as an engineering authority. The user remains responsible for validating calculations, technical statements, assumptions, sources, risks, compliance conclusions and recommendations before they are used in professional deliverables or decisions.

Standards, regulations, market conditions, technology specifications and cost benchmarks change over time. Readers should consult the latest authoritative sources and obtain specialist advice whenever required.

## Professional responsibility

The engineer, developer, adviser, contractor, owner or investor issuing or relying on a deliverable retains responsibility for the underlying decision. AI assistance does not transfer accountability.

# Preface

---

## *Why this volume exists*

Utility-scale Solar PV and BESS development has become a multidisciplinary exercise in managing incomplete information, competing constraints and fast-moving decisions. Engineers and developers must coordinate land, grid, permitting, environmental, civil, electrical, commercial, programme and financing considerations long before a project reaches detailed design.

Artificial Intelligence can materially improve this work when it is embedded inside a controlled professional methodology. It can organise evidence, identify gaps, structure reviews, prepare first drafts, compare options and accelerate communication. Used without discipline, it can also introduce false confidence, unsupported conclusions and hidden errors.

Volume 1 establishes a practical foundation for responsible AI-assisted project development. It begins with engineering philosophy and professional prompting, then follows the early development sequence from research and due diligence through site identification, development planning, land control, remote imagery, field reconnaissance, environmental and social screening, risk management and initial CAPEX benchmarking.

The central principle is simple: AI should increase the time available for engineering judgement, not reduce the need for it.

### **Volume 1 objective**

Enable professionals to create faster, more consistent and more traceable early-stage Solar PV and BESS development outputs while preserving technical integrity and accountability.



## About the Author

---

### SolarDev AI

SolarDev AI is a renewable-energy professional focused on utility-scale Solar PV and BESS project development. His work spans multidisciplinary engineering coordination, technical assessment, project risk, development planning and the translation of complex technical information into decision-ready outputs.

This handbook reflects a practitioner-led approach: AI is treated as a structured professional assistant operating inside real project-development workflows rather than as a replacement for qualified judgement.

## How to Use This Handbook

The volume can be read sequentially as a development workflow or used chapter-by-chapter as a professional reference. Each chapter combines engineering context with repeatable AI-assisted methods.

| Chapter element                                                                                                                                                                               | Purpose                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|
| Engineering background                                                                                                                                                                        | Explains the project-development problem and why it matters.                                     |
| Controlled workflow                                                                                                                                                                           | Breaks the task into evidence, analysis, validation and decision stages.                         |
| Professional tables                                                                                                                                                                           | Provides registers, matrices, scopes and review structures that can be adapted to live projects. |
| Worked example                                                                                                                                                                                | Shows how the methodology applies to a utility-scale Solar PV and BESS opportunity.              |
| Prompt toolkit                                                                                                                                                                                | Includes Quick, Professional and Expert prompts for different levels of task maturity.           |
| Review checklist                                                                                                                                                                              | Provides a final quality-control gate before an AI-assisted deliverable is issued.               |
| <b>Recommended use</b><br>Before using any prompt, define the decision required, identify the available evidence, state the project stage and specify who will review and approve the output. |                                                                                                  |

## Acronyms and Abbreviations

| Term  | Meaning                                          |
|-------|--------------------------------------------------|
| AI    | Artificial Intelligence                          |
| BESS  | Battery Energy Storage System                    |
| BOP   | Balance of Plant                                 |
| CAPEX | Capital Expenditure                              |
| COD   | Commercial Operation Date                        |
| DSO   | Distribution System Operator                     |
| E&S   | Environmental and Social                         |
| EPC   | Engineering, Procurement and Construction        |
| FEED  | Front-End Engineering Design                     |
| GIS   | Geographic Information System                    |
| HSE   | Health, Safety and Environment                   |
| IEC   | International Electrotechnical Commission        |
| LCOE  | Levelised Cost of Energy                         |
| LiDAR | Light Detection and Ranging                      |
| MWac  | Megawatts alternating current                    |
| MWdc  | Megawatts direct current                         |
| MWh   | Megawatt-hours                                   |
| O&M   | Operations and Maintenance                       |
| POI   | Point of Interconnection                         |
| PV    | Photovoltaic                                     |
| RACI  | Responsible, Accountable, Consulted and Informed |
| RTB   | Ready to Build                                   |
| SCADA | Supervisory Control and Data Acquisition         |
| TSO   | Transmission System Operator                     |
| WBS   | Work Breakdown Structure                         |

# Contents

## Volume 1 AI Foundations & Professional Workflows

Page numbers refer to the final PDF edition. In Microsoft Word, page references may update when fields are refreshed after editing.

| Chapter | Title and scope                                                                                                                                                                                             | Page |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|
| 1       | <b>Becoming an AI-Enhanced Utility-Scale Solar Project Development Engineer</b><br>Engineering philosophy, prompt design, validation and professional accountability.                                       | 10   |
| 2       | <b>AI-Assisted Research &amp; Technical Due Diligence for Utility-Scale Solar and BESS Projects</b><br>Research strategy, evidence traceability, information gaps and investment-grade conclusions.         | 23   |
| 3       | <b>AI-Assisted Site Identification &amp; Preliminary Feasibility Screening for Utility-Scale Solar and BESS Projects</b><br>Constraint screening, site scoring, fatal flaws and development prioritisation. | 40   |
| 4       | <b>AI-Assisted Preliminary Development Roadmap for Utility-Scale Solar and BESS Projects</b><br>Workstreams, dependencies, decision gates and Ready-to-Build planning.                                      | 60   |
| 5       | <b>AI-Assisted Landowner Assessment and Land-Control Strategy for Utility-Scale Solar and BESS Projects</b><br>Ownership evidence, parcel strategy, project rights and ethical land engagement.             | 78   |
| 6       | <b>AI-Assisted Satellite and Aerial Image Interpretation for Utility-Scale Solar and BESS Projects</b><br>Remote imagery, access, terrain, drainage, receptors and targeted field verification.             | 99   |
| 7       | <b>AI-Assisted Site Visit Planning, Field Due Diligence and Site Visit Reporting for Utility-Scale Solar and BESS Projects</b><br>Field planning, HSE, evidence capture, issue ownership and reporting.     | 120  |
| 8       | <b>AI-Assisted Environmental and Social Constraint Screening for Utility-Scale Solar and BESS Projects</b><br>Environmental and social baseline, surveys, mitigation and permitting risk.                   | 143  |
| 9       | <b>AI-Assisted Initial Project Risk Register for Utility-Scale Solar and BESS Projects</b><br>Risk causes, consequences, ownership, treatment, triggers and residual exposure.                              | 166  |
| 10      | <b>AI-Assisted Initial CAPEX Benchmark for Utility-Scale Solar and BESS Projects</b><br>Estimate basis, scope, benchmarking, contingency, sensitivities and uncertainty.                                    | 190  |



## Volume 1 Development Sequence

---

1. Establish responsible AI-assisted engineering practice
2. Build an evidence-controlled research and due-diligence process
3. Identify and compare technically plausible sites
4. Convert the preferred opportunity into a coordinated development roadmap
5. Secure land and project rights consistent with the technical concept
6. Use remote imagery to target uncertainty and field verification
7. Capture decision-grade field evidence
8. Define environmental and social constraints, surveys and mitigation
9. Consolidate findings into an accountable project risk register
10. Translate the early project basis into a transparent CAPEX range

### End-state of Volume 1

A structured early-stage development basis that supports informed progression, targeted studies, realistic risk ownership and a transparent initial investment view.

## CHAPTER 1

# Becoming an AI-Enhanced Utility-Scale Solar Project Development Engineer

---

*Professional AI Workflow*

*Engineering methodology, prompt design and professional validation*

Edition v1.1 | Volume 1

*"AI does not replace engineering responsibility; it increases the value of structured engineering judgement."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This opening chapter defines the professional methodology used throughout both volumes. It explains where AI creates value, where it introduces risk, how engineers should structure AI-assisted work, and how to validate every output before it becomes an engineering deliverable.

| Element                | Purpose                                                             |
|------------------------|---------------------------------------------------------------------|
| Learning objectives    | Defines the competencies developed in the chapter.                  |
| Engineering philosophy | Positions AI inside a structured decision-making process.           |
| Professional workflow  | Provides a repeatable method from problem definition to validation. |
| Prompt framework       | Translates consultant instructions into high-quality AI prompts.    |
| Quality controls       | Introduces review questions, common mistakes and validation checks. |
| Prompt toolkit         | Provides quick, professional and expert prompt levels.              |

*Table 1.1 — Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Explain how Artificial Intelligence is changing utility-scale Solar PV and Battery Energy Storage System (BESS) project development.
- Recognise the tasks where AI creates genuine engineering value and the decisions that must remain under professional control.
- Apply a structured AI-assisted workflow across research, technical assessment, documentation and project coordination.
- Develop consultant-grade prompts that include role, context, inputs, task, deliverables and constraints.
- Critically review AI-generated content before incorporating it into technical reports, recommendations or project decisions.
- Integrate AI into daily engineering activities while protecting confidentiality, technical integrity and professional accountability.

## 1.1 Introduction

The renewable energy industry is entering a new phase of digital transformation. Previous decades were defined by improvements in photovoltaic cell architecture, power conversion equipment, battery technology, construction methods and project finance. The next major shift is being driven by Artificial Intelligence (AI).

Unlike a higher-efficiency PV module or a lower-loss inverter, AI does not directly improve the physical performance of a power plant. Its immediate value lies in how it changes the work of engineers: it accelerates information review, organises complex project inputs, drafts structured documents, compares alternatives and supports repeatable decision-making.

For Project Development Engineers, this represents a significant opportunity. A large proportion of the development lifecycle involves collecting information, reviewing technical documents, coordinating specialists, comparing options and preparing reports for internal teams, clients, investors, lenders, authorities and contractors. These activities are essential, but many are repetitive and time-intensive.

Modern AI systems can assist with these tasks in a fraction of the time traditionally required. They can summarise lengthy studies, compare equipment specifications, structure due diligence findings, draft executive reports, organise meeting actions and identify information gaps. Used well, AI allows engineers to devote more time to high-value activities such as technical judgement, project optimisation, stakeholder management and risk reduction.

It is important, however, to distinguish between assistance and authority. Artificial Intelligence is not a licensed engineer. It cannot visit a site, certify a design, accept contractual responsibility, approve safety-critical decisions or understand project history unless that context is supplied. It has no professional liability and no inherent awareness of an organisation's internal standards, risk appetite or commercial commitments.

For this reason, AI should be treated as an engineering assistant rather than an engineering authority. Every workflow in this handbook ends with engineering review and technical validation. Responsibility for the final recommendation always remains with the qualified professional.

#### ENGINEERING INSIGHT

AI can accelerate analysis and documentation, but professional responsibility cannot be delegated. The engineer must understand, verify and approve every conclusion that influences the project.

## Why This Handbook Is Different

Many AI publications focus on general productivity or provide lists of prompts without explaining how those prompts fit into real professional workflows. This handbook takes a different approach: it is written specifically for professionals involved in utility-scale Solar PV and BESS project development.

The target audience includes Project Development Engineers, Solar Design Engineers, Civil Engineers, Grid Connection Engineers, Owner's Engineers, Independent Engineers, EPC Engineers, Technical Advisors, Project Managers and asset owners. The methods are organised around the actual lifecycle of a project—from opportunity screening and due diligence through permitting, grid strategy, technical design, procurement and readiness for construction.

The objective is not merely to produce documents faster. It is to improve the consistency, traceability and quality of engineering work while preserving professional judgement.

## How to Use This Handbook

Each chapter combines engineering methodology with practical AI workflows. Readers may work sequentially through the volumes or use individual chapters as reference material when performing a specific project task.

- Engineering background explains why the task matters and where it fits in the project lifecycle.
- Professional workflows break complex problems into repeatable engineering steps.
- Consultant-grade prompts translate project requirements into structured AI instructions.
- Worked examples demonstrate how the method can be applied to realistic utility-scale projects.

- Engineering commentary identifies limitations, review requirements and decision risks.
- Checklists and prompt toolkits support immediate day-to-day use.

## 1.2 The Modern Project Development Engineer

The role of the Project Development Engineer has evolved considerably. Historically, development engineers focused primarily on technical feasibility. Today, they operate at the intersection of engineering, commercial strategy, environmental management, regulation, project finance and stakeholder coordination.

A modern engineer is expected to coordinate multiple disciplines while maintaining a clear understanding of the project's technical, commercial and regulatory objectives. The breadth of this role explains why development engineers spend a substantial proportion of their time working with information rather than performing isolated calculations.

| Responsibility Area        | Typical Activities                                                                                                    |
|----------------------------|-----------------------------------------------------------------------------------------------------------------------|
| Opportunity identification | Screening new opportunities, identifying fatal flaws, supporting acquisition and exclusivity decisions.               |
| Site assessment            | Reviewing solar resource, topography, land use, access, environmental constraints and expansion potential.            |
| Grid connection            | Comparing substations, coordinating applications, reviewing grid requirements and supporting interconnection studies. |
| Permitting                 | Coordinating environmental studies, technical inputs, authority responses and permit conditions.                      |
| Engineering coordination   | Reviewing layouts, comparing technologies, preparing design bases and coordinating disciplines.                       |
| Commercial support         | Supporting CAPEX estimates, EPC tenders, technical bid evaluation and risk assessment.                                |
| Project governance         | Preparing executive reports, maintaining risk registers, coordinating decisions and supporting Financial Close.       |

*Table 1.2 — Typical responsibilities of a utility-scale Project Development Engineer.*

## 1.3 Where Artificial Intelligence Creates Value

AI is most effective when supporting structured, information-intensive activities. It is less effective when a task depends on field observation, certified calculation, contractual interpretation or professional accountability. Understanding this boundary is essential to responsible adoption.

| Application                        | Typical AI Contribution                                                               | Relative Value |
|------------------------------------|---------------------------------------------------------------------------------------|----------------|
| Research and information gathering | Summarising technical papers, regulations, market information and authority guidance. | High           |

|                           |                                                                                                    |           |
|---------------------------|----------------------------------------------------------------------------------------------------|-----------|
| Technical due diligence   | Consolidating findings, identifying information gaps and structuring preliminary risk assessments. | High      |
| Engineering documentation | Drafting reports, design bases, technical specifications, minutes and executive summaries.         | Very high |
| Technology evaluation     | Comparing modules, inverters, mounting systems, BESS options and supplier submissions.             | High      |
| Risk management           | Organising risk registers, suggesting mitigations and highlighting recurring themes.               | High      |
| Project coordination      | Producing minutes, action trackers, progress summaries and follow-up communications.               | Very high |
| Executive communication   | Converting detailed technical findings into concise decision-focused summaries.                    | Very high |

*Table 1.3 — Areas where AI commonly creates value in project development.*

## Research and Information Gathering

Project development begins long before detailed calculations. Engineers review planning frameworks, transmission information, environmental mapping, manufacturer documentation and technical publications. AI can rapidly summarise this information and organise findings into a structured research note. The engineer should then verify the conclusions against authoritative sources and determine their applicability to the project.

## Technical Due Diligence

Technical due diligence requires the simultaneous review of several disciplines. AI is useful for extracting key findings from environmental reports, geotechnical investigations, grid studies, feasibility assessments and commercial assumptions. It can identify missing information and recurring themes, but it cannot determine investment acceptability without project-specific judgement.

## Engineering Documentation

Documentation is one of the largest administrative burdens in development. Technical reports, Design Basis Memoranda, Employer's Requirements, clarification responses and Investment Committee papers often share repeatable structures. AI can create a strong first draft, after which engineers verify facts, calculations, assumptions, references and recommendations.

## Technology Evaluation

Technology decisions frequently involve dozens of technical, financial and operational criteria. AI can organise datasheet information, produce weighted decision matrices and draft comparison reports. The engineer must select the criteria, verify source information and determine which trade-offs matter for the specific project.



## Risk Management and Coordination

AI can suggest risk categories, draft mitigation measures, consolidate meeting notes and maintain consistent reporting formats. Probability, impact, ownership, commercial strategy and risk acceptance remain human decisions.

## 1.4 Understanding the Limitations of AI

The benefits of AI are significant, but its limitations must be explicitly managed. Professional engineers should never assume that AI-generated content is automatically correct, current or applicable.

### AI Does Not Understand the Project Unless Context Is Provided

AI has no direct knowledge of the client, internal procedures, project history, contractual commitments or local engineering practices. These factors must be provided. Without them, the output will be generic and may conflict with the project's actual requirements.

### AI Can Produce Confident but Incorrect Answers

AI may generate plausible but inaccurate standards, calculations, equipment characteristics, regulations or interpretations. The tone of confidence is not evidence of correctness. Every material statement should be checked against primary documentation, calculations and qualified professional review.

### AI Cannot Replace Engineering Judgement

Professional engineering requires balancing technical, commercial, environmental, programme and regulatory considerations. AI cannot accept liability, approve designs, replace site inspections, certify compliance, sign drawings or make safety-critical decisions. Those responsibilities remain with qualified professionals and authorised organisations.

## Confidentiality, Data Protection and Intellectual Property

Project information may include confidential designs, commercial prices, personal data, grid information, land agreements and intellectual property. Engineers should follow organisational policies before uploading documents to any external AI service. Sensitive information should be removed, anonymised or processed in approved environments.

### COMMON MISTAKE

Do not upload confidential employer, client or project information into an AI service unless its use is authorised by the organisation and compliant with applicable data-protection and contractual requirements.

## 1.5 Engineering Philosophy

Experienced engineers rarely solve complex projects with a single question. They decompose uncertain problems into smaller decisions, analyse each decision using appropriate evidence and then integrate the findings into a coherent recommendation.



Figure 1.1 — Engineering decision sequence used throughout the handbook.

Consider the instruction: “Design a 350 MW solar project with a 200 MW / 400 MWh BESS.” This apparently simple request contains many separate work packages. A professional engineer breaks it down before any AI tool is used.

| Work Package           | Examples of Decisions                                                             |
|------------------------|-----------------------------------------------------------------------------------|
| Opportunity assessment | Site viability, land constraints, permitting route and fatal flaws.               |
| Grid connection        | Point of interconnection, voltage level, reinforcement, curtailment and schedule. |
| Technology selection   | Module technology, inverter architecture, mounting system and BESS chemistry.     |
| Engineering design     | Civil layout, electrical architecture, drainage, foundations, cables and SCADA.   |
| Commercial evaluation  | CAPEX, OPEX, energy yield, LCOE, procurement and contract risk.                   |
| Decision support       | Executive summary, risk register, recommendation and action plan.                 |

Table 1.4 — Decomposition of a complex utility-scale project request.

#### ENGINEERING INSIGHT

Large engineering problems are rarely solved directly. They are solved through a sequence of smaller, well-informed decisions. AI should support that sequence rather than attempt to bypass it.

## 1.6 The AI-Assisted Engineering Workflow

A repeatable workflow improves the reliability, consistency and traceability of AI-assisted engineering work. The sequence below is used throughout the handbook.



Figure 1.2 — AI-assisted engineering workflow.

### Step 1 — Define the Engineering Objective

Identify the decision required, intended audience, project stage and level of detail. A clear objective prevents unfocused analysis.

## Step 2 — Collect Project Information

Provide the same information that a competent engineer would need: coordinates, drawings, reports, specifications, schedules, calculations and constraints.

## Step 3 — Assign a Professional Role

Specify the perspective required, such as Lead Solar Design Engineer, Owner's Engineer, Grid Connection Specialist or Technical Due Diligence Consultant.

## Step 4 — Define the Deliverables

List the exact outputs required, such as an Executive Summary, compliance matrix, risk register, information gaps and action plan.

## Step 5 — Validate the Result

Review the output against project documentation, calculations, applicable standards, utility requirements, internal procedures and professional judgement.

### BEST PRACTICE

The quality of the AI output is determined long before the first sentence is generated. It is determined by the quality of the engineering problem definition and the completeness of the inputs.

## 1.7 The Anatomy of a Consultant-Grade Prompt

A professional prompt should resemble the instructions issued to a specialist consultant. It must establish responsibility, context, scope, inputs, outputs and constraints.

| Component         | What to Include                                                       |
|-------------------|-----------------------------------------------------------------------|
| Professional role | The perspective and level of expertise required.                      |
| Project context   | Country, capacity, technology, stage, client and objective.           |
| Inputs            | Documents, drawings, data, assumptions and source material.           |
| Engineering task  | The specific analysis, comparison, review or document required.       |
| Deliverables      | The requested structure and decision-support outputs.                 |
| Constraints       | Standards, regulations, exclusions, assumptions and required caveats. |

*Table 1.5 — Core components of a consultant-grade prompt.*

### WORKED EXAMPLE — POOR PROMPT

"Review this solar project." This instruction lacks context, supporting information, defined deliverables and an engineering objective. The response will likely be generic.

**WORKED EXAMPLE — CONSULTANT-GRADE PROMPT**

You are acting as the Lead Owner's Engineer reviewing the preliminary design of a 350 MW utility-scale Solar PV project with a 200 MW / 400 MWh BESS in southern Spain. Using the supplied Design Basis Memorandum, preliminary layout, grid connection study, environmental screening and geotechnical investigation, prepare a structured technical review. Include an Executive Summary, Design Assessment, Technology Review, Technical Risk Register, Information Gaps, Recommended Actions and a Go/No-Go recommendation for progression to FEED. Clearly distinguish verified information, engineering assumptions and areas requiring further investigation.

## 1.8 Engineering Commentary

AI-generated content should be regarded as a first draft or decision-support tool, not as a final engineering opinion. A qualified engineer applies experience, engineering principles and professional judgement. AI produces statistically likely text based on patterns and available inputs. The distinction is fundamental.

Professional engineers should question AI outputs in the same way they question manufacturer claims, consultant reports or contractor submissions. The source changes; the review discipline does not.

- Is the information technically correct and internally consistent?
- Are the assumptions appropriate for the project?
- Is supporting evidence available and traceable?
- Does the conclusion apply to this jurisdiction, project stage and design basis?
- What information is missing, uncertain or outside the AI's competence?

AI reduces the time required to organise information and prepare documents. The time saved should be reinvested in better engineering: investigating alternatives, challenging assumptions, improving design quality, reducing risk and communicating decisions more clearly.

## 1.9 Common Mistakes When Using AI

| Common Mistake            | Why It Creates Risk                                                                                 |
|---------------------------|-----------------------------------------------------------------------------------------------------|
| Vague questions           | Requests such as "review the project" do not define context, scope or deliverables.                 |
| Insufficient information  | Constructability, grid or design reviews cannot be credible without the relevant project documents. |
| Replacing judgement       | AI may identify options, but risk acceptance and engineering approval remain human decisions.       |
| Ignoring assumptions      | Unstated assumptions make results difficult to review and unsafe to reuse.                          |
| Combining unrelated tasks | Large multidisciplinary requests should be split into sequential work packages.                     |
| Forgetting the audience   | An Owner's Engineer report and an Investment Committee memo require different detail and language.  |

|                                               |                                                                                                           |
|-----------------------------------------------|-----------------------------------------------------------------------------------------------------------|
| Assuming regulatory knowledge                 | Local regulations and grid codes must be checked against current official sources.                        |
| Treating AI as an authoritative search engine | Generated text is not a substitute for primary documents and verified data.                               |
| Skipping peer review                          | AI-assisted outputs should follow the same review and approval process as other engineering deliverables. |
| Forgetting accountability                     | The engineer, organisation and authorised signatories remain responsible for the recommendation.          |

Table 1.6 – Common failure modes in AI-assisted engineering.

## 1.10 Best Practices

11. Begin with the engineering objective, not with the AI tool.
12. Treat AI as a capable junior engineer that requires clear instructions and supervision.
13. Provide complete, relevant and approved project information whenever possible.
14. Require assumptions, uncertainties and information gaps to be stated explicitly.
15. Break complex projects into repeatable workflows and manageable technical tasks.
16. Validate all material conclusions against project documents, calculations and standards.
17. Maintain version control and traceability for prompts, inputs and issued deliverables.
18. Protect confidential, personal and commercially sensitive information.
19. Use peer review for material technical, financial, contractual and safety-related outputs.
20. Improve the workflow library using lessons learned from real projects.

### BEST PRACTICE

Treat AI like a junior engineer: give it a clear role, complete inputs, a defined output structure and appropriate supervision. This mental model consistently improves results.

## 1.11 Engineering Review Checklist

| Review Area               | Confirmation Required                                                        |
|---------------------------|------------------------------------------------------------------------------|
| Project definition        | Objective, audience, project stage and deliverable are clearly defined.      |
| Input information         | Relevant documents, constraints and approved data have been supplied.        |
| Assumptions               | Assumptions and uncertainties are explicit and reasonable.                   |
| Technical accuracy        | Calculations, terminology, equipment data and conclusions have been checked. |
| Standards and regulation  | Applicable requirements have been verified against current primary sources.  |
| Evidence and traceability | Material claims can be linked to documents, calculations or                  |

|                 |                                                                              |
|-----------------|------------------------------------------------------------------------------|
|                 | recognised references.                                                       |
| Recommendations | Actions are practical, prioritised and aligned with the project objective.   |
| Peer review     | The output has received the review required by the organisation and project. |
| Final approval  | The authorised professional has approved the deliverable before issue.       |

*Table 1.7 – Minimum quality checks for AI-assisted engineering deliverables.*

### CONSULTANT'S QUICK VALIDATION QUESTIONS

Before accepting any AI recommendation, ask: (1) What evidence supports this conclusion? (2) What assumptions were made? (3) Could another solution be better? (4) What information is missing? (5) Would I be comfortable signing this recommendation as a professional engineer?

## 1.12 Prompt Toolkit

Prompts in this handbook are organised into three levels so the user can match the depth of the instruction to the importance and maturity of the task.

| Level        | Best Used For                                                                                  | Typical Output                                                            |
|--------------|------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|
| Quick        | Brainstorming, short summaries, internal notes and preliminary risk identification.            | Concise response or checklist.                                            |
| Professional | Structured assessments, project-team documents, design reviews and client discussions.         | Report with defined sections and actions.                                 |
| Expert       | Investment-grade reviews, Owner's Engineer work, lender support and procurement documentation. | Consultant-style deliverable with risks, assumptions and recommendations. |

*Table 1.8 – Prompt levels used throughout the handbook.*

### QUICK PROMPT

You are a Senior Project Development Engineer. Summarise the key technical risks associated with developing a 250 MW utility-scale Solar PV project at the supplied location. Highlight information gaps and recommend the next engineering actions.

### PROFESSIONAL PROMPT

You are acting as the Lead Project Development Engineer supporting a 250 MW Solar PV and 100 MW / 200 MWh BESS project in Portugal. Using the supplied due diligence report, preliminary layout, environmental screening and grid information, prepare a structured assessment including an Executive Summary, Technical Risks, Opportunities, Outstanding Information and Recommended Next Steps. Clearly distinguish verified information from assumptions.

**EXPERT PROMPT**

You are acting as the Lead Owner's Engineer reviewing the development readiness of a 350 MW utility-scale Solar PV project with a 200 MW / 400 MWh BESS. Using the supplied Design Basis Memorandum, site assessment, grid study, environmental reports, CAPEX estimate and preliminary schedule, prepare an investment-grade report including an Executive Summary, Technical Assessment, Design Maturity Review, Risk Register, Information Gaps, Mitigation Measures, Go/No-Go Recommendation and Prioritised Action Plan. Clearly identify assumptions, uncertainties and recommendations requiring further investigation.

## 1.13 Recommended Engineering References

AI-assisted work should be reviewed against authoritative technical guidance and the current requirements applicable to the project. The references below are indicative starting points; users should verify the latest edition, jurisdictional applicability and contractual status before relying on them.

- IEC standards addressing PV array design, documentation, inspection, commissioning and performance monitoring.
- IEC standards addressing electrical energy storage systems, safety and power-utility communications.
- IEEE interconnection guidance where applicable to the project jurisdiction.
- Country-specific transmission and distribution grid codes.
- IEA PVPS technical reports and good-practice publications.
- NREL and Fraunhofer ISE technical publications.
- PVsyst documentation and validated energy-yield methodologies.
- Manufacturer manuals, warranties, datasheets and independently verified test reports.
- Local planning, environmental, construction and electrical regulations.

## 1.14 Continuing Professional Development

AI tools, engineering standards and renewable-energy technologies continue to evolve. Engineers should treat AI competence as an area of continuing professional development rather than a one-time software training exercise.

- Review new AI capabilities and organisational governance requirements regularly.
- Update prompt templates based on lessons learned from completed projects.
- Share successful workflows within engineering teams while protecting confidential information.
- Continue formal technical development in solar, BESS, grid, civil and commercial disciplines.
- Reassess validation procedures as new AI tools and document-processing capabilities become available.

## 1.15 Chapter Summary

This chapter establishes the methodology that underpins the remainder of the handbook. AI is presented as a professional assistant operating inside a structured engineering process—not as a replacement for engineering education, experience, judgement or responsibility.

The essential principles are problem decomposition, clear objectives, complete inputs, consultant-grade prompting, explicit assumptions, technical validation and accountable approval. These principles are applied in



the following chapters to due diligence, site selection, permitting, grid connection, documentation, risk management, project coordination and professional communication.

## 1.16 Key Takeaways

- AI is a powerful engineering assistant, but it is not an engineering authority.
- The best outputs begin with a clearly defined decision, audience and project context.
- Complex projects should be broken into smaller engineering tasks and repeatable workflows.
- Every material conclusion must be checked against project evidence, current requirements and professional judgement.
- The time saved through AI should be used to improve engineering quality, investigate alternatives and reduce project risk.
- Professional responsibility, confidentiality and final approval always remain with the engineer and the authorised organisation.

### Chapter 1 Completion Checklist

- I can explain where AI creates value in utility-scale Solar PV and BESS development.
- I can distinguish between tasks suitable for AI assistance and tasks requiring qualified professional control.
- I can apply the AI-assisted engineering workflow from problem definition to final validation.
- I can write a consultant-grade prompt using role, context, inputs, task, deliverables and constraints.
- I can critically review AI-generated engineering content before using or issuing it.
- I understand that accountability for the final recommendation remains with the professional engineer.

#### LOOKING AHEAD — CHAPTER 2

AI-Assisted Research & Technical Due Diligence applies the methodology from Chapter 1 to the first major activity in project development: determining whether an opportunity is technically, environmentally and commercially credible before significant resources are committed.

END OF CHAPTER 1

## CHAPTER 2

# AI-Assisted Research & Technical Due Diligence for Utility-Scale Solar and BESS Projects

---

*From information gathering to investment-grade technical conclusions*

*Research strategy, evidence traceability, risk identification and decision support*

Edition v1.1 | Volume 1

*"Due diligence is not the collection of documents. It is the conversion of evidence into a defensible project decision."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a disciplined method for using Artificial Intelligence to accelerate project research and technical due diligence without weakening evidence quality, source traceability or professional accountability. It connects document review, multidisciplinary risk assessment and decision support into a repeatable workflow suitable for developers, investors, lenders and Owner's Engineers.

| Element                   | Purpose                                                                                                  |
|---------------------------|----------------------------------------------------------------------------------------------------------|
| Research strategy         | Defines the questions, source hierarchy and evidence required before analysis begins.                    |
| Due diligence workstreams | Organises the review across land, planning, environment, grid, design, yield, BESS, CAPEX and programme. |
| AI-assisted workflow      | Shows how to ingest, classify, compare and summarise project information efficiently.                    |
| Evidence controls         | Separates verified facts, assumptions, third-party claims and unresolved information gaps.               |
| Risk framework            | Converts findings into prioritised risks, mitigations, owners and decision consequences.                 |
| Prompt toolkit            | Provides reusable prompts for desktop research, document review and investment-grade due diligence.      |

*Table 2.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Design a research plan for a utility-scale Solar PV or BESS opportunity before significant engineering resources are committed.
- Distinguish authoritative primary sources from secondary commentary, vendor claims and unverified project statements.
- Structure technical due diligence across the principal development, engineering, grid, environmental, commercial and programme workstreams.
- Use AI to review large document sets, identify inconsistencies, extract obligations and maintain a traceable evidence register.
- Classify findings by severity, confidence, project impact and required action.
- Prepare consultant-grade outputs for project teams, Investment Committees, lenders, acquisition teams and Owner's Engineers.
- Recognise the limitations of AI-assisted research and apply appropriate engineering validation before issuing conclusions.

## 2.1 Introduction

Every successful utility-scale Solar PV and BESS project begins with research. Before a layout is optimised, an energy model is finalised or an EPC tender is issued, the project team must understand the site, the grid, the permitting route, the environmental constraints, the technology concept and the commercial assumptions that support the opportunity.

At early development stage, information is rarely complete. Documents may have been prepared at different times, by different consultants and for different purposes. Capacities may be quoted inconsistently. Coordinates may not match the land boundary. Grid correspondence may contain conditions that have not been reflected in the programme. Environmental studies may identify seasonal surveys that conflict with the target notice-to-proceed date. Cost estimates may rely on design assumptions that are no longer valid.

Technical due diligence is the process of converting this imperfect information into a structured view of project maturity, technical viability and risk. It asks whether the current evidence supports the proposed investment decision, what uncertainties remain, and which actions are required to protect value.

Artificial Intelligence can materially accelerate this work. It can classify documents, extract key findings, compare repeated statements, identify gaps, draft risk registers and produce consistent summaries across disciplines. It is especially useful when the project data room contains hundreds of files with inconsistent naming, duplicated information and lengthy reports.

The value of AI, however, depends on the quality of the review framework. If the engineering questions are poorly defined or the source hierarchy is ignored, AI can merely produce a faster summary of unreliable information. The objective is not to summarise everything. The objective is to identify the evidence that matters to the decision and determine how much confidence can be placed in it.

### ■ ENGINEERING INSIGHT

Research produces information. Due diligence produces a decision-ready view of the project. The professional task is to connect every material conclusion to evidence, uncertainty and consequence.

## 2.2 Research and Due Diligence in the Project Lifecycle

The depth and purpose of research change as the project matures. Early-stage screening is designed to identify fatal flaws quickly. Acquisition due diligence tests the claims presented by the seller and evaluates value at risk. Pre-FEED and FEED reviews confirm that the technical basis is sufficiently mature for design development, procurement and financing. Lender or Independent Engineer reviews focus on whether technical assumptions are reasonable, documented and compatible with the financial model.

| Project Stage           | Primary Due Diligence Objective                                                             | Typical Decision                         |
|-------------------------|---------------------------------------------------------------------------------------------|------------------------------------------|
| Opportunity screening   | Identify fatal flaws, major constraints and minimum information required for further spend. | Proceed, hold or reject the opportunity. |
| Development acquisition | Test seller claims, project rights, technical maturity, schedule and cost exposure.         | Acquire, reprice, condition or withdraw. |

|                        |                                                                                                  |                                                          |
|------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------|
| Pre-FEED / FEED        | Confirm design basis, survey sufficiency, grid assumptions, constructability and key interfaces. | Approve development budget or design progression.        |
| EPC procurement        | Check tender scope, bidder assumptions, exclusions, performance guarantees and interface risk.   | Shortlist, clarify or award.                             |
| Financing              | Evaluate bankability of design, yield, technology, contracts, schedule and contingency.          | Support Financial Close or require conditions precedent. |
| Construction readiness | Verify permits, land access, IFC maturity, long-lead equipment and execution plans.              | Issue notice to proceed or delay mobilisation.           |

Table 2.2 - Due diligence purpose by project stage.

A common failure is to apply the same level of analysis at every stage. An early-stage opportunity does not require the same design detail as a lender review, but it still requires sufficient evidence to determine whether major risks are visible and manageable. The scope should be proportionate to the decision, the capital at risk and the consequences of being wrong.

#### **BEST PRACTICE**

Define the investment or engineering decision before defining the due diligence scope. The decision determines the required evidence, materiality threshold and level of technical detail.

## 2.3 Building a Professional Research Strategy

Professional research begins with questions rather than searches. Before opening a browser, data room or AI tool, the engineer should define what must be known, why it matters and what source could provide authoritative evidence.



Figure 2.1 - Research strategy from decision to defensible conclusion.

### Define the Decision

Examples include whether to acquire a project, enter exclusivity, approve a development budget, accept a grid solution, progress to FEED or issue an EPC tender. The same project information may be interpreted differently depending on the decision and risk appetite.

### Convert the Decision into Key Questions

A project-level question such as “Is this opportunity viable?” must be decomposed into specific technical questions: Is the land controlled? Is the permitted capacity consistent with the grid application? Are environmental surveys complete? Is the substation route feasible? Are equipment assumptions compatible with the energy model? Is the programme achievable?

## Define the Required Evidence

For each question, specify the evidence that would be considered adequate. A seller presentation may indicate that a grid connection is secured, but the relevant evidence is normally the official connection offer, accepted conditions, payment status and applicable milestones. The due diligence process should distinguish between a claim and the document that proves it.

## Establish a Materiality Threshold

Not every discrepancy deserves the same attention. The materiality threshold should reflect potential impact on project capacity, schedule, CAPEX, revenue, safety, permitting, contractual position or bankability. Small editorial inconsistencies may be noted but should not distract from issues capable of changing the investment decision.

## 2.4 Source Hierarchy and Evidence Reliability

AI can summarise many sources, but it does not automatically know which source should govern. A professional review therefore establishes a source hierarchy before conclusions are drawn.

| Evidence Level                     | Typical Sources                                                                                                    | Indicative Reliability                               | Required Treatment                                                         |
|------------------------------------|--------------------------------------------------------------------------------------------------------------------|------------------------------------------------------|----------------------------------------------------------------------------|
| Level 1 - Primary authority        | Permits, official grid offers, legislation, land titles, executed contracts, issued surveys and certified reports. | Highest, subject to authenticity and current status. | Use as controlling evidence and verify validity, scope and conditions.     |
| Level 2 - Approved project records | Design basis, approved drawings, calculation reports, formal meeting minutes and controlled registers.             | High when revision-controlled and approved.          | Confirm revision, approval status and consistency with primary evidence.   |
| Level 3 - Specialist analysis      | Consultant studies, desktop assessments, vendor calculations and preliminary engineering reports.                  | Variable; depends on scope, inputs and competence.   | Review assumptions, limitations, methodology and applicability.            |
| Level 4 - Secondary information    | Industry reports, published articles, market commentary, mapping portals and public databases.                     | Useful for context but not always project-specific.  | Corroborate material conclusions with primary or project-specific sources. |
| Level 5 - Unverified statements    | Emails, presentations, sales claims, verbal explanations and AI-generated summaries.                               | Lowest until supported.                              | Record as a claim or assumption, not as a verified fact.                   |

*Table 2.3 - Evidence hierarchy for project research and due diligence.*

### COMMON MISTAKE

A polished presentation, confident email or fluent AI summary may be useful, but none of them proves that a project right, permit, design assumption or grid condition exists. Material conclusions must be tied to controlling evidence.

## Currency and Revision Status

A source may be genuine but outdated. Due diligence should record issue date, revision, validity period, approval status and superseded documents. This is particularly important for grid studies, environmental baselines, technology datasheets, cost estimates, programmes and land schedules.

## Geographic and Jurisdictional Applicability

Technical guidance from one jurisdiction may not apply in another. Planning rules, grid codes, environmental procedures, fire requirements and construction practices must be verified for the project location. AI-assisted research should explicitly state the jurisdiction and request that uncertainty be identified rather than silently generalised.

## 2.5 Principal Technical Due Diligence Workstreams

A complete review is multidisciplinary. The precise scope depends on project stage, but the following workstreams capture the principal technical questions for utility-scale Solar PV and BESS projects.

| Workstream                             | Core Review Questions                                                                                                                                           |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Project definition and rights          | Legal entity, project capacity, ownership, exclusivity, development rights, transaction perimeter and consistency across documents.                             |
| Land and access                        | Land control, parcel boundaries, easements, access rights, rights-of-way, setbacks, competing uses and route constraints.                                       |
| Planning and permitting                | Application status, approved capacity, conditions, appeal risk, expiry dates, pre-construction obligations and permit dependencies.                             |
| Environmental and social               | Protected areas, habitats, archaeology, cultural heritage, water, noise, glint and glare, visual impact, community issues and survey seasonality.               |
| Topography, hydrology and geotechnical | Terrain suitability, cut and fill, flood exposure, drainage, erosion, soil conditions, corrosivity, foundation risk and survey sufficiency.                     |
| Solar resource and energy yield        | Dataset selection, long-term adjustment, horizon, soiling, degradation, losses, availability, clipping, uncertainty and consistency with design.                |
| Grid connection                        | Connection rights, capacity, point of interconnection, milestones, securities, studies, reinforcements, curtailment, reactive power and compliance obligations. |
| PV design and technology               | Module, inverter, mounting concept, DC/AC ratio, electrical architecture, layout assumptions, equipment bankability and design maturity.                        |
| BESS design and use case               | Power and energy rating, duration, augmentation, degradation, operating strategy, thermal management, fire safety, warranty and grid services.                  |

|                                       |                                                                                                                                                  |
|---------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|
| Civil and electrical constructability | Site logistics, roads, crossings, drainage, cable routes, substations, interfaces, temporary works, construction sequencing and HSE constraints. |
| CAPEX, OPEX and programme             | Estimate basis, quantities, exclusions, contingency, escalation, long-lead items, development milestones, critical path and schedule realism.    |
| Contracts and procurement interfaces  | EPC scope, owner-supplied equipment, warranties, guarantees, exclusions, grid scope, testing, commissioning and responsibility gaps.             |

Table 2.4 - Core due diligence workstreams for Solar PV and BESS projects.

## 2.6 The AI-Assisted Due Diligence Workflow

AI should be inserted into a controlled document-review process. The following workflow is designed to preserve source traceability while reducing manual effort.



Figure 2.2 - AI-assisted technical due diligence workflow.

### Step 1 - Establish the Scope and Materiality

Define the decision, disciplines, review depth, exclusions, reporting format and materiality thresholds. Record what is outside scope so that silence is not interpreted as approval.

### Step 2 - Create the Document Inventory

List every file with title, date, revision, author, discipline and status. Identify duplicates, missing annexes, corrupted files and documents referenced but not supplied.

### Step 3 - Classify and Prioritise

Group documents by workstream and priority. Review primary evidence and high-impact documents before background material. Do not allow volume to determine importance.

### Step 4 - Extract Structured Findings

Use AI to capture obligations, capacities, dates, assumptions, conditions, exclusions, risks and required actions in a consistent template.

### Step 5 - Cross-Check Documents

Compare values and claims across permits, grid correspondence, layouts, energy models, cost estimates and programmes. Flag conflicts rather than selecting a value without justification.

### Step 6 - Assess Risk and Confidence

Classify each finding by severity, probability, confidence in evidence, project consequence, mitigation and owner.



## Step 7 - Perform Engineering Validation

Qualified specialists verify material conclusions, calculations, standards, contractual interpretations and current regulatory requirements.

## Step 8 - Produce Decision-Support Outputs

Prepare the executive summary, red-flag report, detailed findings, risk register, information request list and prioritised action plan.

### BEST PRACTICE

AI may accelerate extraction and comparison, but the due diligence team must control scope, evidence hierarchy, materiality and final interpretation.

## 2.7 Document Control and Evidence Traceability

A due diligence conclusion is defensible only when the reviewer can show where it came from. Every material finding should be traceable to a document, revision, page, calculation, interview record or explicit assumption.

| Field            | Purpose                                                                                            |
|------------------|----------------------------------------------------------------------------------------------------|
| Finding ID       | Provides a unique reference for review comments, risks and actions.                                |
| Workstream       | Allows sorting by land, permitting, grid, design, BESS, yield, CAPEX or programme.                 |
| Source reference | Identifies document title, revision, date, page or drawing number.                                 |
| Statement type   | Classifies the entry as verified fact, third-party claim, reviewer assumption or unresolved gap.   |
| Finding          | Records the technical observation in neutral, precise language.                                    |
| Impact           | Explains potential effect on capacity, cost, schedule, revenue, compliance, safety or bankability. |
| Confidence       | Indicates the strength and completeness of the evidence.                                           |
| Required action  | Defines the next step, responsible party and target date.                                          |

*Table 2.5 - Minimum fields in an evidence and findings register.*

### Verified Facts, Assumptions and Gaps

These categories should never be blended. A verified fact is supported by controlling evidence. An assumption is a deliberate working basis used because evidence is incomplete. A gap is information required for a conclusion but not available. A third-party claim is a statement received from another party that has not yet been independently verified.

| Classification      | Definition                                                            | Example                                                                |
|---------------------|-----------------------------------------------------------------------|------------------------------------------------------------------------|
| Verified fact       | Supported by current, relevant and authoritative evidence.            | The accepted grid offer states a maximum export capacity of 200 MW.    |
| Third-party claim   | Stated by a project party but not yet supported by adequate evidence. | The seller states that all land leases are executed.                   |
| Reviewer assumption | Temporary basis adopted for analysis and clearly disclosed.           | Assume a two-hour BESS duration pending final use-case confirmation.   |
| Information gap     | Evidence required to complete or validate the review is missing.      | No flood study has been supplied for the proposed substation platform. |

Table 2.6 - Information classifications used in professional due diligence.

### ENGINEERING INSIGHT

The statement “no issue identified” is not equivalent to “issue closed.” It may simply mean that the information required to identify the issue was not provided.

## 2.8 High-Value AI Tasks in Research and Due Diligence

AI creates the greatest value in repeatable, text-intensive tasks where the engineer defines the review framework and verifies the output. The following applications are particularly effective.

| AI Task                   | Professional Use                                                                        | Human Control Required                                                             |
|---------------------------|-----------------------------------------------------------------------------------------|------------------------------------------------------------------------------------|
| Document inventory        | Extract filenames, titles, dates, authors, revisions and disciplines.                   | Confirm metadata, duplicates and missing documents.                                |
| Report summarisation      | Produce structured summaries of methodology, findings, limitations and recommendations. | Check technical accuracy and omitted qualifications.                               |
| Obligation extraction     | Identify permit conditions, grid milestones, payment dates and technical requirements.  | Verify wording against original documents and legal interpretation where required. |
| Cross-document comparison | Compare project capacity, coordinates, dates, equipment and assumptions across files.   | Determine which source governs and whether the conflict is material.               |
| Gap analysis              | Map required evidence against supplied information.                                     | Define what evidence is necessary and prioritise requests.                         |
| Risk register drafting    | Convert findings into risks, impacts, mitigations and actions.                          | Set probability, severity, ownership and acceptance.                               |
| Executive reporting       | Translate detailed findings into concise decision-support language.                     | Ensure balance, materiality and consistency with the technical report.             |
| Meeting and Q&A support   | Prepare clarification questions and consolidate responses.                              | Confirm that responses close the issue and are supported by evidence.              |

Table 2.7 - High-value AI applications and required professional controls.

## 2.9 Risk Rating, Confidence and Materiality

A useful due diligence report distinguishes the seriousness of the issue from the confidence in the evidence. A potentially severe risk supported by limited information should be highlighted differently from a minor issue confirmed by complete documentation.

| Rating                 | Indicative Meaning                                                                                               | Typical Decision Consequence                                          |
|------------------------|------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------|
| Critical / Red         | Potential fatal flaw, loss of project rights, major safety or compliance issue, or material threat to economics. | Immediate escalation; may stop, reprice or condition the transaction. |
| High / Amber-Red       | Material cost, schedule, capacity, revenue or bankability exposure requiring defined mitigation.                 | Action required before approval or included as a condition precedent. |
| Medium / Amber         | Manageable issue with identifiable mitigation and limited decision impact.                                       | Track through development plan, budget and risk register.             |
| Low / Green            | Minor issue, normal development action or documentation improvement.                                             | Close through routine project management.                             |
| Information Gap / Grey | Insufficient evidence to determine exposure.                                                                     | Request information; avoid assuming the risk is low.                  |

Table 2.8 - Indicative technical due diligence rating scale.

Confidence may be rated independently as high, medium or low. A high-confidence finding is supported by current, consistent and authoritative evidence. A low-confidence finding may depend on incomplete documents, unverified statements or uncertain assumptions. Reporting both dimensions helps decision-makers understand not only what the issue may be, but how certain the review team is.

## 2.10 The Consultant-Grade Due Diligence Prompt

A strong due diligence prompt defines the professional role, transaction context, evidence set, review scope, materiality, deliverables and validation rules. It should instruct the AI to avoid inventing missing information and to preserve traceability to sources.

| Prompt Component   | Due Diligence Requirement                                                                            |
|--------------------|------------------------------------------------------------------------------------------------------|
| Role               | Specify Lead Technical Advisor, Owner's Engineer, Independent Engineer or discipline specialist.     |
| Decision context   | State whether the review supports screening, acquisition, financing, FEED or construction readiness. |
| Project definition | Provide location, capacities, technologies, development stage and transaction perimeter.             |

|                  |                                                                                               |
|------------------|-----------------------------------------------------------------------------------------------|
| Inputs           | List supplied reports, drawings, models, contracts, correspondence and registers.             |
| Scope            | Define included workstreams, exclusions, materiality and required depth.                      |
| Deliverables     | Request executive summary, red flags, detailed findings, risk register, gaps and action plan. |
| Evidence rules   | Require source references and classification of facts, claims, assumptions and gaps.          |
| Quality controls | Require explicit uncertainty, no invented citations and professional validation before issue. |

*Table 2.9 - Components of a consultant-grade technical due diligence prompt.*

#### WORKED EXAMPLE - POOR PROMPT

"Review the data room and tell me whether the project is good." The task does not define the transaction decision, materiality, workstreams, evidence hierarchy, output structure or standard of review.

#### WORKED EXAMPLE - PROFESSIONAL PROMPT

You are acting as the Lead Technical Advisor supporting the potential acquisition of a 300 MWp Solar PV project with a 150 MW / 600 MWh BESS in Spain. Review the supplied data room, including land schedules, planning documents, environmental studies, grid correspondence, preliminary layouts, energy-yield report, BESS concept, CAPEX estimate and development programme. Prepare: (1) an Executive Summary; (2) a red-flag table; (3) findings by workstream; (4) a technical risk register; (5) a document and information-gap register; and (6) a prioritised 30/60/90-day action plan. For every material finding, cite the source document and classify the statement as verified fact, third-party claim, reviewer assumption or information gap. Do not infer that an issue is closed merely because no evidence has been supplied. Clearly identify matters requiring legal, environmental, grid or specialist engineering review.

## 2.11 Worked Example: Acquisition-Stage Solar PV and BESS Review

Consider a developer evaluating the acquisition of a late-stage project presented as 300 MWp Solar PV plus a 150 MW / 600 MWh BESS. The seller states that land is secured, environmental approval has been obtained and a 200 MW grid connection is available. The target construction start is eighteen months after acquisition.

The initial data room contains a planning decision, a preliminary layout, an environmental impact report, several land spreadsheets, a grid application, an unsigned connection-offer draft, a P50/P90 energy-yield report, a high-level BESS single-line diagram, a CAPEX estimate and a development programme.

### Step 1 - Establish the Decision Questions

- Are the project rights and capacities consistent across land, planning, grid and design documents?
- Does the supplied evidence support the seller's statement that the project is ready for acquisition?

- Which risks could materially affect purchase price, schedule, capacity, CAPEX or bankability?
- What conditions should be satisfied before signing, completion or release of development funding?

## Step 2 - Build the Evidence Matrix

| Claim                                | Available Evidence                                                                                | Initial Classification                      | Required Action                                                                       |
|--------------------------------------|---------------------------------------------------------------------------------------------------|---------------------------------------------|---------------------------------------------------------------------------------------|
| Land is fully secured.               | Parcel spreadsheet and sample lease; no executed lease set or cadastral reconciliation.           | Unverified claim / gap.                     | Obtain executed agreements, title review and parcel-to-layout reconciliation.         |
| Environmental approval is complete.  | Approval decision includes pre-construction habitat surveys and seasonal restrictions.            | Verified approval with material conditions. | Confirm survey programme, mitigation budget and schedule impact.                      |
| 200 MW grid connection is secured.   | Draft offer is unsigned and references outstanding security payment.                              | High-risk gap.                              | Obtain executed offer, evidence of acceptance, payment status and milestone schedule. |
| 300 MWp layout is feasible.          | Layout extends beyond several listed land parcels and assumes unverified floodplain areas.        | Design inconsistency.                       | Reconcile boundary, flood constraints and usable area; update capacity.               |
| BESS supports four-hour operation.   | Concept SLD and vendor brochure only; no degradation or augmentation model.                       | Preliminary assumption.                     | Define use case, warranty basis, operating profile and augmentation strategy.         |
| Construction can start in 18 months. | Programme excludes seasonal surveys, grid design approvals and long-lead transformer procurement. | High schedule risk.                         | Rebuild integrated programme with dependencies and critical path.                     |

Table 2.10 - Example acquisition-stage evidence matrix.

## Step 3 - Convert Findings into Decision Consequences

The review does not simply list missing documents. It explains why they matter. The unsigned grid offer may affect the existence and timing of the connection right. The land mismatch may reduce installable capacity. Seasonal environmental surveys may move the construction date. The incomplete BESS basis may change CAPEX, warranty assumptions and revenue modelling. These issues may justify conditions precedent, price adjustment, retention, additional exclusivity or withdrawal from the transaction.

## Step 4 - Prepare the Executive Conclusion

### ENGINEERING INSIGHT

The project appears capable of further development, but the supplied information does not currently support the representation that it is fully de-risked or ready for construction. The most material issues are the absence of an executed grid offer, incomplete evidence of land control, inconsistency between the layout and parcel schedule, environmental survey conditions not reflected in the programme, and an immature BESS design basis. Progression may be considered subject to satisfactory closure of the critical information requests, capacity reconciliation and an updated integrated programme and CAPEX model.

## 2.12 Engineering Commentary

The quality of due diligence is determined by the quality of the questions, not by the number of documents reviewed. A data room may contain thousands of pages and still fail to prove a single material claim. Conversely, a small set of current primary documents may provide strong evidence of project rights and maturity.

AI is particularly effective at reducing the mechanical burden of document review. It can extract repeated details, compare tables, identify referenced but missing annexes and maintain consistent wording across a findings register. These capabilities allow the engineering team to spend more time on materiality, causation, mitigation and decision consequences.

The reviewer should also recognise disciplinary boundaries. Grid offer interpretation, land title, environmental legal compliance, tax, contracts and financial modelling may require specialist advice. A technical due diligence report should identify these interfaces clearly rather than provide false certainty outside the reviewer's competence.

## 2.13 Common Mistakes

| Common Mistake                                     | Why It Creates Risk                                                                                |
|----------------------------------------------------|----------------------------------------------------------------------------------------------------|
| Starting without a decision context                | The review becomes a general description instead of a materiality-based assessment.                |
| Reviewing documents in file order                  | Low-value files consume time while controlling evidence is overlooked.                             |
| Treating all sources as equal                      | Vendor claims or presentations may be accepted over permits, contracts or official correspondence. |
| Summarising without cross-checking                 | Conflicts between capacities, dates, boundaries and assumptions remain hidden.                     |
| Confusing absence of evidence with absence of risk | Missing information is incorrectly interpreted as a positive conclusion.                           |
| Using AI without source references                 | Findings cannot be traced, challenged or updated efficiently.                                      |
| Allowing AI to invent standards or citations       | The report appears authoritative but may contain unsupported references.                           |
| Overstating precision at early stage               | Preliminary assumptions are presented as established design facts.                                 |
| Ignoring interfaces between disciplines            | A planning, grid or environmental condition may undermine the engineering programme or economics.  |
| Producing a risk register without actions          | The report identifies exposure but does not support risk reduction or decision-making.             |

*Table 2.11 - Common failure modes in AI-assisted research and due diligence.*

## 2.14 Best Practices

21. Define the decision, materiality threshold, scope and exclusions before reviewing the data room.
22. Create a controlled document inventory and identify superseded, duplicated and missing information.
23. Review primary and high-impact evidence before secondary background material.
24. Require every material finding to include a source reference, confidence level, impact and action.
25. Separate verified facts, third-party claims, reviewer assumptions and information gaps.
26. Cross-check capacities, dates, locations, equipment and programme assumptions across workstreams.
27. Use AI for extraction, comparison and drafting; retain professional control over interpretation and risk acceptance.
28. Escalate matters outside technical competence to legal, environmental, commercial, fire-safety or grid specialists.
29. Maintain a live information-request register and close issues only when adequate evidence has been reviewed.
30. Align the executive summary, detailed findings, risk register and recommendation so that they tell the same technical story.

### BEST PRACTICE

Use the due diligence report as a live decision tool, not a static document. Update findings, evidence status, risk ownership and conditions as the project progresses.

## 2.15 Engineering Review Checklist

| Review Area           | Confirmation Required                                                                                                            |
|-----------------------|----------------------------------------------------------------------------------------------------------------------------------|
| Decision and scope    | Decision context, stage, transaction perimeter, materiality and exclusions are explicit.                                         |
| Document inventory    | Files are listed with date, revision, discipline, status and missing references.                                                 |
| Source hierarchy      | Controlling evidence has been identified and secondary claims are clearly distinguished.                                         |
| Project definition    | Capacity, location, ownership, land, grid and design basis are consistent or discrepancies are reported.                         |
| Workstream coverage   | Land, permitting, environment, surveys, grid, PV, BESS, yield, constructability, cost and programme are addressed as applicable. |
| Evidence traceability | Every material finding has a document, page, drawing, calculation or explicit assumption.                                        |
| Risk classification   | Severity, confidence, impact, mitigation, owner and timing are defined.                                                          |
| Information gaps      | Missing evidence is prioritised and linked to the decision consequence.                                                          |

|                         |                                                                                             |
|-------------------------|---------------------------------------------------------------------------------------------|
| Specialist interfaces   | Legal, contractual, environmental, tax, grid and safety matters are referred appropriately. |
| Executive consistency   | The executive conclusion reflects the detailed findings and risk register.                  |
| Professional validation | Material conclusions have been checked by qualified reviewers before issue.                 |

Table 2.12 - Minimum checks for an AI-assisted technical due diligence deliverable.

### CONSULTANT'S QUICK VALIDATION QUESTIONS

Ask: What decision does this finding affect? What is the controlling evidence? Is the source current and applicable? What uncertainty remains? What happens if the assumption is wrong? What action would reduce the risk, by when, and who owns it?

## 2.16 Prompt Toolkit

The following prompt levels can be adapted to the project stage and decision. Source documents should be supplied through approved, secure tools in accordance with organisational policies.

| Level        | Best Used For                                                                | Typical Output                                                                     |
|--------------|------------------------------------------------------------------------------|------------------------------------------------------------------------------------|
| Quick        | Single-document summaries, preliminary questions and desktop screening.      | Concise summary, risk list or information request.                                 |
| Professional | Multi-document project reviews and structured development-team assessments.  | Findings by workstream, gaps, risks and action plan.                               |
| Expert       | Acquisition, financing, Owner's Engineer and investment-grade due diligence. | Traceable report with red flags, evidence register, conditions and recommendation. |

Table 2.13 - Prompt levels for research and due diligence tasks.

### Level 1 - Quick Research Prompt

#### QUICK PROMPT

Act as a Senior Solar Project Development Engineer. Review the supplied document and provide: (1) purpose and scope; (2) key technical findings; (3) assumptions and limitations; (4) potential project risks; (5) missing information; and (6) five questions for the project team. Do not add facts that are not supported by the document.



## Level 2 - Professional Due Diligence Prompt

### PROFESSIONAL PROMPT

You are acting as the Project Development Engineer reviewing a utility-scale Solar PV and BESS opportunity. Using the supplied land, planning, environmental, grid, design, energy-yield, CAPEX and programme information, prepare a structured assessment by workstream. Identify inconsistencies, material risks, evidence gaps, required specialist reviews and prioritised next actions. For every material conclusion, cite the source and state whether it is a verified fact, third-party claim, reviewer assumption or information gap.

## Level 3 - Expert Technical Advisor Prompt

### EXPERT PROMPT

You are the Lead Technical Advisor supporting an investment decision for the acquisition or financing of the described utility-scale Solar PV and BESS project. Apply a materiality-based review across project rights, land, permitting, environment, surveys, grid connection, PV design, BESS design and safety, energy yield, constructability, CAPEX, OPEX, programme, procurement and contractual interfaces. Produce an Executive Summary, transaction red flags, detailed findings, evidence-confidence matrix, technical risk register, information request list, recommended conditions precedent and a clear proceed / proceed with conditions / do not proceed recommendation. Preserve source traceability, distinguish facts from assumptions, and identify all matters requiring specialist legal, environmental, grid, commercial or fire-safety advice.

## 2.17 Recommended Engineering and Research References

Authoritative research should begin with the primary sources applicable to the project jurisdiction and technology. The following categories provide a suitable reference framework:

- National and regional planning legislation, permitting procedures and official authority guidance.
- Transmission and distribution system operator grid codes, connection procedures, technical requirements and formal correspondence.
- Environmental authority decisions, protected-area databases, water and flood authorities, archaeological records and required survey guidance.
- Land registry, cadastral information, executed land agreements and rights-of-way documentation.
- Applicable IEC, IEEE, NFPA and local electrical, fire-safety, civil and construction requirements, as confirmed for the jurisdiction.
- IEA PVPS, NREL, Fraunhofer ISE and other recognised technical publications relevant to PV performance and project risk.
- Manufacturer datasheets, warranty documents, certification reports and project-specific design calculations.
- Controlled project documents, including design basis, drawings, energy models, schedules, cost estimates, registers and approved meeting records.

Standards, regulations and grid requirements should be checked for current edition, legal status and project applicability before being relied upon.

## 2.18 Chapter Summary

Research and technical due diligence convert incomplete project information into a defensible view of viability, maturity and risk. The process begins with a decision, translates that decision into questions, identifies the evidence required and applies a clear hierarchy of sources.

Artificial Intelligence can dramatically reduce the time required to inventory documents, extract findings, compare repeated statements, identify gaps and draft consistent reports. Its contribution is strongest when the engineering team controls materiality, evidence classification, source traceability and final interpretation.

A professional due diligence output does not merely describe the project. It explains which claims are proven, which assumptions remain, which risks could affect value and what actions are required before the next decision. This methodology will support the later chapters on site assessment, permitting, grid connection, technology selection, design review, project economics and execution readiness.

## 2.19 Key Takeaways

- Research should be driven by the project decision and the evidence needed to support it.
- Primary and controlled project sources should govern over presentations, commentary and unverified statements.
- Technical due diligence must integrate multiple disciplines and identify interfaces between them.
- AI is highly effective for document inventory, extraction, comparison, gap analysis and report drafting.
- Verified facts, third-party claims, assumptions and information gaps must be classified separately.
- Risk severity and evidence confidence are different dimensions and should both be reported.
- Every material conclusion should be traceable to a source and linked to a decision consequence and action.
- Professional validation remains mandatory before findings are issued or relied upon.

## Chapter 2 Completion Checklist

- I can define a materiality-based research and due diligence scope for a Solar PV or BESS project.
- I can identify controlling evidence and distinguish it from unverified project claims.
- I can organise a data room and findings register with appropriate source traceability.
- I can use AI to extract, compare and structure information without delegating engineering judgement.
- I can classify risks, confidence and information gaps in a decision-ready format.
- I can prepare quick, professional and expert prompts for research and due diligence tasks.
- I can review an AI-assisted report before it is used for investment, design or project approval.

## Looking Ahead - Chapter 3

The next chapter applies the same evidence-led methodology to site identification and preliminary feasibility screening. It will show how AI can support location assessment, constraint mapping, land suitability, resource screening and early fatal-flaw identification before detailed development work begins.

## CHAPTER 3

# AI-Assisted Site Identification & Preliminary Feasibility Screening for Utility-Scale Solar and BESS Projects

---

*From geographic opportunity to an evidence-based project shortlist*

*Constraint mapping, site scoring, fatal-flaw identification and development prioritisation*

Edition v1.1 | Volume 1

*"A promising site is not simply land with strong irradiance. It is land where resource, rights, grid, permits and constructability can converge into a financeable project."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a repeatable method for identifying, screening and ranking candidate locations for utility-scale Solar PV and co-located BESS projects. It combines engineering judgement, geospatial evidence and AI-assisted analysis to reduce large search areas into a defensible shortlist for land engagement, site visits and detailed development studies.

| Element              | Purpose                                                                                                               |
|----------------------|-----------------------------------------------------------------------------------------------------------------------|
| Screening brief      | Defines project capacity, technology, market, land need, grid strategy and exclusion criteria.                        |
| Spatial evidence     | Organises authoritative and indicative datasets for land, terrain, hydrology, environment, planning, access and grid. |
| Screening funnel     | Moves from regional opportunity mapping to parcel-level review and site prioritisation.                               |
| Constraint framework | Separates fatal exclusions, major risks, manageable constraints and development opportunities.                        |
| Scoring model        | Ranks sites transparently while preserving uncertainty and preventing false precision.                                |
| AI workflow          | Accelerates data inventory, comparison, narrative assessment, risk registers and decision reporting.                  |
| Prompt toolkit       | Provides reusable prompts for desktop screening, site comparison and expert shortlisting.                             |

*Table 3.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Translate a development strategy into measurable site-screening criteria for Solar PV and BESS projects.
- Apply a staged screening funnel from regional opportunity mapping to parcel-level feasibility review.
- Distinguish authoritative project evidence from indicative desktop datasets and automated interpretations.
- Assess land geometry, resource, terrain, hydrology, planning, environment, grid, access and BESS-specific constraints.
- Create a transparent site-scoring model that includes uncertainty, confidence and materiality.
- Use AI to structure multi-source evidence, compare candidate sites and prepare a defensible shortlist.
- Recognise when desktop screening is insufficient and specialist surveys, authority engagement or site visits are required.

## 3.1 Introduction

Site selection is one of the highest-leverage activities in utility-scale renewable-energy development. A weak location can absorb years of engineering, permitting and commercial effort before its limitations become unavoidable. A well-selected location does not eliminate risk, but it improves the probability that land, grid, permits, constructability and project economics can mature together.

Early site identification usually begins with incomplete and uneven information. Regional solar-resource maps may be available, but parcel rights are unknown. A substation may appear close on a map, but spare capacity, routing rights and reinforcement scope remain uncertain. Terrain may look flat in satellite imagery while local drainage, rock, erosion or micro-topography create substantial civil cost. Public environmental layers may identify protected areas, but they may not capture seasonal species, cumulative impacts or local planning policy.

Artificial Intelligence can accelerate the screening process by organising datasets, extracting constraints, comparing sites, drafting narratives and maintaining consistent scoring. It can also help engineers define the questions that should be answered before landowners are approached or budgets are committed. The technology is most valuable when used inside a disciplined geospatial and engineering workflow rather than as a substitute for GIS analysis, surveys or authority consultation.

The objective of preliminary feasibility screening is not to prove that a project can be built. It is to eliminate unsuitable opportunities quickly, identify the principal uncertainties in promising opportunities and direct limited development resources toward the sites with the best risk-adjusted potential.

### ENGINEERING INSIGHT

Desktop screening is a prioritisation tool, not a development consent, grid confirmation or design approval. Its purpose is to decide where deeper investigation is justified.

## 3.2 The Purpose of Preliminary Site Screening

A professional screening process should answer a decision question. Examples include whether to enter a new region, whether to contact a landowner, which of several parcels should be prioritised, whether a site visit is justified, or whether an acquisition opportunity should progress to technical due diligence.

| Decision Stage | Screening Objective                                                                                                | Typical Output                                    |
|----------------|--------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Market entry   | Identify regions where resource, policy, grid development and land availability may support the target technology. | Regional opportunity map and strategic watchlist. |
| Origination    | Identify candidate land areas and exclude obvious constraints before land engagement.                              | Candidate-site longlist with initial red flags.   |

| Decision Stage        | Screening Objective                                                                                        | Typical Output                                   |
|-----------------------|------------------------------------------------------------------------------------------------------------|--------------------------------------------------|
| Land engagement       | Assess whether parcel geometry, access and apparent constraints justify exclusivity or option discussions. | Land opportunity note and information request.   |
| Site prioritisation   | Compare multiple candidates using common criteria and evidence confidence.                                 | Ranked shortlist and development recommendation. |
| Acquisition screening | Test whether the claimed site basis is credible before full due diligence begins.                          | Preliminary feasibility and fatal-flaw report.   |

Table 3.2 - Site-screening objectives across early development decisions.

#### **BEST PRACTICE**

State the decision and screening depth at the start. A regional search, parcel review and acquisition screen require different datasets, time budgets and confidence levels.

## 3.3 The Site-Screening Funnel

Efficient screening narrows the search area in stages. Each stage removes unsuitable locations or increases confidence in the remaining candidates. Moving directly to detailed parcel analysis across a large region wastes effort and can create inconsistent reviews.



Figure 3.1 - The site-screening funnel from strategy to shortlist.

### Stage 1 - Define the Development Strategy

Set the target market, technology, capacity, commercial model, grid philosophy, land-control strategy and target development timeline. The strategy determines what constitutes a suitable site.

### Stage 2 - Regional Opportunity Mapping

Review solar resource, transmission infrastructure, market rules, terrain patterns, planning context, protected areas, population density and broad land availability.

### Stage 3 - Apply Hard Exclusions

Remove areas that conflict with legal, physical or strategic criteria, such as prohibited planning zones, major water bodies, incompatible land use, extreme slopes or insufficient contiguous area.

### Stage 4 - Identify Candidate Areas

Locate zones where resource, land, terrain, access and grid indicators appear broadly compatible with the project concept.

## Stage 5 - Conduct Parcel-Level Review

Assess cadastral boundaries, parcel geometry, ownership pattern, easements, local access, topography, drainage, visible obstructions and neighbouring receptors.

## Stage 6 - Rank and Prioritise

Score candidates using transparent criteria, risk categories and evidence confidence. Preserve narrative judgement alongside numerical ranking.

## Stage 7 - Validate in the Field

Use site visits, landowner information, authority discussions, surveys and specialist studies to confirm or overturn desktop assumptions.

# 3.4 Define the Project Before Screening the Site

A site cannot be judged without a project definition. The same parcel may be suitable for a 40 MW fixed-tilt project but unsuitable for a 300 MW tracker project with a large substation and four-hour BESS. Screening criteria should therefore be derived from a written development brief.

| Project Parameter                   | Why It Matters to Site Screening                                                                            |
|-------------------------------------|-------------------------------------------------------------------------------------------------------------|
| Target export capacity              | Influences grid voltage, substation scale, land need, cable corridors and project economics.                |
| PV DC capacity and DC/AC philosophy | Affects developable area, equipment density and clipping strategy.                                          |
| Mounting system                     | Changes slope tolerance, grading exposure, row spacing, wind design and land efficiency.                    |
| BESS power, energy and duration     | Determines compound area, safety separation, auxiliary load, grid import/export and logistics requirements. |
| Grid connection strategy            | Defines acceptable distance to candidate substations or transmission corridors and route complexity.        |
| Target commercial operation date    | Makes survey seasonality, permitting lead time and grid milestones material to selection.                   |
| Land-control model                  | Affects acceptable ownership fragmentation, lease cost, negotiation complexity and security requirements.   |
| Design and investment criteria      | Defines minimum yield, maximum civil complexity, environmental tolerance and budget thresholds.             |

*Table 3.3 - Project definition inputs required before screening begins.*

Indicative land-density assumptions may be used for early screening, but they should be treated as ranges rather than fixed rules. Land demand depends on module dimensions, mounting geometry, terrain, setbacks, environmental buffers, roads, drainage, electrical compounds, irregular boundaries, BESS area and future design optimisation.

**COMMON MISTAKE**

A simple hectares-per-megawatt assumption can be useful for regional screening, but it should not be used to confirm buildable capacity. Parcel geometry and exclusions often matter more than gross land area.

## 3.5 Spatial Data and Evidence Hierarchy

Site screening combines multiple geospatial and documentary sources. The review should record source, date, scale, resolution, jurisdiction, limitations and whether the dataset is authoritative or indicative. Apparent precision on a map does not guarantee legal or engineering accuracy.

| Evidence Class                        | Examples                                                                                                                          | Professional Treatment                                                                            |
|---------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|
| Authoritative legal or authority data | Cadastral records, planning designations, permit portals, official flood maps, protected-area registers and utility publications. | Use as the primary desktop evidence while confirming currency, legal status and spatial accuracy. |
| Project-specific controlled data      | Boundary surveys, topographic surveys, geotechnical reports, grid correspondence and approved drawings.                           | Prioritise over public estimates when revision-controlled and applicable to the candidate site.   |
| Technical reference datasets          | Digital elevation models, satellite imagery, resource databases, land-cover maps and public infrastructure layers.                | Use for screening and comparison; validate material matters through project-specific surveys.     |
| Commercial or third-party platforms   | Proprietary GIS portals, market databases and constraint aggregators.                                                             | Review methodology, update cycle, licence conditions and source provenance.                       |
| AI-derived interpretation             | Summaries, image descriptions, dataset comparisons and automatically generated risk narratives.                                   | Treat as draft analysis requiring traceability and engineering verification.                      |

*Table 3.4 - Evidence classes used in preliminary site screening.*

Coordinate reference systems and map alignment should be checked whenever layers are combined. Boundary shifts, raster resolution, generalised lines and outdated imagery can create false overlaps or false clearances. Material buffers and setbacks should be measured in GIS using the appropriate local projection rather than estimated visually.

## 3.6 Land Suitability, Geometry and Control

Gross area is only the starting point. A technically useful site must provide sufficient contiguous and developable land after exclusions, setbacks, topographic constraints, environmental buffers, roads, drainage, electrical compounds and BESS safety areas are considered.

| Land Factor | Questions for Preliminary Screening                                                                          |
|-------------|--------------------------------------------------------------------------------------------------------------|
| Contiguity  | Is the land continuous, or divided by roads, waterways, third-party parcels, utilities or incompatible uses? |



| Land Factor                | Questions for Preliminary Screening                                                                                                     |
|----------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|
| Geometry                   | Does the shape support efficient rows, inverter blocks, roads and cable routing, or create excessive edge losses and fragmented fields? |
| Ownership                  | How many owners and parcels are involved? Are there unknown rights, tenants, mortgages or competing options?                            |
| Access rights              | Is legal and physical access available for surveys, construction traffic, operations and emergency response?                            |
| Easements and encumbrances | Are there pipelines, overhead lines, rights-of-way, irrigation infrastructure or development restrictions?                              |
| Expansion potential        | Can adjacent land support later capacity, BESS augmentation, substation expansion or route alternatives?                                |
| Neighbouring uses          | Could residences, aviation, agriculture, industry or future development create conflicts?                                               |

*Table 3.5 - Land and parcel screening considerations.*

Landowner engagement should not be based solely on an attractive map image. Before commercial terms are advanced, the project team should confirm the correct parcels, indicative usable area, access route, ownership structure and the principal conditions that must be resolved during exclusivity or option periods.

## 3.7 Solar Resource and Climate Screening

Solar resource influences expected generation and project economics, but it should be considered together with temperature, wind, precipitation, snow, hail, soiling, humidity and extreme-weather exposure. A high annual irradiation value does not automatically make a location superior if other conditions increase cost, losses or risk.

| Parameter                            | Screening Relevance                                                                                 |
|--------------------------------------|-----------------------------------------------------------------------------------------------------|
| GHI and POA potential                | Supports regional energy comparison and early production estimates.                                 |
| Temperature                          | Influences module output, inverter loading, cable ratings, BESS thermal management and degradation. |
| Wind and gusts                       | Affects tracker stow strategy, structural design, construction safety and insurance exposure.       |
| Precipitation and drainage intensity | Influences erosion, road design, drainage structures and construction access.                       |
| Snow, hail and icing                 | May affect technology selection, structural loads, damage risk and O&M strategy.                    |
| Soiling and dust                     | Influences expected losses, cleaning demand, water strategy and OPEX.                               |

| Parameter                       | Screening Relevance                                                                   |
|---------------------------------|---------------------------------------------------------------------------------------|
| Corrosive or saline environment | Affects material selection, coatings, connectors, structures and warranty conditions. |

Table 3.6 - Resource and climate parameters for early screening.

#### ENGINEERING INSIGHT

Resource should be assessed as risk-adjusted energy potential, not as a single annual irradiation number. Climate conditions can affect design, availability, degradation, OPEX and insurability.

## 3.8 Terrain, Earthworks and Civil Complexity

Terrain is a principal driver of layout efficiency, grading, foundation design, drainage, access and construction productivity. Desktop elevation data can identify broad slope patterns, but its resolution may not capture local channels, terraces, embankments, rock outcrops or abrupt changes that influence the design.

| Terrain Indicator                                 | Potential Consequence                                                                   |
|---------------------------------------------------|-----------------------------------------------------------------------------------------|
| Average and local slope                           | Tracker tolerance, grading, pile reveal, row spacing, access-road gradients and safety. |
| Slope orientation and variability                 | Table geometry, shading, production asymmetry and block fragmentation.                  |
| Elevation range                                   | Cut-and-fill balance, cable gradients, drainage energy and construction logistics.      |
| Visible rock or shallow soil                      | Pile refusal, pre-drilling, foundation alternatives, equipment wear and cost.           |
| Terraces, channels and erosion                    | Reduced contiguous area, drainage crossings, scour protection and maintenance exposure. |
| Existing agricultural or industrial modifications | Unknown fill, buried services, contaminated land or demolition requirements.            |

Table 3.7 - Terrain indicators and potential civil consequences.

Slope thresholds should reflect the mounting system, structural supplier limits, design philosophy, expected grading tolerance and geotechnical conditions. A single universal slope exclusion is rarely appropriate. The screening report should distinguish hard exclusions from areas that remain technically feasible but may carry higher CAPEX or yield uncertainty.

## 3.9 Hydrology, Flooding and Water Constraints

Water can create both legal and engineering constraints. Floodplains, drainage channels, wetlands, watercourses, irrigation networks and groundwater conditions may reduce buildable

area or require setbacks, crossings, permits and specialised design. Historic satellite imagery may reveal seasonal water patterns that are not visible in a single recent image.

- Review official flood-hazard mapping and note the return periods, modelling basis and map limitations.
- Identify natural drainage paths, catchments, low points, wetlands, reservoirs and watercourse crossings.
- Consider upstream development and off-site runoff rather than evaluating only rainfall falling on the parcel.
- Assess whether roads, tracker rows, fences or cable trenches could obstruct drainage or concentrate flow.
- Identify water rights, abstraction constraints and cleaning-water implications where relevant.
- Escalate uncertain flood and drainage issues for hydrological study before land value or capacity is fixed.

#### COMMON MISTAKE

Treating areas outside a mapped flood zone as automatically flood-free. Public maps may omit local drainage, small catchments, future climate effects or project-induced changes in runoff.

## 3.10 Environmental, Social and Planning Constraints

Environmental and planning screening should identify both formal exclusions and issues that could affect survey duration, design, stakeholder acceptance or consent risk. Many matters cannot be resolved through mapping alone, but early identification improves site selection and programme realism.

| Constraint Category               | Examples of Screening Questions                                                                                   |
|-----------------------------------|-------------------------------------------------------------------------------------------------------------------|
| Protected areas and habitats      | Is the site inside or near designated areas, priority habitats, ecological corridors or sensitive water features? |
| Species and seasonal surveys      | Could breeding, migration, nesting or vegetation seasons delay the evidence programme?                            |
| Cultural heritage and archaeology | Are there designated assets, known remains, historic landscapes or high archaeological sensitivity?               |
| Landscape and visual impact       | Is the site visible from settlements, roads, viewpoints or protected landscapes?                                  |
| Residential receptors             | Could noise, construction traffic, glint and glare, fire concerns or visual change create opposition?             |
| Aviation and communications       | Are there airports, radar, military facilities, telecommunications links or safeguarding zones?                   |
| Agricultural and soil policy      | Are there restrictions on high-value agricultural land, irrigation areas, forestry or land conversion?            |
| Planning policy                   | Does the applicable policy support renewable development at the proposed scale and in the proposed location?      |

*Table 3.8 - Environmental, social and planning screening categories.*

Buffers shown during desktop screening should be treated as preliminary unless they are defined by applicable legislation, authority guidance or project-specific specialist advice. Avoid converting an indicative good-

practice distance into a legal requirement, or assuming that compliance with a minimum distance guarantees acceptability.

### 3.11 Grid Proximity and Connection Realism

Grid infrastructure is a critical selection factor, but map proximity alone is not a connection strategy. A nearby substation may have no available capacity, may operate at an unsuitable voltage, may require major reinforcement or may be separated from the site by difficult routing and land-right constraints.

| Grid Screening Factor                         | Why It Matters                                                                               |
|-----------------------------------------------|----------------------------------------------------------------------------------------------|
| Candidate point of interconnection            | Provides the preliminary basis for voltage, export capacity, route and application strategy. |
| Electrical distance and route                 | Influences losses, cable or line cost, land rights, crossings, permitting and programme.     |
| Substation and network capacity               | Determines whether the apparent connection is technically and commercially credible.         |
| Network reinforcements                        | Can dominate CAPEX, programme and delivery risk.                                             |
| Connection process and queue                  | Influences application timing, securities, studies, milestones and competitive position.     |
| Curtailment and system constraints            | Affects revenue, storage value, operating strategy and bankability.                          |
| Reactive power and grid-code obligations      | May require additional equipment, land and design allowances.                                |
| Private-wire or shared infrastructure options | Can create opportunities but add contractual and interface complexity.                       |

*Table 3.9 - Grid connection questions for preliminary site screening.*

#### COMMON MISTAKE

Distance to the nearest substation is an indicator, not evidence of connection availability. Official utility information, system studies and formal correspondence are required before a connection assumption can support an investment decision.

### 3.12 Access, Logistics and Early Constructability

Construction access and logistics can materially differentiate sites with otherwise similar resource and grid characteristics. Desktop review should identify the probable route from major roads or ports, local bridge and road constraints, settlement interfaces, steep sections, overhead obstructions and the availability of suitable entrances.

- Review the route for transformers, BESS containers, cranes, piling rigs, delivery vehicles and emergency access.

- Identify narrow roads, weak bridges, tight bends, height restrictions, rail crossings and seasonal access limitations.
- Check whether the proposed entrance requires third-party land, visibility improvements or authority approval.
- Consider internal haul roads, laydown areas, temporary compounds and separation between construction and public traffic.
- Identify likely cable-route, drainage, watercourse, pipeline and utility crossings.
- Assess proximity to labour, accommodation, services, ports, quarries, concrete supply and waste facilities where material.

### 3.13 Site-Screening Considerations for Co-Located BESS

A co-located BESS is not simply an additional equipment block. It can change land needs, connection philosophy, fire and emergency planning, auxiliary power, drainage, noise, visual impact, hazardous-material controls, access and stakeholder perception.

#### STANDARDS REFERENCE

BESS fire, safety and emergency-response requirements are typically assessed against system-level standards such as NFPA 855 (installation of stationary energy storage systems), UL 9540A (thermal-runaway fire-propagation test method) and IEC 62933-5-2 (safety requirements for electrical energy storage systems). Applicable editions, scope and any local amendments must be confirmed for the project jurisdiction, authority having jurisdiction and insurer requirements; this handbook does not state binding technical thresholds.

| BESS Site Factor            | Screening Consideration                                                                                                                                          |
|-----------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Compound area and geometry  | Allow for containers or enclosures, inverters or PCS, transformers, roads, clearances, augmentation and maintenance.                                             |
| Safety separation           | Preserve preliminary distances to boundaries, occupied buildings, vegetation, critical equipment and emergency routes, subject to project-specific requirements. |
| Fire and emergency response | Review access, turning, water strategy, isolation, incident containment and local responder capability.                                                          |
| Noise                       | Consider HVAC, transformers and PCS relative to sensitive receptors and night-time limits.                                                                       |
| Flood and drainage          | Avoid low points and preserve safe equipment levels, containment and stormwater management.                                                                      |
| Grid import and export      | Confirm whether charging, auxiliary load and operating mode are compatible with the connection concept and market strategy.                                      |
| Thermal environment         | High ambient temperature, dust, humidity or corrosivity may influence design, degradation and auxiliary consumption.                                             |
| Future augmentation         | Reserve land, electrical capacity, access and fire separation for replacement or additional units.                                                               |

Table 3.10 - Additional site-screening factors for co-located BESS.

**BEST PRACTICE**

Reserve a realistic BESS envelope during site screening even when the final supplier is unknown. Under-allocating the compound can constrain technology choice and later design development.

## 3.14 The AI-Assisted Site-Screening Workflow

AI can support the process before, during and after GIS analysis. It is particularly effective for defining criteria, inventorying sources, standardising site narratives, comparing candidates and converting findings into risk and action registers.




Figure 3.2 - Controlled AI-assisted site-screening workflow.

### Step 1 - Prepare the Screening Brief

Define capacity, technology, land need, target region, grid concept, commercial model, schedule, exclusions and decision criteria.

### Step 2 - Build the Data and Source Register

List each dataset, owner, date, resolution, coordinate system, coverage, legal status and known limitations.

### Step 3 - Create the Constraint Map

Use GIS to combine land, terrain, hydrology, environment, planning, access and infrastructure layers. Separate hard exclusions from risk indicators.

### Step 4 - Generate Candidate Areas

Identify zones with sufficient apparent area and acceptable high-level constraints. Record why each area was selected.

### Step 5 - Conduct Parcel-Level Review

Review boundaries, geometry, visible features, ownership pattern, receptors, routes and preliminary capacity.

### Step 6 - Use AI for Structured Comparison

Provide the evidence register and site findings to AI using a fixed template. Require facts, assumptions, gaps and confidence to be separated.

### Step 7 - Perform Engineering and Specialist Review

Challenge scores, inspect map outputs, verify material claims and identify specialist work required.

## Step 8 - Plan Field Validation

Convert uncertainties into a site-visit checklist, landowner questions, survey scope and authority engagement plan.

## Step 9 - Issue the Shortlist Recommendation

Present the ranking, decisive risks, evidence confidence, conditions for progression and next actions.

### 3.15 Site Scoring, Weighting and Uncertainty

Scoring can improve consistency across many candidate sites, but it can also create false confidence. A high total score should not override a fatal flaw, and small numerical differences should not be treated as meaningful when the underlying evidence is uncertain.

| Category                 | Example Weight | Example Measures                                                                                 |
|--------------------------|----------------|--------------------------------------------------------------------------------------------------|
| Land and geometry        | 20%            | Contiguous usable area, ownership complexity, access rights and expansion potential.             |
| Grid                     | 20%            | Connection route, voltage suitability, network evidence, reinforcement exposure and curtailment. |
| Planning and environment | 20%            | Policy fit, protected areas, receptors, survey burden and consent complexity.                    |
| Terrain and civil        | 15%            | Slope, grading, drainage, geotechnical indicators and constructability.                          |
| Resource and climate     | 10%            | Irradiation, temperature, soiling and extreme-weather exposure.                                  |
| Access and logistics     | 5%             | External route, delivery constraints, construction access and local services.                    |
| Commercial and programme | 10%            | Land cost, negotiation complexity, survey duration and target schedule alignment.                |

*Table 3.11 - Illustrative weighted site-screening model. Weights must be adapted to the development strategy.*

Each category should include both a performance score and an evidence-confidence rating. A site with an attractive grid score based only on map proximity should not rank the same as a site supported by formal utility information. The report should also identify veto criteria that automatically prevent progression until resolved.

| Confidence Level | Meaning                                                                                  | Treatment                                            |
|------------------|------------------------------------------------------------------------------------------|------------------------------------------------------|
| High             | Current authoritative or project-specific evidence directly supports the finding.        | Use in the decision, subject to normal verification. |
| Medium           | Multiple indicative sources are consistent, but project-specific confirmation is absent. | Use for ranking with an explicit validation action.  |

| Confidence Level | Meaning                                                                             | Treatment                                                           |
|------------------|-------------------------------------------------------------------------------------|---------------------------------------------------------------------|
| Low              | The conclusion relies on incomplete, old, low-resolution or unverified information. | Do not rely on it for irreversible commitments.                     |
| Unknown          | No credible evidence is available.                                                  | Record as an information gap and define the required investigation. |

Table 3.12 - Evidence-confidence levels for site screening.

### 3.16 Fatal Flaws, Red Flags and Manageable Constraints

The screening report should classify constraints according to consequence and resolvability. This prevents the team from treating every mapped overlap as fatal or, conversely, minimising issues that could stop the project.

| Classification      | Definition                                                                                                                                        | Typical Response                                                              |
|---------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| Fatal flaw          | A constraint that is legally prohibited, physically impracticable, strategically unacceptable or unlikely to be resolved within the project case. | Reject the site or redesign the opportunity before further expenditure.       |
| Major red flag      | A material issue that could prevent development or materially alter capacity, cost or schedule, but requires investigation before a conclusion.   | Pause commitment, obtain authoritative evidence and define a resolution plan. |
| Moderate constraint | A manageable issue likely to require design allowance, mitigation, survey, permit or commercial provision.                                        | Carry into the risk register, budget and programme.                           |
| Minor constraint    | A limited issue with low expected impact when addressed through normal design or development practice.                                            | Record and monitor.                                                           |
| Opportunity         | A site feature that could improve yield, grid strategy, phasing, land efficiency, logistics or commercial value.                                  | Protect the opportunity and test it during development.                       |

Table 3.13 - Constraint and opportunity classification.

Fatal-flaw criteria should be agreed before sites are scored. Examples may include insufficient contiguous land, incompatible planning designation, unavoidable protected habitat, no credible access, extreme terrain, unresolvable land-control fragmentation or a grid route that is commercially disproportionate. Whether a matter is truly fatal depends on jurisdiction, project strategy, mitigation potential and evidence quality.



## 3.17 Worked Example - Shortlisting Sites for a 300 MWac Solar PV and 150 MW / 300 MWh BESS Project

### PROJECT SCENARIO

A developer is evaluating three candidate sites in a high-resource inland region. The target is approximately 390 MWp of single-axis-tracker PV, exporting 300 MWac, with a co-located 150 MW / 300 MWh BESS. The target commercial operation date is five years away. No formal grid offer or detailed surveys exist at screening stage.

| Criterion                | Site A - Mesa                                  | Site B - Valley                              | Site C - Ridge                                        |
|--------------------------|------------------------------------------------|----------------------------------------------|-------------------------------------------------------|
| Gross land               | 1,020 ha across 9 parcels                      | 890 ha across 4 parcels                      | 1,140 ha across 17 parcels                            |
| Indicative usable area   | High, regular geometry                         | Medium; drainage corridors reduce continuity | Medium; slope and fragmented ridges                   |
| Terrain                  | Mostly gentle with isolated undulations        | Flat lowland with visible channels           | Variable, including steep local sections              |
| Environmental indicators | Near a migration corridor; surveys required    | Wetland and floodplain interfaces            | Lower habitat sensitivity but high visual exposure    |
| Grid indicator           | 18 km to a suitable-voltage substation         | 7 km to a substation with uncertain capacity | 25 km route with a major river crossing               |
| Access                   | Good regional road and two potential entrances | Good road but bridge load capacity unknown   | Mountain road with several tight bends                |
| BESS suitability         | Two possible compounds away from receptors     | Compound area close to flood-risk zone       | Good compound area but difficult transformer delivery |

Table 3.14 - Preliminary comparison of the three candidate sites.

The engineering team first applies the agreed exclusions. No site is immediately rejected, but Site B receives a major red flag because the apparent buildable area overlaps mapped flood-risk and wetland features. Site C remains technically possible but carries high civil, logistics and grid-route exposure. Site A has the most balanced geometry and constructability profile, although ecological survey requirements and the longer grid route remain material.

| Category                 | Weight | Site A | Site B | Site C |
|--------------------------|--------|--------|--------|--------|
| Land and geometry        | 20     | 17     | 13     | 12     |
| Grid                     | 20     | 13     | 15     | 8      |
| Planning and environment | 20     | 13     | 8      | 14     |
| Terrain and civil        | 15     | 13     | 9      | 6      |
| Resource and climate     | 10     | 9      | 9      | 9      |

| Category                 | Weight | Site A | Site B     | Site C |
|--------------------------|--------|--------|------------|--------|
| Access and logistics     | 5      | 5      | 4          | 2      |
| Commercial and programme | 10     | 7      | 7          | 5      |
| Total indicative score   | 100    | 77     | 65         | 56     |
| Evidence confidence      | -      | Medium | Low-Medium | Medium |

Table 3.15 - Illustrative site-scoring output. Scores are preliminary and should not be treated as a design or investment approval.

### BEST PRACTICE

Progress Site A as the preferred candidate, subject to early ecological review, grid-routing options and landowner confirmation. Retain Site B as a conditional alternative only if hydrology and wetland constraints can be resolved without materially reducing capacity. Do not prioritise Site C unless strategic grid information or land economics justify its higher civil and logistics risk.

The immediate next actions are to: confirm the cadastral and ownership schedule for Site A; obtain current ecological records and define seasonal survey requirements; inspect the potential line route and crossing constraints; request preliminary utility engagement; complete a site visit; and prepare a concept layout using a topographic dataset appropriate for capacity screening. Site B should receive a focused flood and wetland desktop study before further land expenditure.

## 3.18 Common Mistakes

| Common Mistake                              | Why It Creates Risk                                                        | Better Practice                                                                     |
|---------------------------------------------|----------------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| Selecting on irradiation alone              | Ignores grid, permits, land control, civil cost and development programme. | Compare risk-adjusted energy potential across all material workstreams.             |
| Using gross area as buildable area          | Overstates capacity and ignores exclusions, geometry and infrastructure.   | Estimate usable area after mapped constraints and preserve uncertainty.             |
| Treating map proximity as grid availability | Can create an unsupported connection and value assumption.                 | Separate physical proximity from network capacity and formal connection evidence.   |
| Applying universal buffers                  | May invent legal constraints or miss jurisdiction-specific requirements.   | Identify the source and status of each setback or buffer.                           |
| Overweighting numerical scores              | Creates false precision and can hide fatal flaws.                          | Use scores with narrative judgement, confidence and veto criteria.                  |
| Ignoring dataset age and resolution         | Outdated or coarse data may misrepresent current site conditions.          | Maintain a source register and validate material issues through current evidence.   |
| Skipping ownership and access complexity    | A technically attractive site may be commercially uncontrollable.          | Review parcel fragmentation, rights and route dependencies early.                   |
| Relying on AI image interpretation          | Automated descriptions may miss features or misclassify land use.          | Use AI as a review aid and verify through GIS, source imagery and field inspection. |

Table 3.16 - Common site-screening errors and controls.

## 3.19 Best Practices

- Begin with a written project and screening brief rather than browsing maps without decision criteria.
- Separate hard exclusions, risk indicators, opportunities and information gaps into different GIS layers and registers.
- Record source provenance, date, scale, resolution, coordinate system and known limitations.
- Use the same scoring definitions across all sites and document every manual adjustment.
- Score evidence confidence separately from apparent site performance.
- Preserve alternative access, grid-route and compound options until authoritative information is available.
- Convert desktop uncertainties into a focused site-visit and survey plan.
- Issue recommendations with conditions, not just rankings, so the development team understands what must be proven next.
- Re-screen the site whenever project capacity, technology, boundary, grid strategy or applicable constraints change.

### BEST PRACTICE

The best screening report is auditable. Another engineer should be able to understand the criteria, reproduce the logic, locate the evidence and see why one site was prioritised over another.

## 3.20 Engineering Review Checklist

| Review Area              | Minimum Check                                                                                  |
|--------------------------|------------------------------------------------------------------------------------------------|
| Project definition       | Capacity, technology, BESS concept, grid strategy, land need and target programme are stated.  |
| Decision and scope       | The screening purpose, depth, exclusions and materiality thresholds are clear.                 |
| Spatial controls         | Coordinate systems, boundary alignment, layer dates, scale and resolution have been checked.   |
| Land                     | Usable area, geometry, ownership pattern, access and encumbrances have been considered.        |
| Resource and climate     | Energy potential and relevant climate risks have been reviewed as ranges.                      |
| Terrain and hydrology    | Slope, drainage, flood, erosion and geotechnical uncertainty are reflected in the assessment.  |
| Environment and planning | Protected areas, receptors, surveys, policy and consent complexity are addressed.              |
| Grid                     | Connection proximity is distinguished from capacity, rights, route and reinforcement evidence. |

| Review Area    | Minimum Check                                                                                        |
|----------------|------------------------------------------------------------------------------------------------------|
| BESS           | Compound area, safety, noise, flood, access, thermal conditions and augmentation are considered.     |
| Scoring        | Weights, definitions, confidence and fatal-flaw criteria are transparent and consistently applied.   |
| AI outputs     | Material statements are traceable to evidence and unsupported conclusions have been removed.         |
| Recommendation | The shortlist, conditions for progression, information gaps and next actions are explicit.           |
| Approval       | Qualified engineering and specialist review has been completed before land or investment commitment. |

Table 3.17 - Minimum quality checks for a preliminary site-screening report.

## 3.21 Prompt Toolkit

The prompts below should be used with a controlled site data pack. Replace bracketed fields, provide source references and require the output to distinguish evidence from assumptions.

### Level 1 - Quick Site Screen

#### QUICK PROMPT

Act as a Senior Solar Project Development Engineer. Review the supplied site description, maps and available constraints for a proposed [capacity] utility-scale Solar PV project with optional BESS. Summarise: (1) apparent strengths; (2) potential fatal flaws; (3) major land, terrain, hydrology, environmental, planning, grid and access risks; (4) missing information; and (5) the ten highest-priority next checks. Do not treat map proximity or unverified statements as confirmed facts.

### Level 2 - Professional Candidate-Site Comparison

#### PROFESSIONAL PROMPT

You are the Lead Project Development Engineer comparing [number] candidate sites for a [MWac] Solar PV and [MW/MWh] BESS project in [jurisdiction]. Use the supplied boundaries, cadastral information, terrain data, resource data, environmental and planning layers, grid infrastructure, access routes and site notes. Evaluate each site across land and geometry, resource and climate, terrain and civil complexity, hydrology, environment and planning, grid connection, access and logistics, BESS suitability, commercial complexity and programme. Produce a site-by-site assessment, fatal-flaw register, weighted score, evidence-confidence rating, key assumptions, information gaps, prioritised actions and a recommended shortlist. Cite the source for every material conclusion.

## Level 3 - Expert Origination and Shortlisting Prompt

### EXPERT PROMPT

You are acting as the Lead Technical Advisor supporting origination of a utility-scale Solar PV and BESS portfolio. Apply a staged screening funnel across the defined search region. Begin by restating the development brief and proposed exclusion criteria. Review the supplied authoritative and indicative datasets, record their provenance and limitations, identify candidate zones, and evaluate shortlisted parcels across project rights, land control, geometry, resource, climate, terrain, hydrology, environment, planning, social receptors, aviation, grid, route corridors, access, logistics, BESS safety and constructability. Separate verified facts, third-party claims, assumptions and information gaps. Produce an executive recommendation, GIS layer and source register requirements, fatal-flaw matrix, risk-adjusted site ranking, evidence-confidence matrix, site-visit plan, specialist survey scope and conditions that must be satisfied before land commitment or acquisition.

## 3.22 Recommended Engineering and Data References

The specific sources depend on jurisdiction. The following categories provide a professional starting framework. Current edition, legal status, spatial resolution and project applicability should always be confirmed.

- National and regional planning legislation, renewable-energy policy, zoning maps and official permitting guidance.
- Land registry, cadastral authorities, boundary surveys, title documentation and executed land agreements.
- Official environmental registers, protected-area databases, habitat records, water authorities and flood-hazard mapping.
- Transmission and distribution system operator network maps, grid codes, connection procedures and formal correspondence.
- Official road, aviation, cultural-heritage, mining, forestry, agricultural and utility-corridor datasets.
- Recognised solar-resource and climate datasets, supported by documented methodology and long-term coverage.
- Digital elevation models, satellite and aerial imagery, topographic surveys and hydrological information with documented resolution.
- Applicable IEC, IEEE, civil, electrical, fire-safety and local construction requirements relevant to concept design and BESS siting.
- Manufacturer technical constraints for modules, trackers, inverters, transformers, BESS enclosures and transport dimensions where relevant.
- Controlled project documents, including boundaries, concept layouts, route studies, risk registers and site-visit records.

## 3.23 Chapter Summary

Preliminary site screening converts a broad geographic opportunity into a prioritised development decision. The process begins with a clear project brief, applies a staged screening funnel, combines multiple evidence sources and separates fatal exclusions from manageable constraints and opportunities.

Artificial Intelligence can significantly improve the speed and consistency of source inventory, site comparison, narrative assessment, risk classification and reporting. Its value depends on controlled GIS analysis, evidence traceability, explicit uncertainty and professional review. AI should not confirm parcel boundaries, legal rights, environmental acceptability, grid capacity or buildable capacity without authoritative evidence and project-specific validation.

A defensible shortlist explains not only which site ranks first, but why, how reliable the evidence is, which conditions could change the ranking and what must be investigated next. This creates a stronger foundation for land engagement, site visits, surveys, grid strategy and the development roadmap.

## 3.24 Key Takeaways

- Site suitability is the convergence of resource, land, grid, permits, constructability, programme and commercial control.
- The project definition must be established before screening criteria are applied.
- A staged screening funnel reduces effort and improves consistency across large search areas.
- Gross area and grid proximity are indicators, not proof of buildable capacity or connection availability.
- Authoritative evidence, dataset limitations, coordinate systems and confidence should be recorded explicitly.
- Scoring supports comparison but must not override fatal flaws, uncertainty or engineering judgement.
- Co-located BESS introduces additional land, safety, noise, access, flood and augmentation considerations.
- AI is most effective for structure, comparison and reporting; GIS analysis and professional validation remain essential.
- The final recommendation should include conditions for progression, not merely a numerical ranking.

## Chapter 3 Completion Checklist

- I can translate a development strategy into a practical site-screening brief.
- I can apply a screening funnel from regional opportunity mapping to parcel-level review.
- I can assess land, resource, terrain, hydrology, environment, planning, grid, access and BESS constraints.
- I can distinguish authoritative evidence from indicative datasets and AI-generated interpretation.
- I can create a transparent scoring model with separate evidence-confidence ratings.
- I can classify fatal flaws, red flags, manageable constraints and opportunities.
- I can use AI to compare candidate sites while preserving source traceability and engineering control.
- I can define the site visits, surveys and authority engagement required before progression.

### LOOKING AHEAD - CHAPTER 4

The next chapter converts a shortlisted opportunity into a Preliminary Development Roadmap. It will structure land, surveys, permitting, environmental work, grid connection, engineering, procurement, financing and decision gates from origination to Ready-to-Build.

### END OF CHAPTER 3

## CHAPTER 4

# AI-Assisted Preliminary Development Roadmap for Utility-Scale Solar and BESS Projects

---

*From shortlisted site to coordinated development execution and Ready-to-Build maturity*

*Workstreams, dependencies, decision gates, critical paths and AI-enabled programme control*

Edition v1.1 | Volume 1

*"A development roadmap is not a list of tasks. It is the logic that connects evidence, approvals, rights, design maturity and investment decisions."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a practical method for converting a shortlisted Solar PV or BESS opportunity into an integrated development roadmap. It explains how to define workstreams, sequence dependencies, identify the critical path, establish decision gates, assign accountability and use AI to maintain a coherent programme from origination through Ready-to-Build.

| Element                 | Purpose                                                                                                                         |
|-------------------------|---------------------------------------------------------------------------------------------------------------------------------|
| Development basis       | Defines the project configuration, target market, commercial objective, stage, assumptions and success criteria.                |
| Workstream architecture | Organises land, permitting, environment, grid, surveys, engineering, commercial, finance and stakeholder activities.            |
| Dependency logic        | Shows which tasks can proceed in parallel and which require evidence, approvals or rights from other workstreams.               |
| Decision gates          | Creates explicit points for pause, re-scope, investment approval, acquisition, FEED, tendering and Ready-to-Build confirmation. |
| Critical-path control   | Identifies the activities most likely to determine the development completion date.                                             |
| Governance system       | Assigns owners, reviewers, approvers, escalation routes and reporting cadence.                                                  |
| AI workflow             | Accelerates roadmap drafting, dependency checks, schedule narratives, risk registers and management reporting.                  |

*Table 4.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Translate a development strategy into a structured, stage-gated programme for Solar PV and BESS projects.
- Define the principal development workstreams and the evidence required from each.
- Map technical, regulatory, commercial and contractual dependencies without creating false schedule certainty.
- Identify critical-path activities, long-lead decisions, schedule float and recovery opportunities.
- Establish decision gates and maturity criteria from origination to Ready-to-Build.
- Use AI to draft, interrogate and maintain a development roadmap while preserving professional control.
- Create governance tools including RACI matrices, deliverable registers, assumptions logs and executive dashboards.



## 4.1 Introduction

Once a site has passed preliminary screening, the development team must convert a promising opportunity into an executable project. This requires more than starting surveys and submitting applications. Each workstream must mature at the right time, using the right evidence, with enough coordination to prevent one unresolved issue from invalidating months of work elsewhere.

Utility-scale Solar PV and BESS projects often fail to progress efficiently because workstreams are managed as independent lists. Land teams negotiate rights without confirming cable routes. Grid applications proceed using layouts that later change substantially. Environmental surveys start too late to capture seasonal windows. Procurement assumptions are fixed before technical requirements mature. Investment decisions are taken without a common definition of development readiness.

A preliminary development roadmap creates the shared logic for the project. It links actions to decisions, decisions to evidence and evidence to maturity. It should identify what must be known, who must produce it, when it is needed, what it enables and what happens if the result is adverse.

Artificial Intelligence can accelerate the creation and maintenance of this roadmap. It can structure workstreams, test dependencies, identify missing tasks, draft decision-gate criteria and convert technical progress into executive reporting. However, AI cannot know the actual authority timetable, land negotiation dynamics, grid queue conditions or project-specific commercial priorities unless these are supplied and validated.

### ENGINEERING INSIGHT

A roadmap should make uncertainty visible. A schedule that hides assumptions behind precise dates is less useful than one that clearly states dependencies, confidence and decision consequences.

## 4.2 What a Development Roadmap Must Achieve

The roadmap is both a planning tool and a decision-control system. It should be detailed enough to coordinate specialist activities, but simple enough that management can understand the route to the next value-creating milestone.

| Objective          | Question the Roadmap Must Answer                                                          | Typical Output                                      |
|--------------------|-------------------------------------------------------------------------------------------|-----------------------------------------------------|
| Define scope       | What project configuration and development outcome are being pursued?                     | Development basis and assumptions register.         |
| Sequence work      | What must happen first, what can run in parallel and what evidence unlocks the next task? | Integrated dependency map and milestone schedule.   |
| Control investment | When should additional expenditure be authorised or withheld?                             | Stage gates with entry and exit criteria.           |
| Expose uncertainty | Which dates, approvals and technical outcomes are uncertain?                              | Confidence ratings, ranges and risk-adjusted dates. |

| Objective             | Question the Roadmap Must Answer                                               | Typical Output                                        |
|-----------------------|--------------------------------------------------------------------------------|-------------------------------------------------------|
| Assign accountability | Who owns each action, deliverable and decision?                                | RACI matrix and deliverable register.                 |
| Support communication | What does management, the project team and external stakeholders need to know? | Dashboards, decision papers and action trackers.      |
| Preserve traceability | Why was a task, assumption or decision included?                               | Evidence references, decision log and change history. |

Table 4.2 - Core functions of a professional development roadmap.

#### BEST PRACTICE

Begin the roadmap with the next investment decision and work backwards to the evidence required. This prevents the programme from becoming a generic checklist.

## 4.3 Development Basis and Success Criteria

Before sequencing activities, the team should agree the development basis. Different objectives create different roadmaps. A merchant BESS, a co-located hybrid project and a contracted Solar PV project may require different grid studies, permit strategies, revenue evidence and procurement timing even when they share the same site.

| Development-Basis Item    | Examples of Required Definition                                                                                                              |
|---------------------------|----------------------------------------------------------------------------------------------------------------------------------------------|
| Project configuration     | PV MW <sub>p</sub> /MW <sub>ac</sub> , BESS MW/MWh, AC- or DC-coupling, standalone or co-located, export limit and expected operating modes. |
| Location and jurisdiction | Municipality, region, planning authority, network operator, land registry context and applicable approval pathway.                           |
| Commercial objective      | Greenfield development, acquisition, build-own-operate, sell at RTB, tolling, PPA, capacity market or merchant exposure.                     |
| Target milestone          | Exclusivity, grid application, permit submission, development consent, financial close, notice to proceed or RTB.                            |
| Design philosophy         | Technology envelope, module/inverter assumptions, tracker strategy, fire strategy, grid-forming requirements and augmentation basis.         |
| Schedule basis            | Target dates, survey seasons, authority lead times, procurement windows and financing constraints.                                           |
| Decision tolerance        | Maximum acceptable CAPEX, connection exposure, curtailment, schedule delay, land fragmentation or permit risk.                               |

Table 4.3 - Minimum development-basis information.

Success criteria should be measurable. “Advance the project” is not a useful target. “Secure option agreements over the project footprint and cable corridor, submit a complete grid application, complete one seasonal ecology cycle and obtain approval to enter FEED” is a controllable milestone.

## 4.4 Workstream Architecture

A utility-scale development programme should be divided into stable workstreams. The exact organisation varies by company and jurisdiction, but the underlying evidence requirements are broadly consistent.

| Workstream                  | Principal Scope                                                                                      | Key Development Evidence                                                       |
|-----------------------------|------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Land and rights             | Site control, access, cable route, easements, option/lease terms and title constraints.              | Executed agreements, title review, cadastral plan and rights matrix.           |
| Planning and permitting     | Development consent, construction licences, land-use compatibility and permit conditions.            | Permit strategy, application register, authority correspondence and approvals. |
| Environment and social      | Ecology, heritage, landscape, noise, water, community and cumulative impacts.                        | Baseline surveys, impact assessment, mitigation plan and consultation record.  |
| Grid connection             | Point of interconnection, studies, application, reinforcement, metering and compliance.              | Connection offer, study reports, compliance plan and route rights.             |
| Site investigations         | Topography, geotechnics, hydrology, contamination, utilities and unexploded ordnance where relevant. | Survey reports, ground model, design parameters and residual risk register.    |
| Engineering                 | Layout, energy yield, civil/electrical basis, BESS concept, fire safety, SCADA and constructability. | Design basis, drawings, calculations, specifications and design-risk register. |
| Commercial and procurement  | CAPEX/OPEX, contracting strategy, market testing, bid process and long-lead equipment.               | Cost model, procurement plan, tender documents and bid evaluations.            |
| Finance and revenue         | Business case, PPA/tolling assumptions, funding conditions and investment approvals.                 | Financial model inputs, revenue evidence and investment committee decisions.   |
| Stakeholders and governance | Authorities, landowners, community, advisers, reporting and decision control.                        | Stakeholder plan, RACI, decision log, dashboard and action register.           |

Table 4.4 - Typical development workstreams and evidence.



Figure 4.1 - Building the preliminary development roadmap.

## 4.5 Stage Definitions from Origination to Ready-to-Build

Terms such as “advanced development” or “near RTB” are frequently used without consistent meaning. A roadmap should define project stages using objective evidence rather than labels.

| Stage            | Purpose                                                                           | Illustrative Exit Evidence                                                                                                                     |
|------------------|-----------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------|
| Origination      | Establish strategic fit and secure the right to investigate.                      | Site shortlist, initial fatal-flaw screen, land approach authority and preliminary grid strategy.                                              |
| Feasibility      | Demonstrate a credible technical and development concept.                         | Preliminary layout, resource/yield basis, initial surveys, permit pathway and grid application basis.                                          |
| Development      | Secure core rights, approvals and connection position.                            | Land control, submitted/approved permits, environmental assessment, grid studies and updated business case.                                    |
| Pre-construction | Convert development evidence into executable design and contracts.                | FEED, geotechnical basis, tender documents, negotiated EPC/supply terms and financing conditions.                                              |
| Ready-to-Build   | Confirm that construction can start after defined final conditions are satisfied. | Effective permits, executable land rights, connection rights, financeable contracts, approved design basis and controlled residual conditions. |

*Table 4.5 - Illustrative stage definitions. Company and jurisdiction-specific definitions should prevail.*

### COMMON MISTAKE

Do not describe a project as Ready-to-Build solely because a principal permit has been granted. Land rights, grid rights, permit conditions, design maturity, contracts and financing conditions must also be tested.

## 4.6 Land and Rights Roadmap

Land is not a single milestone. The project may require separate rights for the generation area, BESS compound, substation, access roads, construction laydown, drainage, cable routes, telecommunications, ecological mitigation and temporary works.

- Confirm cadastral boundaries, ownership, encumbrances and the authority of each negotiating party.
- Map the full rights footprint, including alternative cable and access routes.
- Sequence exclusivity, option, lease, easement and purchase rights to match development expenditure.
- Align long-stop dates, extension rights and conditions precedent with the permit and grid programme.
- Control landowner commitments that could constrain design, construction methods, financing or assignment.
- Maintain a parcel-by-parcel rights matrix and identify single-owner dependencies.

| Land Milestone | Dependency | Decision Enabled |
|----------------|------------|------------------|
|----------------|------------|------------------|

|                                 |                                                    |                                                |
|---------------------------------|----------------------------------------------------|------------------------------------------------|
| Landowner authority confirmed   | Identity, title and representation checks.         | Begin substantive negotiation.                 |
| Heads of terms agreed           | Indicative footprint, access and commercial basis. | Authorise surveys and legal drafting.          |
| Exclusivity or option executed  | Acceptable conditions, duration and access rights. | Commit material development expenditure.       |
| Cable/access rights secured     | Preferred and fallback routes defined.             | Fix connection and logistics concepts.         |
| Lease/easement form financeable | Lender, tax and assignment review.                 | Progress financing and construction contracts. |

Table 4.6 - Illustrative land-rights progression.

## 4.7 Environmental, Planning and Permitting Roadmap

The permitting programme should be built around statutory requirements, survey seasons, authority consultation, application completeness and the design information needed to assess impacts. Late environmental discovery is one of the most common causes of project re-design and delay.

- Confirm the competent authorities, approval hierarchy and whether environmental assessment is mandatory.
- Map seasonal ecology, bird, bat, vegetation, heritage, hydrology, noise and landscape survey windows.
- Determine which design parameters must be frozen before applications are submitted and which can remain as envelopes.
- Allow for pre-application consultation, public consultation, information requests, appeal periods and permit-condition discharge.
- Link mitigation land, biodiversity obligations and community commitments to the land-rights strategy.
- Track permit interdependencies, expiry dates, commencement conditions and change-control requirements.

### COMMON MISTAKE

A missed seasonal survey window can create a delay of many months. Survey mobilisation dates should therefore be treated as critical milestones, not administrative actions.

## 4.8 Grid-Connection Roadmap

Grid connection frequently determines project scale, configuration and timing. The roadmap should distinguish between application submission, technical studies, capacity allocation, connection offer, contractual acceptance, reinforcement delivery, compliance testing and energisation.

| Grid Activity       | Key Inputs                                                                        | Downstream Dependency                        |
|---------------------|-----------------------------------------------------------------------------------|----------------------------------------------|
| Connection strategy | Network topology, target capacity, operating mode, route options and queue rules. | Application scope and project configuration. |

| Grid Activity            | Key Inputs                                                                       | Downstream Dependency                                         |
|--------------------------|----------------------------------------------------------------------------------|---------------------------------------------------------------|
| Application preparation  | Site control evidence, single-line concept, models, data sheets and programme.   | Application completeness and queue position.                  |
| Network studies          | Validated equipment assumptions and dynamic models where required.               | Reinforcement scope, export limit and compliance obligations. |
| Offer assessment         | Cost allocation, milestones, securities, curtailment and termination provisions. | Investment approval and offer acceptance.                     |
| Detailed compliance      | Final equipment, controls, protection, power quality and model validation.       | Energisation and operational approval.                        |
| Route and works delivery | Land rights, permits, utility interfaces and owner/operator responsibilities.    | Physical connection availability.                             |

Table 4.7 - Grid-roadmap activities and dependencies.

**ENGINEERING INSIGHT**

A nearby substation is not a schedule. The roadmap must include queue rules, study duration, offer validity, securities, network works and route rights.

## 4.9 Surveys, Site Investigations and Engineering Maturity

Investigations should be commissioned when they can materially reduce uncertainty or support a decision. Completing every survey immediately may waste capital; completing critical surveys too late may force redesign or invalidate permit submissions.

| Investigation              | Early Use                                                                   | Later Design Use                                                             |
|----------------------------|-----------------------------------------------------------------------------|------------------------------------------------------------------------------|
| Topographic survey         | Confirm developable area, slopes, drainage features and boundary conflicts. | Grading, roads, drainage, pile reveal and cable design.                      |
| Geotechnical investigation | Identify major ground risk and foundation feasibility.                      | Pile design, roads, platforms, trenching, settlement and seismic parameters. |
| Hydrology/flood study      | Test flood exposure and drainage constraints.                               | Drainage system, platform levels, crossings and erosion control.             |
| Utility survey             | Identify conflicts and route constraints.                                   | Protection, diversion and construction method.                               |
| Solar resource/yield study | Support capacity and business-case screening.                               | Bankable yield, loss assumptions and performance guarantees.                 |
| BESS hazard/fire study     | Confirm separation, access and emergency response concept.                  | Fire strategy, ventilation, detection, suppression and authority approval.   |

Table 4.8 - Investigation timing and value.

Engineering maturity should be measured against decisions. A preliminary layout may be sufficient for land negotiations, but not for an EPC fixed price. A concept single-line diagram may support a grid application, but not protection coordination or procurement.

## 4.10 Commercial, Procurement and Cost Development

The commercial roadmap should mature in parallel with engineering. Cost certainty depends on scope certainty, market conditions, contracting strategy and allocation of risks between owner, EPC contractor, suppliers and network operator.

- Create a cost-estimate classification appropriate to each project stage and state the expected accuracy range.
- Separate owner costs, development costs, network charges, taxes, contingencies and escalation from EPC scope.
- Identify long-lead equipment and reservation decisions that may precede final investment approval.
- Align tender timing with design maturity to avoid pricing large quantities of undefined risk.
- Track technical qualifications, exclusions, interface gaps and validity periods during market testing.
- Update the financial model when design, connection, permit or procurement assumptions change.

| Commercial Gate     | Minimum Evidence                                                     | Typical Decision                          |
|---------------------|----------------------------------------------------------------------|-------------------------------------------|
| Benchmark case      | Concept design, capacity, location and market benchmarks.            | Continue feasibility or stop.             |
| Pre-FEED estimate   | Preliminary quantities, grid scope, surveys and risk allowances.     | Approve development budget and FEED.      |
| Tender issue        | Controlled employer requirements, interface matrix and design basis. | Invite binding or semi-binding proposals. |
| Preferred bidder    | Evaluated price, qualifications, schedule and risk allocation.       | Enter contract negotiation.               |
| Financial close/NTP | Executable contracts, permits, land, grid and financing conditions.  | Commit construction capital.              |

*Table 4.9 - Commercial maturity gates.*

## 4.11 Stakeholder, Community and Governance Roadmap

Development timing is influenced by people as much as by technical work. Authorities, landowners, communities, network operators, advisers, investors and internal functions each have different information needs and decision rights.

- Identify stakeholders, influence, interest, expected concerns and required engagement owner.
- Coordinate external messages so that land, permit, grid and community teams do not create contradictory commitments.
- Define which decisions are delegated to the project team and which require executive or investment committee approval.
- Establish meeting cadence, escalation thresholds, action tracking and document-control rules.

- Maintain a decision log recording the evidence, alternatives, approver and consequences of each material decision.

#### **BEST PRACTICE**

Use one integrated action register. Separate trackers maintained by each adviser often hide cross-workstream dependencies and duplicated assumptions.

## 4.12 Dependency Logic and the Critical Path

A roadmap becomes a programme when tasks are connected by logic. Dependencies should reflect the actual evidence or approval needed, not merely a preferred sequence.

| Dependency Type        | Meaning                                                              | Solar/BESS Example                                                                   |
|------------------------|----------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| Finish-to-start        | The successor cannot begin until the predecessor is complete.        | Final geotechnical design begins after field investigation results are available.    |
| Start-to-start         | Activities may progress together after a defined start.              | Environmental assessment drafting begins once baseline surveys commence.             |
| Finish-to-finish       | Outputs should complete together.                                    | Permit drawings and environmental assessment are finalised for the same submission.  |
| External dependency    | Timing is controlled by a third party.                               | Network operator study, authority consultation or land-registry process.             |
| Decision dependency    | A governance decision unlocks expenditure or commitment.             | FEED budget approval before detailed surveys are commissioned.                       |
| Information dependency | A task can proceed only when assumptions reach a minimum confidence. | EPC tender issue after connection scope and project layout are sufficiently defined. |

Table 4.10 - Dependency types used in development planning.

The critical path is the sequence of activities that determines the earliest achievable completion date. It may change as risks emerge or approvals are received. The team should also monitor near-critical paths, because activities with limited float can become critical after a modest delay.




Figure 4.2 - Illustrative permitting critical path.

## 4.13 Schedule Confidence, Ranges and Recovery Planning

Early development schedules should use ranges and confidence levels rather than a single deterministic date. Authority reviews, land negotiations, network studies and seasonal surveys are not fully controlled by the project team.



| Confidence | Meaning                                                                                   | Recommended Treatment                                                   |
|------------|-------------------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| High       | Scope and duration supported by contract, statutory timetable or recent project evidence. | Use a defined date with limited contingency.                            |
| Medium     | Reasonable benchmark exists, but interfaces or third-party timing remain uncertain.       | Use a range and identify the controlling assumptions.                   |
| Low        | Outcome or duration depends on unresolved technical, regulatory or commercial factors.    | Use scenario dates, explicit contingency and an early decision trigger. |

Table 4.11 - Schedule-confidence classification.

Recovery planning should be designed before delay occurs. Options may include parallel studies, alternative routes, additional survey teams, design envelopes, phased applications, early authority engagement, fallback land parcels or procurement reservations. Recovery measures should be assessed for cost, quality, approval risk and reversibility.

#### COMMON MISTAKE

Adding contingency only at the end of the programme does not protect individual decision dates. Place contingency where uncertainty actually exists and identify who can release it.

## 4.14 Decision Gates and Development Maturity

Decision gates prevent the project from spending ahead of evidence. Each gate should state the decision, required evidence, acceptable residual risk, approver and consequence of failure.

| Gate                        | Illustrative Evidence                                                                                          | Possible Outcomes                                 |
|-----------------------------|----------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| G0 - Origination approval   | Strategic fit, preliminary screen, target capacity and land approach plan.                                     | Proceed, refine search or reject.                 |
| G1 - Feasibility budget     | Initial land interest, grid concept, fatal-flaw review and preliminary business case.                          | Fund surveys/application or pause.                |
| G2 - Development commitment | Controlled land rights, credible permit route, grid application and updated cost/yield.                        | Commit full development budget, re-scope or exit. |
| G3 - FEED/tender approval   | Material permits progressing, investigations complete enough, grid scope credible and financing case positive. | Enter FEED/tender or defer.                       |
| G4 - Investment approval    | Permits, rights, connection, contracts, risk allocation and returns satisfy policy.                            | Approve, approve with conditions or reject.       |
| G5 - Ready-to-Build         | Conditions precedent and residual actions controlled with named owners and dates.                              | Issue NTP or hold.                                |

Table 4.12 - Illustrative development decision gates.

A maturity score can support comparison across projects, but it should not average away fatal weaknesses. A project with excellent engineering maturity but no credible land control is not 80% developed. Gate criteria should therefore include mandatory conditions as well as weighted indicators.

## 4.15 The AI-Assisted Roadmap Workflow

AI is most useful when the project team provides a controlled development basis, evidence register and desired decision structure. The output should then be challenged against jurisdiction-specific processes and adviser experience.




Figure 4.3 - AI-assisted development-roadmap workflow.

31. Define the target milestone, commercial objective, project configuration and decision horizon.
32. Provide the available land, grid, permit, environmental, engineering, cost and programme evidence.
33. Ask AI to classify verified facts, assumptions, commitments, conditions and information gaps.
34. Generate a workstream breakdown with deliverables, owners, durations and dependencies.
35. Challenge the sequence for missing seasonal windows, authority steps, land rights, technical interfaces and governance decisions.
36. Create gate criteria, critical-path narrative, risk register and management dashboard.
37. Validate every regulatory step, duration and technical dependency with responsible specialists.
38. Update the roadmap under document control whenever the development basis changes.

### AI TIP

AI-generated dates are planning hypotheses unless supported by contracts, statutory rules, authority confirmation or reliable project benchmarks.

## 4.16 Governance Tools: RACI, Deliverables and Change Control

A roadmap should connect schedule activities to accountable people and controlled documents. Without this connection, progress reporting can describe activity without demonstrating maturity.

| Tool                 | Purpose                                    | Minimum Content                                                                         |
|----------------------|--------------------------------------------|-----------------------------------------------------------------------------------------|
| RACI matrix          | Clarifies responsibility and approval.     | Responsible, accountable, consulted and informed parties for each material deliverable. |
| Deliverable register | Tracks evidence maturity.                  | Document, owner, status, revision, due date, reviewer and decision supported.           |
| Assumptions log      | Prevents unverified inputs becoming facts. | Assumption, source, owner, validation action, expiry and impact.                        |
| Decision log         | Preserves governance traceability.         | Decision, evidence, alternatives, approver, date and consequences.                      |

| Tool             | Purpose                                         | Minimum Content                                                            |
|------------------|-------------------------------------------------|----------------------------------------------------------------------------|
| Interface matrix | Controls boundaries between parties and scopes. | Interface, information exchange, owner, acceptance criterion and due date. |
| Change register  | Assesses impacts of development-basis changes.  | Change, reason, cost, schedule, permits, contracts, risk and approval.     |

Table 4.13 - Core governance tools supporting the roadmap.

## 4.17 Worked Example - Development Roadmap for a 300 MWac Solar PV and 150 MW / 300 MWh BESS Project

A developer has shortlisted approximately 620 hectares in southern Spain for a hybrid project. The concept comprises 390 MWp of Solar PV, 300 MWac export capacity and a 150 MW / 300 MWh AC-coupled BESS. The commercial strategy is to progress the project to Ready-to-Build and retain optionality between a long-term PPA and partial merchant exposure.

At roadmap initiation, the project has indicative landowner interest, a preliminary GIS screen, a nearby 400 kV network node, no confirmed capacity allocation, limited ecological information and no intrusive site investigation. Management wants a decision within eight weeks on whether to fund the full development programme.

| Known or Claimed Item  | Status                                                                  | Roadmap Treatment                                                                     |
|------------------------|-------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
| Main land area         | Six parcels; owners identified; no option agreements.                   | Prioritise title review, heads of terms and survey-access rights.                     |
| Grid opportunity       | Substation 11 km away; capacity unverified.                             | Complete network strategy and prepare application data; preserve two route corridors. |
| Environmental baseline | Public layers show no direct protected-area overlap.                    | Commission ecology and avifauna scoping immediately; confirm seasonal windows.        |
| Site conditions        | Desktop terrain appears generally suitable with two drainage corridors. | Procure topographic, hydrology and preliminary geotechnical studies.                  |
| Project economics      | Benchmark CAPEX and yield only.                                         | Build scenario model including connection, land and BESS augmentation ranges.         |
| Target milestone       | RTB in approximately 30-36 months.                                      | Use a range; authority and grid durations remain low-confidence.                      |

Table 4.14 - Initial project evidence and roadmap treatment.

| Period     | Priority Activities                                                                                                         | Decision or Evidence Produced   |
|------------|-----------------------------------------------------------------------------------------------------------------------------|---------------------------------|
| 0-2 months | Title review, land terms, grid strategy, survey mobilisation, permit-pathway confirmation and initial cost/yield scenarios. | G1 feasibility-budget decision. |

| Period       | Priority Activities                                                                                                                       | Decision or Evidence Produced                     |
|--------------|-------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| 2-6 months   | Execute options, complete topography and early ground/flood work, initiate seasonal ecology, prepare grid application and concept design. | Controlled feasibility basis and grid submission. |
| 6-15 months  | Environmental assessment, authority consultation, design development, route rights, network studies and updated business case.            | G2 development-commitment confirmation.           |
| 15-24 months | Permit determination, connection-offer assessment, FEED investigations, procurement strategy and lender/adviser engagement.               | G3 FEED/tender approval.                          |
| 24-32 months | Condition discharge, detailed grid compliance, EPC/supply tender, financing and final land documentation.                                 | G4 investment approval.                           |
| 30-36 months | Close remaining conditions, execute contracts and verify RTB evidence.                                                                    | G5 Ready-to-Build/NTP decision.                   |

Table 4.15 - Illustrative high-level roadmap. Dates are planning ranges, not confirmed authority commitments.

| Critical or Near-Critical Item | Risk                                                                   | Early Mitigation                                                                            |
|--------------------------------|------------------------------------------------------------------------|---------------------------------------------------------------------------------------------|
| Seasonal avifauna surveys      | Missing a survey window could delay the environmental submission.      | Mobilise specialist immediately and confirm minimum survey protocol with authority/adviser. |
| Grid study and offer           | Capacity, reinforcement cost and timing may alter project scale.       | Develop size scenarios, preserve design flexibility and define offer-acceptance limits.     |
| Cable route rights             | A single owner or planning constraint could block the preferred route. | Maintain at least one feasible fallback corridor and start engagement early.                |
| Hydrology and drainage         | Flood constraints may reduce usable area or require major civil works. | Complete early hydrology model before fixing the permit layout.                             |
| BESS fire/planning basis       | Authority requirements may change spacing or compound location.        | Agree preliminary fire strategy and emergency-access concept during pre-application.        |
| EPC market timing              | Price validity may not align with permit and financing dates.          | Use staged market testing and separate long-lead reservation decisions.                     |

Table 4.16 - Example critical-path risks and mitigations.

#### ENGINEERING INSIGHT

Proceed to the feasibility budget gate only if land exclusivity can be secured on acceptable terms, survey windows can be met and the grid strategy supports at least one viable capacity scenario. Do not anchor the investment case to the 30-month date until the permit pathway and network study timetable are confirmed.

## 4.18 Professional AI Prompt

### PROFESSIONAL PROMPT

You are acting as the Lead Project Development Engineer for a utility-scale Solar PV and BESS project. Using the supplied project brief, site-screening report, land status, grid information, permitting pathway, environmental constraints, survey proposals, concept design, cost assumptions and target commercial milestone, prepare a Preliminary Development Roadmap.

Structure the output as follows:

1. Executive Summary and recommended development strategy.
2. Verified facts, assumptions, commitments and information gaps.
3. Workstream breakdown covering land, permitting, environment, grid, surveys, engineering, commercial, finance and stakeholders.
4. Deliverables, dependencies, durations, owners and decision consequences.
5. Critical path and near-critical activities.
6. Decision gates with entry criteria, exit criteria and approvers.
7. Risk register with mitigation and early-warning indicators.
8. Ninety-day action plan and management dashboard.
9. Alternative scenarios if grid, permit or land assumptions change.

Do not invent statutory durations, authority requirements or project evidence. Mark all unsupported dates as planning assumptions and identify the specialist validation required.

## 4.19 Prompt Toolkit

### Quick Prompt - Roadmap Gap Check

#### QUICK PROMPT

Review the supplied development schedule for a utility-scale Solar PV and BESS project. Identify missing workstreams, hidden dependencies, seasonal constraints, unsupported dates, unclear ownership and decisions that lack defined evidence. Return a prioritised correction list.

### Professional Prompt - Integrated Roadmap

#### PROFESSIONAL PROMPT

Act as the Project Development Manager. Convert the supplied project information into an integrated roadmap from the current stage to Ready-to-Build. Include workstreams, deliverables, owners, dependencies, milestone ranges, critical path, decision gates, risks, assumptions and a ninety-day action plan. Distinguish confirmed dates from estimates.

## Expert Prompt - Investment and Recovery Scenarios

### EXPERT PROMPT

Act as an independent development adviser. Audit the project roadmap and test base, downside and recovery scenarios. Assess whether land, grid, permits, environmental surveys, engineering, procurement and financing can mature coherently. Identify gate failures, schedule compression risks, expenditure at risk and the minimum evidence required before each investment decision.

## 4.20 Common Mistakes

| Mistake                              | Why It Matters                                                                   | Corrective Practice                                            |
|--------------------------------------|----------------------------------------------------------------------------------|----------------------------------------------------------------|
| Using a generic checklist            | Activities may not support the actual investment decision or jurisdiction.       | Build backwards from the next gate and required evidence.      |
| Treating all dates as certain        | Third-party and technical uncertainty disappears from reporting.                 | Use ranges, confidence levels and explicit assumptions.        |
| Ignoring cross-workstream interfaces | Land, grid, permits and design can mature on incompatible bases.                 | Maintain dependency and interface matrices.                    |
| Starting detailed design too early   | Design effort may be invalidated by permits, ground conditions or grid outcomes. | Match engineering maturity to decision needs.                  |
| Calling a project RTB prematurely    | Material rights, conditions or contracts may remain unresolved.                  | Use objective, mandatory RTB evidence criteria.                |
| Allowing AI to invent processes      | Incorrect statutory steps or durations can distort the programme.                | Validate with authorities, advisers and official sources.      |
| Failing to update the business case  | Schedule and scope changes may not reach investment decisions.                   | Link roadmap changes to cost, yield, revenue and risk updates. |

Table 4.17 - Common roadmap errors and corrective practices.

## 4.21 Best Practices

- Define a single controlled development basis and require every workstream to use it.
- Build the programme around decisions and evidence, not activity volume.
- Use ranges and confidence ratings for external and uncertain durations.
- Mobilise seasonal and long-lead activities early, while preserving stop/go points for discretionary expenditure.
- Maintain alternative land, route, capacity and procurement scenarios where reversibility has material value.
- Link every schedule change to cost, risk, permit, contract and financing consequences.
- Use one integrated dashboard that shows maturity, critical path, decisions, risks and overdue actions.
- Re-baseline only after changes are approved; retain the previous baseline for accountability.

## 4.22 Engineering Review Checklist

| Review Area        | Validation Question                                                                                                    | Complete                 |
|--------------------|------------------------------------------------------------------------------------------------------------------------|--------------------------|
| Development basis  | Are configuration, target milestone, commercial strategy and success criteria defined?                                 | <input type="checkbox"/> |
| Workstreams        | Are all land, permit, environment, grid, survey, engineering, commercial, finance and stakeholder activities included? | <input type="checkbox"/> |
| Dependencies       | Does each major task state what evidence or approval enables it?                                                       | <input type="checkbox"/> |
| Seasonality        | Are ecological, weather, access and authority windows included?                                                        | <input type="checkbox"/> |
| Critical path      | Are critical and near-critical activities identified and reviewed regularly?                                           | <input type="checkbox"/> |
| Decision gates     | Are evidence, approvers, residual-risk limits and failure outcomes defined?                                            | <input type="checkbox"/> |
| Dates              | Are confirmed dates distinguished from estimates and scenarios?                                                        | <input type="checkbox"/> |
| Governance         | Are owners, reviewers, escalation routes and reporting cadence clear?                                                  | <input type="checkbox"/> |
| Commercial linkage | Do scope and schedule changes update cost, yield, revenue and financing assumptions?                                   | <input type="checkbox"/> |
| AI validation      | Have regulatory steps, durations and technical dependencies been independently checked?                                | <input type="checkbox"/> |

Table 4.18 - Development-roadmap engineering review checklist.

## 4.23 Recommended Reference Framework

The roadmap should reference current official and project-specific sources. Requirements vary by jurisdiction, technology and network operator. The following categories provide the evidence hierarchy:

- Planning, environmental assessment and construction legislation issued by the competent authorities.
- Official grid-code, connection-process and network-operator documentation.
- Land registry, cadastral, easement and property-law advice from qualified local counsel.
- Applicable IEC, IEEE, EN, NFPA and local electrical, civil, fire and safety standards.
- Authority-approved survey protocols and recognised environmental guidance.
- Contractual requirements, investment policies, lender conditions and company development procedures.
- Current supplier, EPC and adviser evidence for procurement lead times and cost ranges.

**■ STANDARDS REFERENCE**

Standards and official procedures change. Confirm the current edition, jurisdictional adoption and project applicability before relying on any roadmap assumption.

## 4.24 Chapter Summary

A Preliminary Development Roadmap converts a shortlisted opportunity into a controlled route toward investment and construction. It defines the project basis, organises workstreams, connects dependencies, identifies the critical path, establishes decision gates and assigns accountability.

The most useful roadmaps expose uncertainty rather than hiding it. They distinguish confirmed dates from planning assumptions, preserve alternative scenarios and link technical progress to commercial decisions. AI can accelerate the drafting, interrogation and reporting of the programme, but specialist validation remains essential for authority processes, grid requirements, land rights and engineering dependencies.

## 4.25 Key Takeaways

- A development roadmap is a decision-and-evidence system, not a generic task list.
- Land, permits, environment, grid, surveys, engineering, procurement and finance must mature on a common basis.
- Critical-path and near-critical activities should be reviewed continuously, especially seasonal and third-party actions.
- Stage gates should define mandatory evidence, acceptable residual risk, approvers and failure consequences.
- Roadmap dates should carry confidence levels and clearly stated assumptions.
- AI is valuable for structuring, checking and communicating the roadmap, but it must not invent regulatory processes or certainty.
- Ready-to-Build status must be demonstrated through objective rights, approvals, design, contract and financing evidence.

### LOOKING AHEAD - CHAPTER 5

The next chapter focuses on Landowner Assessment and Land-Control Strategy. It will examine ownership verification, parcel structure, negotiation readiness, option and lease principles, access and cable rights, landowner risk, information requests and AI-assisted preparation for land engagement.

## END OF CHAPTER 4



## CHAPTER 5

# AI-Assisted Landowner Assessment and Land-Control Strategy for Utility-Scale Solar and BESS Projects

---

*From promising land opportunity to bankable, buildable and durable project rights*

*Ownership evidence, parcel strategy, access and cable rights, commercial terms, negotiation readiness and AI-enabled land control*

Edition v1.1 | Volume 1

*"A technically attractive site has limited development value until the project can demonstrate clear, durable and financeable rights over every parcel, route and interface it depends on."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a structured method for assessing landowners, verifying parcel conditions and developing a land-control strategy for utility-scale Solar PV and BESS projects. It connects cadastral and title evidence with engineering requirements, commercial terms, negotiation planning, project interfaces and investment gates. The objective is not simply to obtain a signature, but to establish rights that remain usable through development, financing, construction, operation, augmentation and decommissioning.

| Element              | Purpose                                                                                                                              |
|----------------------|--------------------------------------------------------------------------------------------------------------------------------------|
| Ownership evidence   | Confirms who appears entitled to negotiate and identifies the documents and professional checks required before reliance.            |
| Parcel strategy      | Determines which parcels are essential, replaceable, optional or required only for routes and temporary works.                       |
| Landowner assessment | Evaluates decision authority, objectives, constraints, counterparties, communication preferences and negotiation readiness.          |
| Rights architecture  | Defines the required option, lease, purchase, easement, access, cable, drainage, construction and security rights.                   |
| Commercial framework | Structures rent, option payments, indexation, milestones, extensions, compensation and restoration obligations.                      |
| Risk and conditions  | Records title, encumbrance, tenancy, mortgage, inheritance, boundary, planning, route and community risks.                           |
| AI workflow          | Accelerates document inventories, parcel comparisons, issue lists, meeting preparation, term-sheet reviews and management reporting. |

*Table 5.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Translate the physical requirements of a Solar PV and BESS project into a complete land-rights brief.
- Distinguish cadastral information, registry evidence, survey evidence, legal title and negotiated assumptions.
- Assess parcel fragmentation, ownership complexity, route dependencies and landowner concentration risk.
- Prepare a structured landowner opportunity assessment without making unsupported legal conclusions.
- Compare option, lease, purchase, licence and easement structures at a conceptual development level.
- Identify access, cable, substation, drainage, temporary-construction, security and decommissioning rights that are often overlooked.
- Use AI to organise evidence, prepare negotiations and review consistency while protecting confidentiality and preserving legal oversight.

- Define decision gates and conditions for progressing land expenditure, surveys, applications and acquisition.

## 5.1 Introduction

Land control is one of the first value-creating workstreams in project development and one of the easiest to underestimate. A site may have excellent irradiation, favourable terrain and apparent grid proximity, yet remain undevelopable because ownership is uncertain, key parcels are excluded, access is not secured, cable routes cross third-party land or the negotiated rights do not survive financing and construction requirements.

The land workstream must therefore connect three different realities. The first is the legal reality: who owns or controls the land, what burdens affect it and what instruments are valid in the jurisdiction. The second is the engineering reality: which areas, corridors, setbacks, compounds and temporary rights are actually required. The third is the commercial reality: whether the counterparty is willing and able to grant those rights on terms compatible with the project economics and programme.

Artificial Intelligence can help development teams structure this information, compare parcels, identify inconsistencies, prepare questions and draft internal assessments. It cannot verify ownership, interpret local property law with authority, conduct a boundary survey, negotiate ethically on behalf of the developer or replace qualified legal advice. Every conclusion affecting title, enforceability, registration, tax, inheritance, tenancy or security must be validated by competent local professionals.

### COMMON MISTAKE

This chapter provides a project-development framework, not legal advice. Land instruments, title conclusions and enforceability must be reviewed by qualified local counsel, notaries, surveyors and other competent professionals in the relevant jurisdiction.

## 5.2 Why Land Control Determines Project Value

A development opportunity gains value when the developer can demonstrate a credible route from identified land to durable project rights. Investors and lenders do not assess only whether a landowner has expressed interest. They assess whether the project controls the complete footprint, whether the rights are clear and assignable, whether access and routes are protected, and whether the duration and termination provisions support the expected asset life.

| Development Question                   | Weak Evidence                                                    | Stronger Evidence                                                                             |
|----------------------------------------|------------------------------------------------------------------|-----------------------------------------------------------------------------------------------|
| Who controls the land?                 | Name supplied by an intermediary or unverified cadastral record. | Current registry/title evidence reviewed by local counsel and matched to parcel mapping.      |
| Is the full project footprint covered? | A single indicative polygon or verbal agreement.                 | Parcel schedule linked to controlled layout, routes, compounds, setbacks and temporary works. |

| Development Question                 | Weak Evidence                               | Stronger Evidence                                                                                             |
|--------------------------------------|---------------------------------------------|---------------------------------------------------------------------------------------------------------------|
| Can the project reach the site?      | Existing informal track visible on imagery. | Documented access rights suitable for construction, operation, emergency and replacement vehicles.            |
| Can electricity leave the site?      | Straight-line route to a substation.        | Feasible corridor with land rights strategy, crossings, interfaces and alternatives.                          |
| Will rights survive project changes? | Fixed concept area with no flexibility.     | Defined variation, micro-siting, route, substation, BESS and extension rights within agreed limits.           |
| Are rights financeable?              | Personal promise or short-form letter.      | Executed, registrable and assignable instrument with appropriate term, cure, security and lender protections. |

Table 5.2 - Progression from informal land interest to development-grade evidence.

#### ENGINEERING INSIGHT

Land control should be assessed as an integrated system. A project can fail because of one missing access strip, cable corridor, substation parcel or construction laydown area even when the main generation footprint is secured.

## 5.3 Establishing the Land Requirements Brief

The land team should not negotiate against an undefined engineering concept. Before engagement, the project should prepare a controlled land requirements brief that translates the current design basis into rights, areas, corridors and flexibility provisions.



Figure 5.1 - Converting the engineering concept into a land-control strategy.

| Requirement Category      | Typical Components                                                                             | Development Question                                                                 |
|---------------------------|------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| Permanent generation area | PV blocks, tracker rows, inverter stations, internal roads, drainage and setbacks.             | Which parcels are essential to the target capacity and which can be substituted?     |
| BESS and substation area  | Battery enclosures, PCS, transformers, fire separation, control buildings and expansion zones. | Is the area suitable for safety, access, noise, flood and augmentation requirements? |
| Linear rights             | Export cable, fibre, drainage, water, communications and utility corridors.                    | Are route width, installation, inspection, repair and replacement rights included?   |
| Access rights             | Construction access, operational access, emergency access and abnormal-load routes.            | Are rights continuous from public highway to every critical compound?                |

| Requirement Category | Typical Components                                                                                | Development Question                                                                          |
|----------------------|---------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------|
| Temporary rights     | Laydown, crane pads, batching, worker facilities, storage, passing places and temporary widening. | Are timing, restoration and compensation mechanisms defined?                                  |
| Ancillary rights     | Surveys, monitoring, boreholes, fencing, signage, vegetation management and security.             | Can the developer perform required activities before and after construction?                  |
| Future flexibility   | Micro-siting, route adjustment, repowering, augmentation and project extension.                   | What controlled flexibility is necessary without creating unacceptable landowner uncertainty? |

Table 5.3 - Land requirements that should be translated into explicit rights.

## 5.4 Ownership, Cadastral and Boundary Evidence

Land information is often assembled from sources created for different purposes. A cadastral map may support taxation or parcel administration, a registry extract may evidence registered interests, a survey may define measured boundaries and a landowner may describe long-standing occupation. These sources can overlap without being identical.

The development team should classify each statement according to its evidence status and avoid describing an indicative parcel map as a confirmed legal boundary. Coordinate reference systems, mapping dates, parcel identifiers, subdivisions, consolidations and unresolved overlaps should be recorded explicitly.

| Evidence Type                | What It May Support                                                                         | Key Limitation / Required Check                                                                       |
|------------------------------|---------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------|
| Cadastral record             | Parcel identifier, indicative extent, administrative reference and potential taxpayer link. | May not prove ownership or surveyed legal boundary; confirm currency and jurisdictional meaning.      |
| Land registry/title record   | Registered owner and registered interests, subject to local system and document scope.      | Requires legal interpretation; unregistered rights, pending changes or off-register claims may exist. |
| Boundary/topographic survey  | Measured physical features, coordinates, fences and surveyor interpretation.                | Must be reconciled with title and agreed scope; physical occupation may differ from legal boundary.   |
| Tax or municipal record      | Administrative or fiscal information.                                                       | May not establish legal ownership or complete encumbrances.                                           |
| Landowner declaration        | Practical history, occupation, access use, tenants and local context.                       | Must be verified; memory, family arrangements or informal rights may be incomplete.                   |
| Legal opinion / title report | Professional conclusion on title, rights and identified risks.                              | Depends on scope, assumptions, searches and jurisdiction; update before reliance or closing.          |

Table 5.4 - Evidence hierarchy for ownership and boundary assessment.

**COMMON MISTAKE**

Do not use “owner confirmed” merely because a name appears on a map or because one family member attends a meeting. Record exactly what has been verified, by whom, from which source and on what date.

## 5.5 Parcel Structure and Land-Control Geometry

The geometry of land control can be as important as the total hectares secured. A project assembled from many narrow or disconnected parcels creates additional interfaces, negotiation dependencies, fencing complexity, route constraints and risk of holdout by a small number of essential owners.

| Geometry Indicator                  | Why It Matters                                                                | Possible Response                                                                             |
|-------------------------------------|-------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------|
| Essential parcel concentration      | One owner controls land without which the concept cannot function.            | Develop alternative layout or route; sequence negotiation carefully; protect confidentiality. |
| Fragmentation                       | Many owners and boundaries increase execution and programme risk.             | Prioritise contiguous blocks, standardise terms and track parcel-level conditions.            |
| Narrow connectors                   | A small strip may control access, cable or internal circulation.              | Confirm width, turning, construction and maintenance requirements early.                      |
| Irregular exclusions                | Houses, habitats, watercourses or retained uses reduce efficient layout area. | Model net buildable land and preserve micro-siting rights.                                    |
| Disconnected BESS/substation parcel | Creates separate access, cable and security interfaces.                       | Confirm independent rights, route continuity and operational responsibility.                  |
| Boundary uncertainty                | May affect setback, row placement, fencing and neighbour disputes.            | Commission survey and maintain design buffers until resolved.                                 |

*Table 5.5 - Parcel geometry indicators and development responses.*

A parcel schedule should therefore classify land by function and criticality rather than merely by owner. Useful categories include essential generation land, design-flexibility land, BESS/substation land, access land, export-route land, temporary construction land and optional expansion land.

## 5.6 Landowner Opportunity Assessment

A landowner assessment should support respectful, informed and efficient engagement. It is not a judgement of personality. It is a structured view of the counterparty, decision process, stated objectives, known constraints and evidence required to move forward.

| Assessment Area    | Questions to Explore                                                                                      | Evidence / Output                                                     |
|--------------------|-----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------|
| Decision authority | Who can negotiate, approve and execute?<br>Are co-owners, spouses, companies, heirs or trustees involved? | Authority map, signatory requirements and legal verification actions. |

| Assessment Area      | Questions to Explore                                                                                     | Evidence / Output                                        |
|----------------------|----------------------------------------------------------------------------------------------------------|----------------------------------------------------------|
| Objectives           | Income, sale, family succession, continued agriculture, infrastructure improvement or community benefit? | Negotiation priorities and potential value exchanges.    |
| Current land use     | Owner-operated, leased, grazed, cropped, vacant, protected, mortgaged or subject to third-party rights?  | Occupancy and termination plan; compensation interfaces. |
| Timing               | Is the owner ready now? Are harvest, inheritance, financing or tax events relevant?                      | Realistic engagement and execution programme.            |
| Risk perception      | Concerns about construction, visual impact, fire, noise, restoration, neighbours or reputation?          | Targeted information pack and mitigation commitments.    |
| Communication        | Preferred language, adviser involvement, meeting format and documentation level?                         | Engagement plan and record-keeping protocol.             |
| Relationship network | Are neighbouring owners, local representatives or intermediaries influential?                            | Stakeholder map and confidentiality strategy.            |

Table 5.6 - Landowner opportunity-assessment framework.

**BEST PRACTICE**

Use factual, respectful language. Record what the landowner has stated, what has been independently verified and what remains an assumption. Avoid speculative labels or subjective character assessments.

## 5.7 Counterparty and Decision-Authority Complexity

A parcel may involve more parties than the apparent owner. Co-ownership, inheritance, corporate ownership, mortgages, usufruct, tenants, agricultural operators, family arrangements, insolvency, court proceedings or public rights can affect the ability to grant usable project rights.

| Complexity                          | Development Risk                                                      | Priority Action                                                                    |
|-------------------------------------|-----------------------------------------------------------------------|------------------------------------------------------------------------------------|
| Multiple co-owners                  | Delay, inconsistent expectations or incomplete execution.             | Map all required parties and obtain legal confirmation of execution requirements.  |
| Deceased owner / succession pending | No clear authority to bind the land.                                  | Obtain specialist legal advice and realistic timetable before critical reliance.   |
| Corporate owner                     | Internal approvals, authorised signatories and security restrictions. | Review corporate documents, authority and approval process.                        |
| Mortgage or security                | Consent, priority or enforcement may affect the project rights.       | Identify lender/security holder and required consent or non-disturbance structure. |

| Complexity              | Development Risk                                                                | Priority Action                                                                |
|-------------------------|---------------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Tenant or operator      | Possession, crop, access and termination rights may conflict with construction. | Review agreements and define surrender, compensation and timing.               |
| Intermediary            | Misaligned incentives or unclear mandate.                                       | Verify written authority, fee arrangement and communication protocol.          |
| Public or communal land | Special procurement, approval, transparency or public-law requirements.         | Confirm official process and authority before commercial assumptions are made. |

Table 5.7 - Counterparty complexities requiring early verification.

## 5.8 Land-Control Instruments

The appropriate instrument depends on jurisdiction, development stage, capital strategy, landowner preference and project risk. The categories below describe commercial functions only. Local legal advice is required to determine valid form, registration, tax, enforceability and interaction with property rights.

| Instrument                      | Typical Development Function                                                                             | Key Questions                                                                                                |
|---------------------------------|----------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------|
| Exclusivity / heads of terms    | Creates a limited negotiation window and records principal commercial understanding.                     | Is it binding, for how long, on what scope and with what confidentiality and cost obligations?               |
| Option                          | Provides a right, but not obligation, to enter a lease or purchase after development conditions are met. | Option period, extensions, exercise mechanics, assignability, access before exercise and termination rights. |
| Lease                           | Grants operational use for a defined term, often after option exercise.                                  | Premises, permitted use, rent, term, renewals, repair, restoration, security and lender protections.         |
| Purchase                        | Transfers ownership where acquisition is commercially and legally appropriate.                           | Price, conditions, taxes, title, retained rights, completion timing and development failure exposure.        |
| Easement / servitude / wayleave | Secures access, cable, drainage, utilities or other rights over third-party land.                        | Route definition, width, construction rights, repair, vegetation, relocation and priority.                   |
| Licence                         | Permits limited surveys, access or temporary activities.                                                 | Revocability, duration, insurance, damage, reinstatement and whether stronger rights are later required.     |

Table 5.8 - Conceptual functions of common land-control instruments.

### ENGINEERING INSIGHT

The instrument should be reviewed not only for today's development activity but also for assignment, security, lender cure, construction, operation, repowering, augmentation, decommissioning and the full expected project term.



## 5.9 Rights Beyond the Main Site

Land agreements frequently focus on the visible generation footprint and overlook the rights needed to build, connect and operate the project. These omissions may emerge late, when negotiating leverage is lower and programme impact is greater.

| Right                           | Minimum Topics to Consider                                                                                         | Typical Failure Mode                                                              |
|---------------------------------|--------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------|
| Survey and investigation        | Entry, vehicles, drones where lawful, boreholes, monitoring equipment, vegetation disturbance and reinstatement.   | Developer cannot complete required studies before option exercise.                |
| Access                          | Public-road connection, width, gates, turning, abnormal loads, emergency access, upgrades and maintenance.         | Existing track is physically present but no enforceable or adequate right exists. |
| Export and communications route | Cable/fibre installation, working width, joint bays, markers, inspection, repair, replacement and crossing rights. | Route is shown on a layout but not secured through every parcel.                  |
| Drainage and water management   | Outfalls, culverts, channels, maintenance and upstream/downstream interfaces.                                      | Consent is absent for off-site works or discharge path.                           |
| Temporary construction          | Laydown, crane pads, parking, offices, storage, batching, borrow/spoil and temporary widening.                     | Permanent lease area cannot support efficient construction logistics.             |
| Security and vegetation         | Fencing, surveillance, lighting, firebreaks, trimming and access control.                                          | Operational obligations conflict with retained land use.                          |
| Decommissioning and restoration | Removal access, timing, standards, security, residual infrastructure and land condition.                           | End-of-term obligations are vague or commercially unquantified.                   |

*Table 5.9 - Ancillary rights that should be tested against the project lifecycle.*

## 5.10 Commercial Terms and Payment Architecture

Commercial terms should reflect the value and risk transferred at each development stage. A project may use reservation or option payments during development, followed by rent, purchase consideration or easement compensation after exercise. The structure should be clear enough to model and administer, while remaining adaptable to the final controlled area and project configuration.

| Commercial Topic             | Questions for the Development Team                             | Control Measure                                                      |
|------------------------------|----------------------------------------------------------------|----------------------------------------------------------------------|
| Option / reservation payment | When is it payable, refundable, credited, staged or increased? | Payment schedule linked to executed rights and verified milestones.  |
| Operational rent             | Per hectare, per MW, fixed amount, revenue-linked or hybrid?   | Model multiple scenarios and define measurement basis unambiguously. |

| Commercial Topic                | Questions for the Development Team                                                 | Control Measure                                                             |
|---------------------------------|------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| Indexation                      | Which index, base date, frequency, cap/floor and treatment of negative indexation? | Use consistent financial-model assumptions and legal drafting.              |
| Capacity or area adjustment     | What happens if the final project is smaller, larger or reconfigured?              | Define minimum, maximum and adjustment mechanisms.                          |
| Easement compensation           | One-off, annual, area-based, route-based or loss-based?                            | Separate permanent rights, temporary working area and proven damage.        |
| Crop / disturbance compensation | How are losses, timing and evidence assessed?                                      | Pre-agreed method, records and independent assessment where appropriate.    |
| Taxes and costs                 | Who bears transaction taxes, registration, advisers, survey and notarial costs?    | Explicit allocation and approval limits.                                    |
| Restoration / security          | Is security required and how is liability limited?                                 | Define standard, timing, mechanism and interaction with permits or lenders. |

Table 5.10 - Commercial-term architecture for land control.

**BEST PRACTICE**

Avoid comparing headline rent alone. The economic effect also depends on option period, indexation, minimum payments, affected area, route compensation, extensions, taxes, restoration and termination rights.

## 5.11 Conditions, Milestones, Longstop Dates and Extensions

Development rights must remain alive long enough for the project to complete uncertain third-party processes. At the same time, landowners require visibility over duration, payments and release. The agreement should therefore connect time, evidence and extension rights in a transparent way.

| Mechanism            | Purpose                                                                         | Development Consideration                                                                                |
|----------------------|---------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| Conditions precedent | Prevents exercise or completion until defined matters are satisfied or waived.  | Use objective evidence and clear responsibility; avoid conditions that cannot be controlled or verified. |
| Milestone payments   | Recognises increased land commitment as the project advances.                   | Link to meaningful, auditable events rather than ambiguous “progress”.                                   |
| Longstop date        | Sets the latest date for exercise, completion or satisfaction of conditions.    | Include realistic authority, grid and seasonal uncertainty.                                              |
| Extension option     | Allows additional development time in exchange for payment or defined criteria. | Preserve unilateral or objective exercise mechanics where commercially achievable.                       |

| Mechanism         | Purpose                                                              | Development Consideration                                                               |
|-------------------|----------------------------------------------------------------------|-----------------------------------------------------------------------------------------|
| Partial exercise  | Allows the developer to take only the final required area or routes. | Ensure the retained land and landowner obligations remain workable.                     |
| Release mechanism | Returns unnecessary land and reduces ongoing burden.                 | Coordinate with survey results, design freeze, route selection and lender requirements. |

*Table 5.11 - Timing and flexibility mechanisms in development-stage land control.*

## 5.12 Title, Encumbrances and Third-Party Rights

Land due diligence should identify matters that may prevent, delay or qualify the project rights. The development team should maintain an issue register that links each title or third-party matter to the affected parcel, project function, responsible adviser, required evidence and decision deadline.

| Issue Category                                  | Possible Project Impact                                             | Typical Follow-Up                                                        |
|-------------------------------------------------|---------------------------------------------------------------------|--------------------------------------------------------------------------|
| Mortgage / charge                               | Priority, consent, enforcement or non-disturbance risk.             | Obtain legal advice, consent strategy and lender interface requirements. |
| Existing lease / tenancy                        | Possession, crop, access, termination and compensation constraints. | Review agreement, expiry, surrender and operator engagement plan.        |
| Access or utility rights                        | Third-party use may conflict with layout, fencing or safety.        | Map rights and define protection, relocation or coexistence strategy.    |
| Restrictive covenant / use limitation           | May constrain energy, industrial, building or commercial use.       | Legal interpretation and release/consent strategy.                       |
| Boundary dispute / adverse occupation           | Reduces usable area and creates litigation or neighbour risk.       | Survey, legal investigation and design buffer or exclusion.              |
| Agricultural support or conservation obligation | May trigger repayment, consent or land-use constraints.             | Specialist advice and commercial allocation.                             |
| Heritage / water / mining / public rights       | May restrict works or introduce authority interfaces.               | Confirm official records and integrate into permitting and design.       |

*Table 5.12 - Land issues and project-development follow-up.*

## 5.13 Negotiation Strategy and Ethical Engagement

Landowner engagement should be based on clarity, respect and controlled authority. The development team should understand which terms it can negotiate, which require approval and which commitments must not be made. Meeting records should distinguish information, proposals, concerns, actions and unresolved points.

- Prepare a parcel-specific brief before each engagement, including known evidence, required rights and open questions.

- Explain the development process and uncertainty honestly; avoid presenting planning, grid or financing outcomes as guaranteed.
- Use consistent core principles across similarly situated landowners while recognising legitimate parcel-specific differences.
- Do not pressure vulnerable or uncertain parties; allow appropriate adviser involvement and review time.
- Confirm the role and authority of agents, intermediaries and family representatives before sharing confidential terms.
- Record offers, counteroffers, non-financial concerns and approval limits in a controlled negotiation log.
- Coordinate community and neighbour implications rather than treating every negotiation as isolated.

#### BEST PRACTICE

AI should not be used to manipulate, profile or exploit landowners. Use it to organise facts, improve clarity and prepare fair engagement—not to infer sensitive personal characteristics or generate coercive tactics.

## 5.14 Land Information Request and Data Room

A controlled information request reduces repeated questions and allows legal, engineering and commercial teams to work from the same evidence. The requested documents will vary by jurisdiction and owner type, and privacy requirements must be respected.

| Information Group                  | Illustrative Documents / Questions                                                                 | Owner                             |
|------------------------------------|----------------------------------------------------------------------------------------------------|-----------------------------------|
| Identity and authority             | Identity, corporate authority, powers of attorney, co-owner and signatory information.             | Legal / land team.                |
| Title and parcel evidence          | Registry extracts, deeds, cadastral references, plans, subdivisions and pending applications.      | Legal / survey.                   |
| Occupancy and use                  | Tenancies, farm operations, crops, grazing, buildings, licences and informal users.                | Land / legal.                     |
| Security and burdens               | Mortgages, charges, easements, rights of way, utilities, litigation and notices.                   | Legal.                            |
| Access and infrastructure          | Road use, gates, bridges, drainage, water, electricity, telecoms and maintenance responsibilities. | Engineering / land.               |
| Environmental and heritage context | Known protected features, contamination, water issues, archaeology and prior studies.              | Environment / engineering.        |
| Commercial and tax                 | Existing income, tax treatment questions, adviser requirements and payment preferences.            | Commercial / legal / tax adviser. |

*Table 5.13 - Illustrative land data-room request.*

The data room should apply document naming, version control, access permissions, privacy controls and a source register. AI tools should be used only in accordance with company policy, confidentiality obligations and applicable data-protection requirements.

## 5.15 The AI-Assisted Land Assessment Workflow

AI is most valuable when it operates on a controlled evidence set and produces structured outputs for professional review. The workflow below keeps legal conclusions and negotiation authority outside the AI system.



Figure 5.2 - AI-assisted landowner and land-control workflow.

39. Define the project configuration, required land functions, decision objective and permitted use of confidential data.
40. Create an evidence inventory and classify each document by source, date, parcel, authority and reliability.
41. Build a parcel-rights matrix linking generation, BESS, substation, access, cable, drainage and temporary-construction needs.
42. Ask AI to identify inconsistencies, missing evidence, duplicate parcel references and unanswered questions without making ownership conclusions.
43. Prepare landowner meeting briefs, agendas, question lists and neutral summaries of the project process.
44. Compare commercial term sheets and flag inconsistencies against the approved negotiation mandate.
45. Submit title, legal form, registration, tax, security and enforceability matters to qualified advisers.
46. Update the parcel register, risk register, action log and development roadmap after each verified change.

| AI Task              | Useful Output                                                     | Mandatory Human Control                                      |
|----------------------|-------------------------------------------------------------------|--------------------------------------------------------------|
| Document inventory   | Parcel-indexed source list and missing-document schedule.         | Confirm completeness, confidentiality and source identity.   |
| Term comparison      | Clause/term matrix and deviations from approved position.         | Legal review and commercial approval.                        |
| Meeting preparation  | Agenda, factual brief, open questions and action template.        | Land-team judgement, cultural context and ethical review.    |
| Issue classification | Potential title, route, occupancy and authority questions.        | No legal conclusion without counsel and source verification. |
| Management reporting | Parcel status dashboard, critical dependencies and decisions due. | Validate status with responsible workstream owners.          |

Table 5.14 - Appropriate AI support and required professional controls.

## 5.16 Land-Control Status and Confidence Framework

A single status such as “secured” can hide material uncertainty. The project should report both the maturity of the land right and confidence in the underlying evidence.

| Status                     | Definition                                                                                          | Typical Evidence                                                      |
|----------------------------|-----------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------|
| Identified                 | Parcel and potential counterparty are known but authority and rights are not verified.              | Indicative map, referral or initial contact.                          |
| Engaged                    | Counterparty has been contacted and interest or process has been discussed.                         | Meeting record and information request.                               |
| Commercially aligned       | Principal commercial terms are substantially agreed, subject to documentation and approvals.        | Approved heads of terms or term sheet.                                |
| Executed development right | Option, exclusivity, licence or equivalent is executed in required form.                            | Executed document and evidence of authority, subject to legal review. |
| Exercise-ready             | Conditions, title, consents, surveys and required approvals are sufficiently resolved for exercise. | Closing checklist and adviser confirmations.                          |
| Operationally controlled   | Long-term lease, ownership and ancillary rights are effective for construction and operation.       | Completion documents, registrations and lender-required evidence.     |

Table 5.15 - Illustrative land-control maturity states.

| Confidence | Meaning                                                                                                          | Reporting Rule                                                       |
|------------|------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------|
| High       | Current authoritative evidence has been reviewed by the competent professional and matches the project register. | May support decision, subject to stated scope and conditions.        |
| Medium     | Evidence is credible but incomplete, dated or awaiting professional confirmation.                                | Use with explicit qualification and action owner.                    |
| Low        | Based mainly on informal statements, indicative mapping or unverified assumptions.                               | Do not rely on for irreversible investment or formal representation. |

Table 5.16 - Evidence-confidence classification for land reporting.

## 5.17 Worked Example - Land-Control Strategy for a 280 MWac Solar PV and 140 MW / 280 MWh BESS Project

A developer is evaluating a 280 MWac Solar PV project with a co-located 140 MW / 280 MWh BESS. The concept requires approximately 520 hectares of gross search area, a 12-hectare BESS/substation compound, construction access from a regional road and an approximately 7.5 km export-cable corridor. The initial opportunity was introduced by one land agent and described as “controlled by three families”.

Desktop review shows that the apparent site comprises fourteen cadastral parcels. The main generation area is divided among four ownership groups. One narrow parcel is essential for internal access, the BESS compound is on a separately owned parcel, and the shortest export route crosses five additional properties. Registry and

cadastral identifiers do not fully align for two parcels, and part of the site appears to be operated under an agricultural tenancy.

| Item                | Initial Statement                        | Verified / Current Position                                                           | Treatment                                                                 |
|---------------------|------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------|
| Main site ownership | Three families control the site.         | Four ownership groups identified; authority not yet verified for all parties.         | Prepare owner/authority map and obtain current title evidence.            |
| Buildable area      | Approximately 600 ha available.          | Gross polygon 598 ha; preliminary exclusions reduce indicative usable area to 472 ha. | Retain design flexibility and test capacity before agreeing minimum rent. |
| Access              | Existing farm road reaches the site.     | Physical route crosses an intervening parcel with no documented project right.        | Develop primary and alternative access-right strategy.                    |
| BESS area           | Can be placed anywhere on the main land. | Preferred low-gradient compound is separately owned and near residences.              | Assess alternative compounds, noise/fire buffers and independent access.  |
| Cable route         | Substation is 7.5 km away.               | Shortest corridor crosses five third-party properties and a watercourse.              | Compare route alternatives and initiate easement screening.               |
| Occupancy           | Owner-operated farmland.                 | One section reportedly farmed by a tenant; documents not supplied.                    | Request tenancy evidence and integrate crop/possession timing.            |

Table 5.17 - Worked-example evidence classification.

The project team creates a functional parcel matrix rather than treating the opportunity as one site:

| Land Function         | Criticality | Current Control             | Primary Risk                                     | Next Decision                                                    |
|-----------------------|-------------|-----------------------------|--------------------------------------------------|------------------------------------------------------------------|
| Core PV block A       | Essential   | Commercial discussion only. | Two co-owners and incomplete authority evidence. | Proceed to legal verification before issuing final term sheet.   |
| Core PV block B       | Essential   | Draft option under review.  | Agricultural tenancy and harvest timing.         | Confirm possession/surrender strategy and compensation basis.    |
| Flex PV block C       | Replaceable | No engagement.              | Fragmented parcels and lower layout efficiency.  | Hold as design alternative; do not make critical path initially. |
| Internal access strip | Essential   | Uncontrolled.               | Single small parcel creates holdout risk.        | Develop alternative access and prioritise discreet engagement.   |

| Land Function            | Criticality               | Current Control                      | Primary Risk                                                      | Next Decision                                                        |
|--------------------------|---------------------------|--------------------------------------|-------------------------------------------------------------------|----------------------------------------------------------------------|
| BESS/substation compound | Preferred but replaceable | Owner interested.                    | Noise setback, separate access and higher commercial expectation. | Complete concept comparison before committing to footprint.          |
| Export corridor route 1  | Preferred                 | 0 of 5 rights secured.               | Watercourse crossing and multiple owners.                         | Undertake route study and define route 2 before negotiations mature. |
| Temporary laydown        | Required for construction | Not included in current term sheets. | Insufficient construction space on permanent lease area.          | Add temporary right and reinstatement mechanism.                     |

Table 5.18 - Worked-example functional parcel and rights strategy.

AI is used to compare the fourteen parcels, identify inconsistent identifiers, prepare owner-specific question lists and create a term-sheet deviation matrix. The land manager validates all meeting information, the surveyor reconciles mapping and local counsel verifies title, authority, tenancy and instrument form. The investment team does not treat the site as land-secured until the essential access strip and a feasible export corridor have a credible control strategy.

| Decision Gate                      | Required Evidence                                                                                   | Outcome                                                        |
|------------------------------------|-----------------------------------------------------------------------------------------------------|----------------------------------------------------------------|
| Approve land budget                | Controlled parcel map, owner/authority hypothesis, concept capacity range and negotiation mandate.  | Conditional approval with capped early expenditure.            |
| Authorise surveys                  | Executed entry rights over all survey areas, insurance and reinstatement terms.                     | Survey mobilisation only for controlled areas.                 |
| Submit material permit/grid design | Stable site boundary, access concept, BESS/substation options and export-route assumptions.         | Proceed with documented alternatives and explicit uncertainty. |
| Exercise principal options         | Title report, authority, tenancy resolution, final controlled area, access and route strategy.      | Exercise only after legal, technical and commercial sign-off.  |
| Declare land ready for financing   | Effective long-term rights, registrations/consents, lender protections and residual issue schedule. | Formal land-control certificate by responsible advisers.       |

Table 5.19 - Worked-example land decision gates.

## 5.18 Consultant-Grade Prompt Methodology

Land prompts should direct AI to organise and question evidence without making legal conclusions. They should state the jurisdiction, project stage, permitted data use, available documents, required outputs and matters reserved for counsel.



| Prompt Component | Land-Control Application                                                                                                                                         |
|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Role             | Development land manager, Owner's Engineer, project controls analyst or commercial adviser—not "property lawyer" unless the output is clearly non-authoritative. |
| Context          | Project capacity, technology, stage, jurisdiction, target dates, parcel count, route needs and decision objective.                                               |
| Inputs           | Controlled parcel schedule, title summaries, cadastral plans, concept layout, route study, meeting notes and approved commercial mandate.                        |
| Task             | Compare parcels, identify evidence gaps, prepare questions, review consistency or draft an internal assessment.                                                  |
| Deliverables     | Executive summary, parcel matrix, rights gaps, owner questions, risk register, action plan and decision conditions.                                              |
| Constraints      | Do not infer ownership, provide legal advice, invent terms, expose unnecessary personal data or treat unverified statements as facts.                            |

*Table 5.20 - Anatomy of a consultant-grade land prompt.*

### LEVEL 1 - QUICK PROMPT

Using the supplied parcel schedule and concept layout, list the land rights required for the Solar PV area, BESS/substation compound, access, export cable, drainage and temporary construction. Separate confirmed information, assumptions and questions. Do not make legal ownership conclusions.

### LEVEL 2 - PROFESSIONAL PROMPT

You are supporting the land manager for a utility-scale Solar PV and BESS project. Review the controlled parcel register, cadastral plans, meeting notes and concept layout. Prepare: (1) parcel-by-parcel status; (2) required permanent and temporary rights; (3) ownership/authority evidence gaps; (4) access and cable-route dependencies; (5) commercial-term inconsistencies; (6) risks and next actions. Distinguish verified evidence from landowner statements and project assumptions. Flag all matters requiring local legal or survey advice.

### LEVEL 3 - EXPERT PROMPT

Act as a senior renewable-energy development adviser preparing an internal Land-Control Readiness Review for a [capacity] Solar PV and [power/energy] BESS project in [jurisdiction]. Use only the supplied controlled documents. Assess the completeness and internal consistency of the parcel schedule, ownership/authority evidence, title summaries, concept footprint, BESS/substation land, construction and operational access, export cable corridors, temporary works, term sheets, option/lease milestones and decision gates. Deliver an executive recommendation, functional parcel matrix, evidence-confidence table, critical land dependencies, commercial deviation schedule, information request, risk register and conditions for progression. Do not provide legal advice or state that title or enforceability is confirmed. Identify every conclusion requiring validation by local counsel, surveyor, tax adviser or other competent professional.

## 5.19 Common Mistakes

| Mistake                                               | Why It Creates Risk                                                               | Corrective Practice                                                                      |
|-------------------------------------------------------|-----------------------------------------------------------------------------------|------------------------------------------------------------------------------------------|
| Treating cadastral mapping as title proof             | Creates false ownership and boundary certainty.                                   | Use precise evidence labels and obtain professional title/survey verification.           |
| Securing only the generation footprint                | Access, export, drainage or temporary works remain uncontrolled.                  | Prepare a lifecycle rights schedule before negotiation.                                  |
| Negotiating before layout requirements are understood | Commercial commitments may lock in unsuitable areas or insufficient flexibility.  | Issue a controlled land requirements brief and update it through design maturity.        |
| Relying on one spokesperson                           | Other owners, heirs, companies, lenders or tenants may be required.               | Verify decision authority and all required counterparties.                               |
| Comparing headline rent only                          | Indexation, area definition, payments, taxes and extensions change the economics. | Use a full commercial-term model and deviation matrix.                                   |
| Using “land secured” as a binary status               | Hides conditions, route gaps, expiry and evidence uncertainty.                    | Report maturity, confidence, essential parcels and conditions separately.                |
| Uploading sensitive landowner data without controls   | May breach confidentiality, privacy or company policy.                            | Minimise data, control access and use approved AI environments only.                     |
| Allowing AI to draft legal conclusions                | Creates inaccurate or unauthorised advice.                                        | Reserve title, form, tax, enforceability and registration conclusions for professionals. |

*Table 5.21 - Common land-control errors and corrective practices.*

## 5.20 Best Practices

- Maintain one controlled parcel schedule linked to the latest project boundary, layout, route and document register.
- Classify every parcel by function, criticality, replaceability, status, confidence and next decision.
- Verify authority before assuming that a meeting attendee can bind all required parties.
- Secure survey, access and route rights early enough to protect the development programme.
- Preserve alternative layouts and routes until essential land dependencies have credible solutions.
- Use consistent commercial principles and approval limits, with documented reasons for parcel-specific deviations.
- Integrate land actions into the development roadmap, risk register, cost model and investment gates.
- Protect personal and commercially sensitive information through minimisation, permissions and controlled systems.
- Require legal, survey, tax and technical sign-off before irreversible commitment or external representation.

## 5.21 Engineering and Development Review Checklist

| Review Area            | Validation Question                                                                                                   | Check                    |
|------------------------|-----------------------------------------------------------------------------------------------------------------------|--------------------------|
| Project basis          | Does the land brief match the current capacity, layout, BESS, substation, route and construction strategy?            | <input type="checkbox"/> |
| Parcel register        | Are all required permanent, linear, temporary and optional parcels included and uniquely identified?                  | <input type="checkbox"/> |
| Evidence               | Is each ownership, boundary and rights statement classified by source, date and confidence?                           | <input type="checkbox"/> |
| Authority              | Have all necessary owners, co-owners, signatories, lenders, tenants and intermediaries been identified?               | <input type="checkbox"/> |
| Access and route       | Is there a credible controlled strategy from public road to site and from site to connection point?                   | <input type="checkbox"/> |
| BESS/substation        | Are safety, noise, flood, emergency access, expansion and independent control requirements addressed?                 | <input type="checkbox"/> |
| Instrument             | Does the proposed structure support development, assignment, security, construction, operation and full project term? | <input type="checkbox"/> |
| Commercial terms       | Are payments, indexation, area/capacity adjustments, taxes, extensions and restoration modelled consistently?         | <input type="checkbox"/> |
| Third-party issues     | Are mortgages, tenants, easements, occupiers, disputes and other burdens assigned for follow-up?                      | <input type="checkbox"/> |
| Governance             | Are negotiation authority, approvals, meeting records, deviations and decisions controlled?                           | <input type="checkbox"/> |
| AI and confidentiality | Was AI used only within approved controls, with sensitive data minimised and outputs independently verified?          | <input type="checkbox"/> |
| Decision readiness     | Are conditions for land budget, surveys, applications, option exercise and financing explicitly defined?              | <input type="checkbox"/> |

Table 5.22 - Landowner assessment and land-control review checklist.

## 5.22 Recommended Reference Framework

Land-control requirements vary materially by jurisdiction, ownership system, project structure and financing strategy. The current project should use the following categories of authoritative and professional sources:

- Current land registry, cadastral and official property records from the competent authorities.
- Qualified local legal advice on title, ownership, co-ownership, inheritance, leases, easements, registration, tax, security and enforceability.
- Licensed surveyor evidence, controlled coordinate systems, boundary plans and route surveys.
- Applicable planning, environmental, agricultural, forestry, water, heritage and public-rights legislation and official guidance.
- Network-operator and utility requirements affecting substation, cable, access and route rights.
- Current project layouts, access studies, logistics plans, BESS fire/noise assessments and construction method assumptions.
- Approved company land policies, commercial mandates, anti-bribery procedures, data-protection requirements and document-control standards.
- Lender, insurer and investor requirements for assignment, security, direct agreements, cure rights, non-disturbance and remaining term.

### ■ STANDARDS REFERENCE

Confirm the current legal position and official source date before relying on any property or land-right conclusion. A previously valid template may be unsuitable for a different jurisdiction, ownership type or financing structure.

## 5.23 Chapter Summary

Landowner assessment and land-control strategy convert an attractive site into a project that can be surveyed, permitted, financed, built and operated. The process starts with a clear engineering land brief, distinguishes ownership and boundary evidence, maps every permanent and temporary right, assesses counterparties and structures commercial and timing mechanisms around the actual development programme.

The strongest land strategies make critical dependencies visible. They identify essential parcels, alternative routes, access gaps, BESS/substation requirements, third-party interests and evidence confidence before the project becomes committed to one configuration. AI can improve structure, consistency and reporting, but it must remain inside confidentiality controls and cannot replace legal, survey, commercial or ethical judgement.

## 5.24 Key Takeaways

- Land control is a system of interconnected parcels, routes, rights, counterparties and conditions—not a single signed agreement.
- Cadastral, registry, survey, legal and landowner evidence must be distinguished and reconciled.
- The land requirements brief should cover PV, BESS, substation, access, export, drainage, temporary works, security and decommissioning.
- Parcel criticality and replaceability are more informative than total hectares alone.

- Commercial terms should be evaluated as a complete payment and risk architecture, not by headline rent.
- Land status should report maturity, evidence confidence, expiry, conditions and unresolved interfaces.
- Ethical engagement, controlled authority and accurate records are essential to durable relationships.
- AI is effective for evidence organisation, comparison and meeting preparation, but legal conclusions and negotiation decisions remain human responsibilities.
- A project should not be described as land-ready until all essential footprints and routes have a credible, validated control strategy.

#### LOOKING AHEAD - CHAPTER 6

The next chapter focuses on AI-Assisted Satellite and Aerial Image Interpretation. It will show how remote imagery can support parcel reconnaissance, land-use review, access and terrain observations, neighbouring receptors, construction constraints and targeted site-visit planning without replacing GIS analysis, survey or field verification.

### END OF CHAPTER 5

## CHAPTER 6

# AI-Assisted Satellite and Aerial Image Interpretation for Utility-Scale Solar and BESS Projects

---

*From remote imagery to decision-grade site intelligence and targeted field verification*

*Imagery selection, evidence confidence, land-use interpretation, access, terrain, drainage, receptors, change detection and AI-enabled review*

Edition v1.1 | Volume 1

*“Remote imagery does not prove that a site is buildable. It helps the development team ask better questions, focus fieldwork and expose assumptions before they become design commitments.”*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a disciplined method for using satellite, aerial, orthophoto and drone imagery during the development of utility-scale Solar PV and BESS projects. It explains how remote imagery can support site reconnaissance, parcel understanding, land-use classification, access and logistics review, drainage observations, neighbouring-receptor screening, change detection and targeted site-visit planning. The objective is to convert visual observations into traceable engineering questions without confusing imagery interpretation with survey, GIS, environmental, legal or geotechnical evidence.

| Element                  | Purpose                                                                                                                           |
|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------|
| Imagery brief            | Defines the project questions, required resolution, dates, coverage, source and output before review begins.                      |
| Source hierarchy         | Distinguishes satellite, official orthophoto, commercial aerial, drone, LiDAR and informal imagery by capability and reliability. |
| Interpretation framework | Organises observations across land use, access, terrain, hydrology, receptors, utilities, construction and BESS interfaces.       |
| Evidence classification  | Separates visible observation, probable interpretation, unverified inference and required field confirmation.                     |
| Change detection         | Compares imagery dates to identify new roads, buildings, vegetation removal, drainage change, earthworks or land-use transition.  |
| AI workflow              | Accelerates image inventories, observation logs, comparison matrices, field questions and management summaries.                   |
| Field verification       | Converts remote observations into a focused site-visit plan, survey scope and evidence-closure process.                           |

*Table 6.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Define a remote-imagery review brief linked to specific development and engineering decisions.
- Select appropriate imagery sources by date, spatial resolution, spectral characteristics, positional accuracy and legal use constraints.
- Distinguish direct visual observations from interpretations, assumptions and conclusions requiring specialist confirmation.
- Review imagery for land use, access, topography indicators, hydrology, neighbouring receptors, utilities and construction constraints.
- Use multi-date imagery to identify material site changes and stale assumptions.
- Apply AI to organise and compare imagery-derived observations while preventing fabricated certainty.

- Prepare an auditable observation register and targeted field-verification plan.
- Recognise when remote imagery is insufficient and specialist GIS, survey, environmental, geotechnical or legal work is required.

## 6.1 Introduction

Remote imagery is often the first visual evidence available to a development team. Before access is secured, surveys are commissioned or consultants mobilise, satellite and aerial images can reveal the broad character of a site: field patterns, roads, buildings, water features, vegetation, industrial activity, neighbouring receptors and visible signs of recent change.

This early visibility is valuable, but it can also create false confidence. A clear image may appear authoritative even when it is old, seasonally misleading, geometrically distorted, poorly georeferenced or incapable of showing the subsurface, ownership, legal rights, flood frequency, soil strength, habitat significance or true road capacity. Features can be obscured by canopy, shadow, cloud, crop cycles or image compression. Apparent boundaries may not be cadastral boundaries. Apparent tracks may not carry enforceable access rights.

The professional use of imagery therefore requires a controlled chain from question to source, observation, interpretation, confidence, action and verification. Artificial Intelligence can help compare images, classify visible features, structure observation logs and draft field questions. It cannot establish legal title, certify survey accuracy, determine ecological status, prove drainage performance or replace professional review of the original geospatial data.

### ENGINEERING INSIGHT

Treat remote imagery as an evidence layer, not as the project truth. Every material observation should be linked to its source date, location, confidence and required method of confirmation.

## 6.2 What Remote Imagery Can and Cannot Establish

The value of imagery depends on matching the question to the capability of the source. Remote review is strongest when used to identify visible conditions, compare alternatives and direct further investigation. It is weakest when used to make definitive conclusions about matters that are not directly observable.

| Question         | Imagery Can Support                                                                                  | Imagery Cannot Prove                                                                                         |
|------------------|------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------|
| Current land use | Visible crops, grazing patterns, forestry, buildings, disturbed land and broad operational activity. | Legal use rights, tenancy, agricultural classification or future land-use restrictions.                      |
| Access           | Road alignment, apparent width, junction geometry, bridges, gates and visible obstructions.          | Ownership, legal access, pavement strength, bridge capacity or abnormal-load acceptance.                     |
| Terrain          | Broad slope patterns, ridges, depressions, cut/fill evidence and erosion indicators.                 | Design-grade levels, soil profile, rock depth or earthworks quantities without survey and geotechnical data. |



| Question    | Imagery Can Support                                                                         | Imagery Cannot Prove                                                                     |
|-------------|---------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------|
| Hydrology   | Visible watercourses, ponds, channels, wet areas and historical flood marks where apparent. | Flood probability, drainage capacity, groundwater level or hydraulic performance.        |
| Environment | Woodland, hedgerows, wetlands, habitat mosaics and visible protected-use indicators.        | Ecological value, species presence, legal protection or seasonal sensitivity.            |
| Receptors   | Buildings, roads, settlements, recreation areas and industrial neighbours.                  | Occupancy, ownership, sensitivity, noise criteria or stakeholder position.               |
| Utilities   | Some overhead lines, substations, pipelines corridors and service tracks.                   | Underground utilities, capacity, ownership, protection zones or connection availability. |

Table 6.2 - Appropriate and inappropriate conclusions from remote imagery.

#### COMMON MISTAKE

Do not convert “not visible” into “not present.” A feature may be hidden, underground, seasonal, outside the image date or below the source resolution.

## 6.3 Imagery Sources and Their Development Uses

No single image source is suitable for every task. Development teams should maintain an imagery inventory that records provider, acquisition date, nominal resolution, coordinate reference system, processing level, coverage, licence restrictions and known limitations.

| Source Type                          | Typical Strength                                                                 | Typical Limitation                                                          | Best Development Use                                                                   |
|--------------------------------------|----------------------------------------------------------------------------------|-----------------------------------------------------------------------------|----------------------------------------------------------------------------------------|
| Open satellite imagery               | Frequent regional coverage and multi-date comparison.                            | Moderate spatial resolution; cloud and seasonal effects.                    | Regional screening, vegetation and land-use change, broad hydrology and context.       |
| Commercial high-resolution satellite | Improved detail and recent targeted acquisition.                                 | Cost, licence restrictions, off-nadir distortion and variable availability. | Parcel-level reconnaissance, route review and recent change confirmation.              |
| Official orthophoto                  | Geometrically corrected, often high resolution and suitable for mapping context. | Update frequency varies; local coverage and terms differ.                   | Site and route interpretation, receptor mapping and controlled GIS overlays.           |
| Aerial survey photography            | High detail over defined areas and potential stereo analysis.                    | May require specialist processing and acquisition planning.                 | Detailed terrain, infrastructure and construction-condition review.                    |
| Drone imagery                        | Very high resolution, flexible capture and repeatability.                        | Requires lawful operation, access, weather, ground control and processing.  | Site inspection, progress records, detailed feature mapping and targeted verification. |

| Source Type                     | Typical Strength                                                         | Typical Limitation                                                | Best Development Use                                                      |
|---------------------------------|--------------------------------------------------------------------------|-------------------------------------------------------------------|---------------------------------------------------------------------------|
| LiDAR / elevation products      | Surface and terrain elevation, canopy and feature-height information.    | Point density, classification, datum and date must be understood. | Slope, drainage, earthworks screening, vegetation and visibility studies. |
| Street-level / informal imagery | Useful visual context for roads, junctions and public-facing interfaces. | Uncontrolled date, perspective, completeness and usage rights.    | Preliminary logistics questions only; never a substitute for inspection.  |

Table 6.3 - Remote-imagery sources and appropriate applications.

## 6.4 Defining the Imagery Review Brief

Image review should begin with a written brief. Without one, reviewers tend to collect attractive screenshots rather than evidence linked to decisions. The brief should identify the site, alternatives, project configuration, decision stage, imagery dates and the questions that must be answered.



Figure 6.1 - Controlled remote-imagery review workflow.

| Brief Component    | Required Content                                                                                                  |
|--------------------|-------------------------------------------------------------------------------------------------------------------|
| Project basis      | Capacity, technology, approximate footprint, BESS and substation concept, export route and development stage.     |
| Review boundary    | Main site, access approaches, grid route, neighbouring receptors, hydrological catchment and alternative parcels. |
| Decision questions | Examples: fatal flaw, comparative suitability, access feasibility, survey planning or acquisition support.        |
| Image requirements | Target dates, minimum resolution, seasonal conditions, historical comparison and acceptable source hierarchy.     |
| Output format      | Annotated map, observation register, issue matrix, photo sheet, route notes and field-action list.                |
| Evidence rules     | Source citation, confidence scale, no-go conclusions, assumptions and specialist escalation requirements.         |
| Data governance    | Licence, confidentiality, personal data, security-sensitive infrastructure and approved AI environment.           |

Table 6.4 - Minimum contents of an imagery review brief.

## 6.5 Source Validation and Image Metadata

A visual interpretation is only as reliable as the source record behind it. Every image used for a material conclusion should be traceable to acquisition metadata or the best available provider information.

| Metadata Field          | Why It Matters                                                                      | Review Question                                                                |
|-------------------------|-------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Acquisition date        | Determines whether the image represents current conditions and relevant season.     | Could land use, vegetation, construction or access have changed since capture? |
| Spatial resolution      | Controls the minimum feature size that can be interpreted reliably.                 | Is the source detailed enough for the stated observation?                      |
| Geometric accuracy      | Affects alignment with parcels, routes, contours and other GIS layers.              | Is it appropriate for reconnaissance or for measurement?                       |
| Viewing geometry        | Off-nadir or oblique images can shift tall features and distort apparent distances. | Are buildings, trees or slopes displaced by perspective?                       |
| Cloud, shadow and haze  | Can hide or imitate water, vegetation and surface condition.                        | Are key areas obscured or ambiguous?                                           |
| Processing level        | Orthorectification, mosaicking and enhancement affect interpretation.               | Has the image been corrected, resampled or colour-enhanced?                    |
| Licence and attribution | Controls whether imagery can be stored, shared, published or used commercially.     | Are project use, derivative annotations and distribution permitted?            |

*Table 6.5 - Image metadata required for defensible interpretation.*

### BEST PRACTICE

Place the source name and acquisition date directly on every annotated image. A screenshot without traceable metadata should not carry a material project conclusion.

## 6.6 Establishing an Evidence and Confidence Framework

Remote-image reviews should separate what is directly visible from what is inferred. This distinction is essential when AI tools are involved because models may express uncertain interpretation in confident language.

| Classification | Definition                                                     | Example                                                            | Required Treatment                                       |
|----------------|----------------------------------------------------------------|--------------------------------------------------------------------|----------------------------------------------------------|
| Observed       | Feature is directly visible at the stated date and resolution. | A surfaced road and bridge are visible on the official orthophoto. | Record source, date, location and image reference.       |
| Interpreted    | A probable meaning is assigned to visible evidence.            | Linear dark feature is interpreted as a drainage ditch.            | State interpretation and confidence; seek corroboration. |

| Classification | Definition                                                  | Example                                               | Required Treatment                                         |
|----------------|-------------------------------------------------------------|-------------------------------------------------------|------------------------------------------------------------|
| Inferred       | Conclusion extends beyond what the image directly supports. | Road is assumed suitable for transformer delivery.    | Do not rely; assign inspection or engineering study.       |
| Not observable | Question cannot be answered from the source.                | Underground utilities or legal access rights.         | Use another evidence source or professional investigation. |
| Contradictory  | Different dates or sources show inconsistent conditions.    | Water feature visible in winter but absent in summer. | Retain both records and investigate seasonality or change. |

Table 6.6 - Evidence classification for imagery-derived findings.

| Confidence | Typical Basis                                                                                    | Permitted Use                                                                         |
|------------|--------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
| High       | Clear feature, suitable resolution, recent source and corroboration from another evidence layer. | Can guide planning, but material design still requires appropriate professional data. |
| Medium     | Feature is visible but interpretation, date or geometry introduces uncertainty.                  | Use to prioritise questions, surveys and alternatives.                                |
| Low        | Feature is ambiguous, source is old/poor or conclusion depends on inference.                     | Do not rely for commitment; field or specialist confirmation required.                |

Table 6.7 - Confidence scale for remote-image observations.

## 6.7 Land Use, Parcel Pattern and Operational Activity

Imagery can reveal how land is physically used, how fields are accessed and whether operational activity may conflict with a proposed layout. Reviewers should avoid assuming that visible field edges are ownership boundaries or that apparently unused land is available.

| Visible Indicator                  | Possible Development Relevance                                                                  | Verification Required                                                      |
|------------------------------------|-------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------|
| Field boundaries and hedgerows     | May affect layout efficiency, ecology, drainage, access and landowner interfaces.               | Cadastral data, ecology survey, survey control and land negotiations.      |
| Crop patterns                      | Indicate active agriculture, irrigation, seasonal access and potential compensation interfaces. | Landowner/tenant records, agricultural assessment and seasonal site visit. |
| Forestry or scrub                  | May imply clearance, habitat, fire, visibility and ground-condition constraints.                | Forestry/ecology review, permitting and site inspection.                   |
| Buildings and compounds            | Can create exclusion zones, demolition issues, occupants, contamination or reuse opportunities. | Ownership, occupancy, structural, environmental and planning checks.       |
| Quarries, fill or disturbed ground | May indicate variable ground, contamination, heavy traffic or prior excavation.                 | Historical land-use research, geotechnical and contamination studies.      |

| Visible Indicator           | Possible Development Relevance                                                 | Verification Required                           |
|-----------------------------|--------------------------------------------------------------------------------|-------------------------------------------------|
| Irrigation infrastructure   | Can affect routes, drainage, continued operations and landowner expectations.  | Utility/operator information and field mapping. |
| Seasonal livestock activity | May influence fencing, access, vegetation management and coexistence strategy. | Landowner engagement and operational plan.      |

Table 6.8 - Land-use observations and required confirmation.

## 6.8 Access, Roads and Construction Logistics

Remote imagery is highly useful for planning access reconnaissance. It can identify candidate approaches, junctions, bridges, settlements, gates, sharp bends, narrow corridors and alternative routes. It cannot determine structural capacity or legal availability.

| Review Area                | Remote Observation                                                                                  | Engineering Question                                                                              |
|----------------------------|-----------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|
| Public-road approach       | Road class, urban sections, junctions, roundabouts, roadside development and apparent restrictions. | Can abnormal loads and construction traffic reach the site without unacceptable works or impacts? |
| Final site approach        | Track continuity, width, surface, gates, vegetation, water crossings and gradients.                 | What upgrades, rights, drainage and maintenance are required?                                     |
| Bridge / culvert crossings | Visible span, alignment, approach geometry and potential bypass options.                            | What capacity, condition and authority approvals must be confirmed?                               |
| Internal circulation       | Field entrances, headlands, narrow strips, watercourses and potential loop routes.                  | Can construction and emergency vehicles circulate safely?                                         |
| Laydown and delivery areas | Open, level or previously disturbed areas near access and compounds.                                | Are temporary rights, bearing capacity, drainage and turning space sufficient?                    |
| Alternative routes         | Secondary roads or neighbouring parcel links.                                                       | Can route resilience reduce dependence on one critical interface?                                 |

Table 6.9 - Image-based logistics review questions.

### COMMON MISTAKE

A road that appears wide enough on imagery may contain weak bridges, overhead restrictions, buried services, local traffic constraints or legal limitations. Do not issue transport feasibility from imagery alone.

## 6.9 Terrain, Earthworks and Surface-Condition Indicators

Two-dimensional imagery can suggest terrain character through shadows, contour overlays, field patterns, erosion, retaining features and drainage lines. Stronger assessment requires elevation data, topographic survey and geotechnical investigation.

| Indicator                        | Possible Interpretation                                                         | Required Follow-Up                                                |
|----------------------------------|---------------------------------------------------------------------------------|-------------------------------------------------------------------|
| Closely spaced contour bands     | Steeper terrain, increased grading, tracker articulation and access challenges. | Digital terrain model review and topographic survey.              |
| Terracing or retaining walls     | Historic slope modification and constrained machinery movement.                 | Field inspection, structural review and survey.                   |
| Erosion gullies                  | Concentrated runoff, erodible soils or unstable drainage paths.                 | Hydrology, erosion-control and geotechnical assessment.           |
| Patchy vegetation / exposed soil | Shallow soil, rock, compaction, disturbance or seasonal stress.                 | Geotechnical walkover, boreholes/trial pits and land-use history. |
| Existing cut/fill platforms      | Potential compound or laydown opportunity, but variable fill may be present.    | Survey, contamination and ground investigation.                   |
| Long uninterrupted slopes        | Higher runoff velocities, grading and row-to-row constraints.                   | Tracker/fixed-tilt suitability modelling and drainage concept.    |

Table 6.10 - Terrain and surface-condition indicators visible remotely.

## 6.10 Hydrology, Drainage and Flood Indicators

Multi-date imagery can help identify persistent and seasonal water features, drainage networks, ponding, floodplain use, erosion and changes to upstream catchments. The findings should guide hydrological study rather than replace it.

| Observation                             | Potential Significance                                                    | Confirmation Method                                                              |
|-----------------------------------------|---------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| Visible watercourse or drainage channel | Setbacks, crossings, permitting, erosion and maintenance access.          | Official mapping, field survey, hydraulic assessment and authority consultation. |
| Dark or saturated ground                | Possible ponding, wetland, irrigation, soil moisture or image shadow.     | Seasonal comparison, site visit, soils/ecology and drainage review.              |
| Ponds / reservoirs                      | Water rights, biodiversity, flood storage, safety and access constraints. | Ownership, hydrology, ecology and operational information.                       |
| Debris or sediment fans                 | High-energy runoff, erosion or culvert overtopping.                       | Catchment review, field evidence and drainage modelling.                         |
| Recent channel works                    | Changed flood paths, maintenance or third-party interventions.            | Current authority records and site verification.                                 |
| Downstream receptors                    | Potential consequence of altered runoff or failure of drainage controls.  | Catchment mapping, flood-risk assessment and stakeholder review.                 |

Table 6.11 - Hydrology observations and escalation requirements.

## 6.11 Environmental and Social Receptors

Imagery can support the early identification of visible ecological and social interfaces. It should be used to design surveys and engagement, not to determine environmental significance or stakeholder acceptability.

| Receptor                     | Visible Clues                                                           | Development Question                                                                     |
|------------------------------|-------------------------------------------------------------------------|------------------------------------------------------------------------------------------|
| Woodland / hedgerows         | Continuous canopy, mature trees, corridors and isolated specimens.      | What habitat, setback, root-protection, fire and visual constraints apply?               |
| Wetlands / riparian zones    | Water-tolerant vegetation, channels, marsh patterns and seasonal water. | What ecological and hydrological investigations are required?                            |
| Residential receptors        | Houses, farms, villages and new development.                            | What noise, glint/glare, traffic, fire, visual and engagement issues require assessment? |
| Cultural / heritage features | Historic structures, earthworks, cemeteries or traditional landscapes.  | What official records and specialist studies are required?                               |
| Recreation / public access   | Trails, sports areas, viewpoints and informal tracks.                   | Are public rights, safety, amenity or route diversions relevant?                         |
| Industrial neighbours        | Factories, quarries, warehouses, pipelines and utility compounds.       | Are there hazardous, access, dust, vibration, security or cumulative interfaces?         |

Table 6.12 - Visible receptors and development questions.

## 6.12 Grid, Utilities and Linear Infrastructure

Remote imagery can clarify the physical context of a connection opportunity and potential route, including overhead lines, substations, roads, railways, waterways and obvious utility corridors. It cannot establish electrical capacity or underground-service status.

| Feature                  | Imagery Contribution                                                             | Further Evidence                                                                   |
|--------------------------|----------------------------------------------------------------------------------|------------------------------------------------------------------------------------|
| Substation               | Location, apparent footprint, access, surrounding land and visible line entries. | Network data, ownership, voltage, capacity, expansion and protection requirements. |
| Overhead line            | Alignment, tower positions, crossings and potential route interfaces.            | Voltage, conductor, easements, clearances, outage and connection studies.          |
| Cable corridor           | Broad route alternatives and visible obstacles.                                  | Topographic, utility, environmental, land-rights and constructability studies.     |
| Rail / motorway crossing | Crossing location and approach context.                                          | Authority standards, method, permits, possessions and cost.                        |
| Pipeline / utility strip | Possible corridor from vegetation or maintenance track patterns.                 | Official utility searches, operator records and field detection.                   |

| Feature            | Imagery Contribution                 | Further Evidence                                                    |
|--------------------|--------------------------------------|---------------------------------------------------------------------|
| Telecommunications | Visible towers and some line routes. | Service availability, ownership, fibre route and resilience design. |

Table 6.13 - Remote review of grid and utility interfaces.

## 6.13 BESS-Specific Image Interpretation

BESS sites concentrate safety, access, drainage, noise, security and emergency-response requirements within a relatively small footprint. Remote imagery can screen candidate compounds and surrounding receptors, but the final design requires current standards, authority engagement and specialist studies.

| BESS Topic               | Remote Review                                                               | Field / Specialist Confirmation                                                   |
|--------------------------|-----------------------------------------------------------------------------|-----------------------------------------------------------------------------------|
| Compound location        | Flat or disturbed land, separation from PV rows, substation and access.     | Survey levels, geotechnical capacity, fire strategy and layout design.            |
| Emergency access         | Route continuity, turning possibilities and alternative approach.           | Fire-authority requirements, road geometry, load capacity and all-weather access. |
| Receptors                | Nearby houses, workplaces, roads and public areas.                          | Occupancy, noise limits, risk criteria and engagement.                            |
| Drainage / flood         | Low areas, channels, ponds and upstream catchment.                          | Flood-risk and drainage assessment; platform level and containment design.        |
| Vegetation / wildfire    | Woodland, scrub, agricultural burning or fuel continuity.                   | Wildfire assessment, vegetation management and emergency planning.                |
| Expansion / augmentation | Adjacent usable space and construction access.                              | Land rights, phasing, electrical design and operating constraints.                |
| Security                 | Public approaches, overlooking, adjacent activity and perimeter complexity. | Security risk assessment, lighting, surveillance and access control.              |

Table 6.14 - BESS-focused remote imagery review.

## 6.14 Multi-Date Review and Change Detection

A single image captures one moment. Development decisions often require understanding how the site changes over time. Historical and recent imagery can reveal changes that affect baseline assumptions, surveys, land negotiations and design.




Figure 6.2 - Multi-date imagery and change-detection workflow.



| Detected Change                | Possible Project Impact                                                 | Action                                                           |
|--------------------------------|-------------------------------------------------------------------------|------------------------------------------------------------------|
| New building or residence      | Receptor, setback, land-control, noise, glint/glare or planning impact. | Update receptor register and verify occupancy/planning status.   |
| Road upgrade or closure        | Changed logistics route, access rights or traffic impacts.              | Confirm current road authority information and inspect route.    |
| Vegetation clearance or growth | Changed habitat, fire, shading, visual or survey baseline.              | Update ecology/forestry scope and field verification.            |
| Drainage or pond alteration    | Changed flood path, irrigation, wetland or land use.                    | Review current hydrology and ownership/authority records.        |
| Earthworks or quarry activity  | Ground risk, contamination, dust, traffic or opportunity for platforms. | Update land-use history and commission specialist investigation. |
| New utility corridor           | Crossing, easement, setback, route conflict or connection opportunity.  | Obtain utility information and update constraint mapping.        |

*Table 6.15 - Material changes identifiable through multi-date imagery.*

#### ENGINEERING INSIGHT

Change detection must distinguish real site change from differences caused by season, sun angle, sensor, resolution, processing or image alignment.

## 6.15 Measurement, Scale and Positional Caution

Web-map measurements and screenshots are useful for preliminary questions, but they should not be treated as survey. Positional error can arise from source georeferencing, reprojection, off-nadir viewing, terrain, mosaicking and display scale.

| Use                       | Acceptable Preliminary Application                            | Do Not Use For                                                          |
|---------------------------|---------------------------------------------------------------|-------------------------------------------------------------------------|
| Distance measurement      | Broad comparison of route alternatives or receptor proximity. | Final cable length, legal setback, road geometry or bill of quantities. |
| Area measurement          | Early gross-area and alternative-parcel comparison.           | Lease boundary, net developable area or compensation calculation.       |
| Feature coordinates       | Navigation and desktop issue marking.                         | Construction set-out, cadastral conclusion or survey control.           |
| Elevation from public DEM | Regional slope and drainage screening.                        | Foundation levels, detailed grading or flood platform design.           |
| Visual boundary tracing   | Approximate review of fields and physical occupation.         | Ownership boundary or enforceable rights.                               |

*Table 6.16 - Appropriate limits for imagery-derived measurements.*

## 6.16 The Structured Observation Register

The principal deliverable from remote review should be an observation register linked to annotated images and project actions. This prevents findings from becoming disconnected comments in email or presentation slides.

| Field            | Required Entry                                                                                       |
|------------------|------------------------------------------------------------------------------------------------------|
| Observation ID   | Unique reference linked to image annotation and project register.                                    |
| Location         | Coordinates, parcel/route reference or map grid sufficient for follow-up.                            |
| Source           | Provider, image name, acquisition date, resolution and licence/attribution note.                     |
| Observation      | Neutral description of what is directly visible.                                                     |
| Interpretation   | Possible meaning, clearly separated from the observation.                                            |
| Confidence       | High, medium or low with a short justification.                                                      |
| Materiality      | Potential effect on land, permitting, grid, design, cost, programme, safety or stakeholder outcomes. |
| Required action  | Field check, survey, specialist study, authority query, land question or design response.            |
| Owner / due date | Responsible person and target closure milestone.                                                     |
| Closure evidence | Photo, survey, report, official record, decision or revised design reference.                        |

Table 6.17 - Minimum remote-imagery observation-register fields.

## 6.17 AI-Assisted Image Review Workflow

AI can support remote-image interpretation when the workflow is designed to preserve source traceability and human judgement. The model should be asked to describe visible features before interpreting them, identify uncertainty and avoid conclusions outside the image capability.



Figure 6.3 - Human-controlled AI image-review workflow.

| Workflow Step   | AI Contribution                                                                     | Professional Control                           |
|-----------------|-------------------------------------------------------------------------------------|------------------------------------------------|
| Image inventory | Create structured list of files, dates, coverage and metadata supplied by the user. | Verify metadata against the original provider. |

| Workflow Step        | AI Contribution                                                                              | Professional Control                                                      |
|----------------------|----------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|
| Feature description  | Describe visible roads, buildings, vegetation, water, terrain indicators and infrastructure. | Check image quality and reject hallucinated or misidentified features.    |
| Comparison           | Summarise differences between dates, sites or routes.                                        | Confirm alignment, season and sensor differences before calling a change. |
| Observation register | Draft neutral observations, confidence and questions.                                        | Engineer assigns materiality, action and final wording.                   |
| Field plan           | Convert unresolved observations into inspection points and photo requirements.               | HSE, access, specialists and site logistics remain human decisions.       |
| Management summary   | Condense findings into decision-relevant themes.                                             | Ensure no unverified inference is presented as fact.                      |

Table 6.18 - Appropriate division of work between AI and professionals.

#### AI TIP

Require the model to use phrases such as “visible observation,” “possible interpretation,” and “not determinable from the image.” Confidence language should never be allowed to substitute for evidence.

## 6.18 Prompt Design for Remote-Imagery Tasks

A strong prompt should define the professional role, project context, image source, acquisition date, question, output structure and prohibited conclusions. The model should not be asked to infer legal, ecological, geotechnical or electrical facts from pixels.

| Prompt Component       | Example Requirement                                                                                         |
|------------------------|-------------------------------------------------------------------------------------------------------------|
| Role                   | Act as a utility-scale Solar PV and BESS development engineer supporting desktop site reconnaissance.       |
| Context                | State capacity, project stage, location context, candidate parcels, BESS and connection concept.            |
| Inputs                 | List each image, date, resolution, orientation, annotations and supporting GIS layers.                      |
| Task                   | Review access, land use, receptors, drainage indicators, utilities and construction constraints.            |
| Evidence rules         | Separate direct observation from interpretation; state confidence and image limitations.                    |
| Prohibited conclusions | Do not determine ownership, habitat status, flood level, soil capacity, road capacity or grid availability. |

| Prompt Component | Example Requirement                                                                                  |
|------------------|------------------------------------------------------------------------------------------------------|
| Deliverables     | Observation register, annotated-feature list, priority risks, data gaps and field-verification plan. |

Table 6.19 - Consultant-grade prompt structure for imagery review.

**PROFESSIONAL PROMPT**

You are acting as a Senior Utility-Scale Solar PV and BESS Development Engineer. Review the supplied orthophotos and satellite images for a proposed 300 MWac Solar PV project with a 150 MW / 300 MWh BESS. For each image, record source and acquisition date, describe only visible features, and separately identify possible interpretations. Assess apparent land use, access routes, terrain and erosion indicators, water features, neighbouring receptors, overhead infrastructure, construction constraints and BESS compound considerations. Assign confidence as high, medium or low and explain why. Do not make conclusions about ownership, legal access, ecological status, flood level, soil capacity, road strength or grid capacity. Produce: (1) executive summary, (2) observation register, (3) material risks and opportunities, (4) inconsistencies between image dates, (5) required specialist studies, and (6) prioritised site-visit checklist.

## 6.19 Worked Example: 300 MWac Solar PV + 150 MW / 300 MWh BESS

A developer is evaluating a 610-hectare agricultural area and two export-route alternatives. The desk review includes a three-year-old official orthophoto, recent commercial satellite imagery, a public elevation model and historical satellite images covering wet and dry seasons. No site visit has yet been completed.

| Review Question  | Remote Observation                                                                                                | Initial Interpretation                                                                                     | Confidence / Action                                                              |
|------------------|-------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| Primary access   | A surfaced regional road connects to a narrow local road; two small bridges are visible before the site entrance. | Route may be suitable for light vehicles but bridge and turning constraints could affect heavy deliveries. | Medium. Commission route inspection, swept-path review and bridge data request.  |
| Eastern parcels  | Winter images show repeated dark linear features and ponding; dry-season image shows crop use.                    | Seasonal drainage or irrigation may constrain layout and earthworks.                                       | Medium. Hydrology walkover, drainage mapping and landowner questions.            |
| Western ridge    | Elevation model and shadows indicate stronger slopes and erosion gullies.                                         | Tracker articulation, grading and drainage risk may be higher than gross area suggests.                    | High for slope presence; survey and geotechnical confirmation required.          |
| BESS candidate A | Flat disturbed ground near substation, but a residence is visible approximately 280 m away.                       | Constructability may be favourable; noise, fire and stakeholder interface require study.                   | High for visible receptor. Add receptor survey and compare alternative compound. |

| Review Question  | Remote Observation                                                                     | Initial Interpretation                                                                       | Confidence / Action                                |
|------------------|----------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|----------------------------------------------------|
| BESS candidate B | Agricultural parcel farther from residences but crossed by a visible drainage channel. | Lower receptor exposure but potentially higher drainage and cable-route complexity.          | Medium. Hydrology and route review.                |
| Export route 1   | Shorter route crosses five fields and one watercourse.                                 | Land and environmental interfaces may outweigh shorter length.                               | Medium. Parcel and crossing study.                 |
| Export route 2   | Longer route broadly follows an existing road and overhead-line corridor.              | Potentially easier access, but utility clearances and road authority interfaces are unknown. | Medium. Utility and authority consultation.        |
| Recent change    | Latest imagery shows a new warehouse and access road near the northern boundary.       | Baseline receptor, traffic and land assumptions are stale.                                   | High. Update stakeholder and planning information. |

*Table 6.20 - Worked-example imagery observation register.*

The review does not select a final layout. It narrows the engineering questions and changes the order of work. The development team decides to inspect the primary access and both bridges first, include wet-season evidence in the hydrology scope, retain two BESS alternatives, and avoid committing to the western ridge until topographic and earthworks screening is complete.

| Priority | Field Verification Task                                                                                    | Reason                                                           |
|----------|------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------|
| 1        | Drive and photograph the complete abnormal-load approach, bridge crossings, junctions and site entrances.  | Could create a fatal logistics constraint or major upgrade cost. |
| 2        | Walk eastern drainage features and record culverts, channels, ponding evidence, outfalls and field levels. | Affects usable area, permitting, drainage and layout.            |
| 3        | Inspect both BESS alternatives, neighbouring receptors, emergency approaches and vegetation conditions.    | Required for safety, noise, flood and stakeholder comparison.    |
| 4        | Ground-truth the western ridge, erosion gullies and apparent rock/exposed-soil areas.                      | Affects grading, foundations, roads and tracker suitability.     |
| 5        | Verify both export-route alternatives, crossings, land occupation and existing utility interfaces.         | Required before route strategy and land priorities are fixed.    |
| 6        | Confirm the new warehouse activity, boundary relationship and traffic pattern.                             | Updates project baseline and stakeholder register.               |

*Table 6.21 - Targeted site-visit priorities generated from the remote review.*

## 6.20 Converting Findings into a Site-Visit Plan

Every unresolved material observation should become a field question, survey requirement or specialist action. A site visit is most effective when the team knows exactly what evidence must be captured and how it will close the remote-review issue.

| Remote Issue              | Field Instruction                                                                              | Required Evidence                                                         |
|---------------------------|------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|
| Possible drainage channel | Inspect upstream/downstream continuity and crossings after recent rainfall where safe.         | Geotagged photos, dimensions, flow evidence, levels and hydrology notes.  |
| Narrow access route       | Record carriageway, shoulders, junctions, overhead constraints, bridges and passing locations. | Route photo log, measurements, asset references and logistics actions.    |
| Potential receptor        | Confirm building use from lawful public/site observation and stakeholder records.              | Receptor ID, location, type, occupancy evidence and assessment action.    |
| Apparent disturbed ground | Inspect fill, waste, excavation, staining, structures and current use.                         | Photo log, land-use interview and geotechnical/contamination scope.       |
| BESS wildfire interface   | Record fuel types, slope, access, water availability and neighbouring activities.              | Vegetation map, photos and fire-risk specialist input.                    |
| Route crossing            | Inspect watercourse, road, rail or utility crossing and available working area.                | Dimensions, photos, authority/owner references and constructability note. |

Table 6.22 - Translating imagery observations into field evidence.

## 6.21 Common Mistakes

| Mistake                                  | Why It Creates Risk                                                  | Better Practice                                              |
|------------------------------------------|----------------------------------------------------------------------|--------------------------------------------------------------|
| Using an undated screenshot              | Current condition and evidence traceability cannot be established.   | Record source, date, resolution and coverage.                |
| Treating field edges as legal boundaries | Physical occupation may not match title or cadastral data.           | Use official property evidence and survey.                   |
| Calling an image interpretation a fact   | Uncertainty is hidden and decisions may rely on a misclassification. | Separate observed, interpreted, inferred and not observable. |
| Assuming absence from imagery            | Small, hidden, underground or seasonal features may be missed.       | State the detection limit and assign confirmation.           |
| Measuring with survey-level confidence   | Image geometry and display tools may not support precise dimensions. | Use measurements only for preliminary comparison.            |
| Ignoring image date differences          | Apparent change may be sensor/season; real change may be missed.     | Align sources and classify change confidence.                |

| Mistake                                     | Why It Creates Risk                                                 | Better Practice                                                |
|---------------------------------------------|---------------------------------------------------------------------|----------------------------------------------------------------|
| Allowing AI to infer specialist conclusions | Models may fabricate ecology, flood, legal or ground certainty.     | Use prohibited-conclusion rules and professional review.       |
| Failing to close findings                   | Useful observations remain disconnected from surveys and decisions. | Maintain owner, due date and closure evidence in the register. |

Table 6.23 - Common remote-imagery review mistakes and controls.

## 6.22 Best Practices

- Begin with decision questions and an imagery brief rather than unstructured browsing.
- Use the best available original imagery and retain acquisition metadata and usage rights.
- Compare multiple dates and seasons where drainage, vegetation or land use may vary.
- Describe visible evidence neutrally before assigning an interpretation.
- Use confidence and materiality separately: a clearly visible feature may have uncertain project impact.
- Maintain annotated images and a structured observation register with unique references.
- Cross-check imagery against cadastral, topographic, environmental, grid, utility and land evidence.
- Use AI to organise and challenge the review, not to create certainty beyond the pixels.
- Convert every material uncertainty into a field, survey, authority, land or specialist action.
- Update the imagery baseline when development, design or external conditions materially change.

## 6.23 Engineering and Development Review Checklist

| Review Area  | Validation Question                                                                            | Check                    |
|--------------|------------------------------------------------------------------------------------------------|--------------------------|
| Brief        | Are the project decision, review boundary, image requirements and outputs clearly defined?     | <input type="checkbox"/> |
| Source       | Are provider, acquisition date, resolution, geometry, processing and licence recorded?         | <input type="checkbox"/> |
| Coverage     | Do the images cover the site, access, grid route, catchment, receptors and alternatives?       | <input type="checkbox"/> |
| Evidence     | Are observations separated from interpretations, inferences and non-observable matters?        | <input type="checkbox"/> |
| Confidence   | Is confidence justified by image quality, date and corroboration?                              | <input type="checkbox"/> |
| Change       | Have material differences between dates been checked for season, sensor and alignment effects? | <input type="checkbox"/> |
| Measurements | Are preliminary image measurements clearly distinguished from survey data?                     | <input type="checkbox"/> |

| Review Area  | Validation Question                                                                                           | Check                    |
|--------------|---------------------------------------------------------------------------------------------------------------|--------------------------|
| PV / civil   | Have land use, access, slope, erosion, drainage and constructability indicators been reviewed?                | <input type="checkbox"/> |
| BESS         | Have receptors, access, flood, vegetation, security and expansion interfaces been screened?                   | <input type="checkbox"/> |
| Grid / route | Have substations, lines, corridors, crossings and route alternatives been assessed without assuming capacity? | <input type="checkbox"/> |
| AI control   | Were prohibited conclusions, confidentiality, source traceability and human verification enforced?            | <input type="checkbox"/> |
| Closure      | Does each material issue have an owner, action, due date and required closure evidence?                       | <input type="checkbox"/> |

Table 6.24 - Satellite and aerial image interpretation review checklist.

## 6.24 Prompt Toolkit

### Level 1 - Quick Prompt

#### QUICK PROMPT

Review this dated aerial image of a proposed utility-scale Solar PV and BESS site. List only the visible features relevant to land use, access, water, neighbouring receptors, utilities and construction. Separate direct observations from possible interpretations, state uncertainty, and provide five questions for the site visit. Do not make legal, ecological, geotechnical, flood or grid-capacity conclusions.

### Level 2 - Professional Prompt

#### PROFESSIONAL PROMPT

Act as a Senior Solar PV and BESS Development Engineer. Using the supplied image set, metadata, preliminary site boundary and route options, prepare a structured remote-imagery review. Record source/date, classify each item as observed, interpreted, inferred or not observable, assign confidence, and assess potential materiality for land, permitting, access, civil design, hydrology, environment, BESS, grid route, cost and programme. Produce an observation register, image-date comparison, specialist data-gap list and prioritised site-visit plan. Do not infer ownership, legal rights, habitat status, road strength, flood levels, soil capacity or network capacity.



## Level 3 - Expert Prompt

### EXPERT PROMPT

You are acting as the Lead Owner's Engineer supporting acquisition-stage technical due diligence for a utility-scale Solar PV and co-located BESS project. Review all supplied satellite, orthophoto, aerial, drone and elevation products together with their metadata and supporting GIS layers. Establish an evidence hierarchy; identify source conflicts and stale baselines; evaluate land-use pattern, access/logistics, terrain and earthworks indicators, hydrology, environmental/social receptors, neighbouring development, utilities, substation context, export-route alternatives and BESS-specific safety/operational interfaces. For every finding, provide image reference, acquisition date, neutral observation, interpretation, confidence, potential project consequence, required verification, responsible discipline and recommended timing. Include a change-detection summary, fatal-flaw candidates, site-visit route, photo schedule, survey scope and executive recommendation. Explicitly identify all matters that cannot be determined from imagery and require survey, legal, environmental, geotechnical, grid or authority confirmation.

## 6.25 Recommended Reference Framework

Remote-imagery work should use current, authoritative and properly licensed sources appropriate to the jurisdiction and decision. The following reference categories should be incorporated into the project evidence framework:

- Official national or regional orthophoto, cadastral-viewing and mapping services, including acquisition-date and accuracy documentation.
- Open satellite programmes and provider metadata for spatial, spectral, temporal and processing characteristics.
- Commercial satellite or aerial imagery licence terms, acquisition specifications and positional-accuracy statements.
- Current topographic, digital terrain, digital surface and LiDAR products from competent authorities or qualified providers.
- Applicable drone-operation, privacy, data-protection, security and airspace requirements for project-specific capture.
- Official flood, watercourse, environmental, heritage, forestry, planning, transport and utility datasets.
- Current cadastral/title evidence and licensed survey information for property and boundary matters.
- Project document-control, GIS, cybersecurity, confidentiality and AI-governance procedures.

### STANDARDS REFERENCE

Always work from the original source and current metadata where possible. A web viewer or presentation screenshot may be useful for communication but should not replace the controlled geospatial dataset used for analysis.

## 6.26 Chapter Summary

Satellite and aerial imagery provide a fast, scalable and valuable view of a development opportunity. They can reveal visible land use, access patterns, terrain indicators, water features,

receptors, infrastructure and recent change before expensive fieldwork begins. Their value is greatest when the review is tied to specific decisions and converted into targeted verification.

The professional method is to define the imagery brief, validate sources, distinguish observation from interpretation, assign confidence, compare multiple dates, record findings in an auditable register and close material uncertainties through site inspection, survey, specialist study or official evidence. AI can accelerate description, comparison and reporting, but it must not be allowed to infer facts outside the image capability or obscure uncertainty behind fluent language.

## 6.27 Key Takeaways

- Remote imagery is an evidence layer, not proof that a site is buildable or bankable.
- Source date, resolution, geometry, processing and licence are part of every material finding.
- Direct observation must be separated from interpretation, inference and matters that are not observable.
- Multi-date imagery can expose stale assumptions, but season and sensor differences must be controlled.
- Image-derived measurements are preliminary unless supported by appropriate survey-grade data.
- PV, BESS, access, drainage, receptors, utilities and route interfaces require different review questions.
- The observation register links images to confidence, materiality, actions, owners and closure evidence.
- AI is effective for structured comparison and question generation, but not for legal, ecological, geotechnical, flood or grid conclusions.
- The strongest output from remote review is a focused plan for field verification and specialist investigation.

### LOOKING AHEAD - CHAPTER 7

The next chapter focuses on AI-Assisted Site Visit Planning and Field Due Diligence. It will convert remote observations, project risks and information gaps into a safe, efficient inspection plan, multidisciplinary evidence schedule and issue-closure workflow.

## END OF CHAPTER 6

## CHAPTER 7

# AI-Assisted Site Visit Planning, Field Due Diligence and Site Visit Reporting for Utility-Scale Solar and BESS Projects

---

*From desktop uncertainty to field evidence, issue ownership and decision-ready reporting*

*Inspection strategy, HSE, evidence capture, multidisciplinary reconnaissance, AI-enabled synthesis and closure control*

Edition v1.1 | Volume 1

*"A site visit creates value only when it closes a decision-relevant uncertainty. Photographs without questions, coordinates, context and follow-up are records of travel—not engineering evidence."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a controlled method for planning, executing and reporting multidisciplinary site visits for utility-scale Solar PV and Battery Energy Storage System projects. It converts desktop findings, remote-imagery observations and development risks into a safe field inspection plan; defines the evidence that must be captured; and provides a structured route from observation to verified fact, issue, action and decision. Artificial Intelligence is used to prepare inspection schedules, organise field records, identify contradictions and draft reports, while qualified professionals retain responsibility for safety, technical interpretation and final conclusions.

| Element               | Purpose                                                                                                                       |
|-----------------------|-------------------------------------------------------------------------------------------------------------------------------|
| Visit brief           | Defines the decisions, scope, boundaries, participants, evidence needs and limitations before mobilisation.                   |
| HSE and permissions   | Confirms lawful access, induction, hazards, weather, lone-working controls, emergency arrangements and stop-work authority.   |
| Inspection plan       | Organises routes, locations, disciplines, interview questions, measurements, photographs and time allowances.                 |
| Evidence protocol     | Standardises geotagged photographs, field notes, coordinates, sketches, measurements, source references and chain of custody. |
| Discipline checklists | Guides review of land, access, terrain, drainage, environment, community, grid, utilities, PV and BESS interfaces.            |
| Issue classification  | Separates observations, verified findings, assumptions, risks, actions and matters requiring specialist investigation.        |
| AI workflow           | Accelerates preparation, transcription, photo indexing, contradiction checks, report drafting and action tracking.            |
| Closure process       | Assigns owner, due date, evidence requirement and decision impact to every material open item.                                |

*Table 7.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Define the purpose, timing and scope of a site visit in relation to development decisions and information gaps.
- Prepare a safe and efficient multidisciplinary visit plan with lawful access, HSE controls and clear responsibilities.
- Translate desktop and imagery findings into location-specific field questions and evidence requirements.
- Inspect land, access, terrain, drainage, environmental, social, grid, utility, PV and BESS interfaces systematically.

- Capture photographs, measurements, interviews and observations in a traceable, decision-grade format.
- Distinguish direct observation from interpretation, assumption and specialist conclusion.
- Use AI to organise field evidence and draft reports without fabricating certainty or exposing confidential data.
- Prepare an issue-based site visit report with prioritised actions, owners, deadlines and closure evidence.

## 7.1 Introduction

A site visit is one of the highest-leverage activities in early project development. In a few hours, an experienced team can confirm or challenge assumptions that would otherwise survive for months: whether access is practical, whether drainage is more complex than maps suggest, whether a parcel is actively used, whether neighbours are closer or more sensitive than expected, and whether the preferred BESS or substation area is genuinely suitable.

The same visit can also create false confidence. A dry-weather inspection may miss seasonal water. A public-road drive-by may not establish internal access. A photograph may be taken from the wrong location or without scale. A landowner statement may be useful but unverified. A visually flat field may conceal poor soils, buried utilities or flood risk. The purpose of field reconnaissance is therefore not to prove the project feasible; it is to improve the evidence base and direct the next professional investigations.

The professional workflow begins before mobilisation. Every location, question and required record should be linked to a development decision. During the visit, the team captures neutral observations and preserves uncertainty. After the visit, findings are reconciled with desktop evidence, contradictions are escalated, and material gaps become controlled actions.

### ■ ENGINEERING INSIGHT

Plan the visit around decisions, not around sightseeing. Every stop should answer a question, test an assumption or collect evidence required by a defined workflow.

## 7.2 What a Site Visit Can and Cannot Establish

Field reconnaissance is stronger than remote review for visible and accessible conditions, but it remains a snapshot. It should not be confused with a topographic survey, geotechnical investigation, ecological survey, legal opinion, transport assessment, hydrological study or grid-capacity confirmation.

| Topic                | A Site Visit Can Support                                                                                        | A Site Visit Cannot Prove                                                                       |
|----------------------|-----------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------|
| Access and logistics | Visible route condition, geometry, obstructions, bridge locations, gates, gradients and operational interfaces. | Legal rights, structural capacity, abnormal-load approval or long-term maintenance obligations. |
| Land use             | Current occupation, crops, livestock, buildings, tracks, fencing, irrigation and apparent operational activity. | Ownership, tenancy, title status, compensation entitlement or future availability.              |

| Topic                     | A Site Visit Can Support                                                                                      | A Site Visit Cannot Prove                                                                             |
|---------------------------|---------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------|
| Terrain and ground        | Broad slope, erosion, exposed rock, fill, soft ground indicators and earthworks evidence.                     | Design levels, bearing capacity, contamination, rock depth or foundation suitability.                 |
| Hydrology                 | Channels, culverts, ponding, erosion, water marks and outfalls visible at the time of visit.                  | Flood return periods, groundwater regime, hydraulic capacity or wet-season performance.               |
| Environment and community | Habitats, receptors, noise sources, public use, heritage features and local context visible during the visit. | Protected status, species presence, legal significance, stakeholder consent or impact acceptability.  |
| Grid and utilities        | Substations, overhead lines, route corridors, access, crossings and visible utility assets.                   | Available capacity, connection rights, protection settings, underground services or utility approval. |
| BESS compound             | Space, access, slope, drainage, vegetation, receptors, security context and emergency approach.               | Fire code compliance, acoustic compliance, cell safety, plume behaviour or final emergency strategy.  |

Table 7.2 - Appropriate and inappropriate conclusions from a site visit.

#### COMMON MISTAKE

Do not convert “not seen during the visit” into “not present.” Visibility, access, season, weather, vegetation and visit duration all limit detection.

## 7.3 Defining the Visit Objective and Decision Context

The visit brief should identify what decision the team must support. Acquisition screening, development baseline confirmation, route selection, FEED preparation and lender due diligence require different scopes and levels of evidence.

| Visit Type                 | Primary Objective                                                                                         | Typical Output                                                      |
|----------------------------|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------|
| Origination reconnaissance | Identify fatal flaws, access barriers and obvious site incompatibilities before committing material cost. | Go / hold / reject note and priority data-gap list.                 |
| Acquisition due diligence  | Test seller assumptions, validate key risks and define conditions precedent or price protections.         | Issue register, red flags, reliance limits and acquisition actions. |
| Development baseline visit | Establish current site condition and coordinate survey, permitting and land workstreams.                  | Controlled baseline report and consultant scope inputs.             |
| Design reconnaissance      | Inform layout, roads, drainage, substation, BESS and route development.                                   | Design observations, interface register and survey requests.        |

| Visit Type                 | Primary Objective                                                                       | Typical Output                                             |
|----------------------------|-----------------------------------------------------------------------------------------|------------------------------------------------------------|
| Constructability visit     | Review logistics, work fronts, temporary areas, crossings and construction constraints. | Constructability report and enabling-works actions.        |
| Independent / lender visit | Confirm project maturity and challenge material technical assumptions.                  | Independent findings, limitations and conditions to close. |

Table 7.3 - Site visit types and decision outputs.

## 7.4 The Controlled Site Visit Workflow



Figure 7.1 - Controlled site visit and field due diligence workflow.

The workflow protects the project from three recurring failures: visiting without a clear question, collecting evidence without traceability and issuing a report without closing the resulting actions. The visit is therefore one controlled stage within the wider evidence-management process.

| Stage              | Key Control                                                                                            | Expected Record                                             |
|--------------------|--------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| Decision need      | Identify the decision, assumptions and consequences if uncertainty remains.                            | Visit objective and decision statement.                     |
| Desktop review     | Review latest drawings, imagery, registers, studies, land data and known risks.                        | Pre-visit evidence pack and contradiction list.             |
| Visit brief        | Define locations, questions, participants, route, evidence and time plan.                              | Approved inspection plan and responsibility matrix.         |
| HSE and access     | Confirm permissions, hazards, weather, communications and emergency arrangements.                      | RAMS / field safety plan, contacts and access confirmation. |
| Field evidence     | Capture observations neutrally with coordinates, time, photos, measurements and interview attribution. | Field log, photo register, sketches and measurement sheets. |
| Reconciliation     | Compare field evidence with documents and classify conflicts or gaps.                                  | Evidence matrix and updated risk register.                  |
| Report and closure | State conclusions, limitations, actions, owners and required closure evidence.                         | Issued site visit report and action tracker.                |

Table 7.4 - Site visit workflow controls and records.

## 7.5 Preparing the Pre-Visit Evidence Pack

The field team should receive a concise, current and controlled evidence pack. Sending an uncontrolled data room to mobile devices creates confusion and increases the chance that obsolete boundaries or routes will be used.

| Evidence Item           | Minimum Content                                                                                     | Field Use                                         |
|-------------------------|-----------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Site plan               | Current boundary, parcel IDs, north arrow, coordinates, scale, access and candidate infrastructure. | Navigation and location referencing.              |
| Annotated imagery       | Latest source/date, numbered observations, alternative routes and priority verification points.     | Field-question schedule and change confirmation.  |
| Land schedule           | Owners, occupiers, options, access permissions, critical parcels and no-entry areas.                | Lawful access and land-interface discussion.      |
| Risk / gap register     | Material unknowns, assumptions, decision impacts, owners and required evidence.                     | Prioritisation of inspection effort.              |
| Survey and study status | Available topography, geotechnical, hydrology, ecology, heritage and utility data.                  | Avoid duplicate work and identify contradictions. |
| Grid and route plan     | POI, substation, overhead lines, underground route options, crossings and access.                   | Grid-interface and route reconnaissance.          |
| HSE information         | Known hazards, emergency contacts, weather, PPE, restricted areas and communications.               | Safe mobilisation and stop-work decisions.        |
| Field forms             | Observation IDs, photo log, measurement forms, interview template and action sheet.                 | Consistent evidence capture.                      |

*Table 7.5 - Minimum pre-visit evidence pack.*

### BEST PRACTICE

Freeze the field pack at a stated revision and date. Any change made after issue should be communicated explicitly to the full team before the visit begins.

## 7.6 Team Composition, Roles and Responsibilities

The visit team should be proportionate to the decision. A large multidisciplinary group may be inefficient during early screening, while a single engineer may miss critical environmental, social, land or safety issues. Roles should be assigned before mobilisation.



| Role                              | Primary Responsibility                                                                         | Typical Field Focus                                                                          |
|-----------------------------------|------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|
| Visit lead                        | Scope, safety coordination, time control, evidence completeness and closing discussion.        | Decision questions, priorities and overall site context.                                     |
| Solar / electrical engineer       | PV layout, substation, collector system, routes, interfaces and constructability observations. | Terrain/layout fit, cable routes, equipment access and utility conflicts.                    |
| Civil engineer                    | Access, earthworks, drainage, crossings, temporary works and ground indicators.                | Road geometry, slopes, erosion, water and platform areas.                                    |
| BESS specialist                   | Compound siting, access, safety separation, drainage, noise, emergency and O&M interfaces.     | Receptors, fire access, expansion, security and service routes.                              |
| Environmental / social specialist | Habitat, water, heritage, receptors, public use and stakeholder context.                       | Sensitive areas, community interfaces and survey requirements.                               |
| Land / development representative | Permissions, owner relationships, parcel status, occupiers and local intelligence.             | Boundaries, operations, access rights and stakeholder records.                               |
| Local guide / landowner           | Lawful access and operational knowledge.                                                       | Seasonal conditions, use history and practical constraints; statements require verification. |

Table 7.6 - Site visit roles and field responsibilities.

## 7.7 Health, Safety, Security and Lawful Access

No technical objective justifies unsafe or unauthorised fieldwork. Site conditions may include traffic, uneven terrain, livestock, machinery, waterways, extreme heat, storms, wildfire, electrical infrastructure, hunting activity, contaminated ground or poor communications. Local requirements and organisational HSE procedures govern the visit.

| Control Area           | Minimum Requirement                                                                                       |
|------------------------|-----------------------------------------------------------------------------------------------------------|
| Access permission      | Written or clearly documented permission for every private area, route, building and asset to be entered. |
| Risk assessment        | Location-specific hazards, persons at risk, controls, residual risk and stop-work criteria.               |
| Weather and daylight   | Forecast, heat/cold limits, lightning, wind, rainfall, flood, wildfire and daylight window.               |
| Communications         | Coverage check, contact list, check-in schedule, backup method and escalation protocol.                   |
| Emergency arrangements | Nearest medical support, coordinates, evacuation routes, vehicle condition and first aid.                 |

| Control Area        | Minimum Requirement                                                                                          |
|---------------------|--------------------------------------------------------------------------------------------------------------|
| PPE and equipment   | Appropriate footwear, visibility, sun/heat protection, water, navigation, measuring and first-aid equipment. |
| Restricted assets   | Utility, substation, railway, road, industrial or security-sensitive boundaries respected.                   |
| Data and privacy    | Approved photography, drone, recording and personal-data practices; no unlawful capture.                     |
| Stop-work authority | Every participant may stop the visit when conditions or instructions are unsafe or unclear.                  |

Table 7.7 - Minimum HSE, security and access controls.

### STANDARDS REFERENCE

A field plan is invalid if it relies on entering land, structures, substations, roads or watercourses without permission and appropriate safety controls.

## 7.8 Building the Route and Stop Schedule

The route should maximise evidence value while respecting access, time, fatigue and safety constraints. Stops are best organised by issue criticality rather than by convenience alone.

| Stop Category                  | Typical Question                                                                      | Evidence to Capture                                                                        |
|--------------------------------|---------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|
| Public-road approach           | Can construction and abnormal loads reach the site without obvious fatal constraints? | Route photographs, junctions, bridges, gradients, restrictions and alternative approaches. |
| Primary site entrance          | Is the proposed entrance practical and legally/physically compatible with operations? | Coordinates, geometry, sight lines, gate, drainage, width and surrounding use.             |
| Representative terrain zones   | Do mapped slopes and surface conditions reflect reality?                              | Panoramas, slope estimates, erosion, rock, soft ground and access notes.                   |
| Drainage and water crossings   | Where does water enter, move through and leave the site?                              | Channels, culverts, banks, ponding, marks, outfalls and local statements.                  |
| BESS / substation alternatives | Which location best balances constructability, safety and interfaces?                 | Space, slope, access, drainage, receptors, vegetation, utilities and expansion.            |
| Export-route crossings         | What physical and stakeholder interfaces affect the route?                            | Road, water, rail, utility, parcel, woodland and work-area evidence.                       |
| Sensitive receptors            | What residential, community, heritage or ecological context requires assessment?      | Lawful observations, distances, screening, activity and survey actions.                    |

Table 7.8 - Route stops linked to decision questions and evidence.

## 7.9 Evidence Capture and Field Data Standards

Field evidence must remain intelligible after the team leaves the site. A strong record allows another competent reviewer to understand where the evidence was captured, what was observed, what remains uncertain and why the item matters.



Figure 7.2 - Field evidence chain from observation to closure.

| Field                     | Required Standard                                                                                    |
|---------------------------|------------------------------------------------------------------------------------------------------|
| Unique reference          | Use a consistent location and observation ID linked to maps, photos and report tables.               |
| Date and time             | Record local date/time and weather or relevant conditions.                                           |
| Coordinates               | Capture coordinate system and device accuracy; do not imply survey precision.                        |
| Orientation               | Record camera direction or include a labelled panorama where practical.                              |
| Neutral description       | State what is visible before interpreting cause or consequence.                                      |
| Scale / measurement       | Include measured value, method, instrument and approximate accuracy where relevant.                  |
| Photo quality             | Use context, medium and detail images; avoid duplicates without purpose.                             |
| Source attribution        | Identify whether information came from direct observation, document, landowner or other interviewee. |
| Confidence and limitation | State visibility, access, season, weather and any reason the observation may be incomplete.          |
| Action link               | Identify the professional study, decision or workstream needed to close the issue.                   |

Table 7.9 - Minimum field evidence standards.

## 7.10 Land, Boundaries and Operational Use

The field team should observe how the land is actually occupied and operated while avoiding legal conclusions from physical features. Fences, hedges, tracks and cultivation limits may not coincide with title boundaries.

| Observation Area         | Field Questions                                                                 | Follow-Up Evidence                                                  |
|--------------------------|---------------------------------------------------------------------------------|---------------------------------------------------------------------|
| Boundary features        | Are fences, walls, hedges or markers visible? Do they align with the field map? | Licensed survey, cadastral/title review and landowner confirmation. |
| Occupiers and tenants    | Who is using the land and for what activity?                                    | Lease/tenancy evidence, authority and compensation review.          |
| Agricultural operations  | What crops, livestock, irrigation, harvesting and access patterns exist?        | Seasonal operations plan and land agreement provisions.             |
| Buildings and structures | Are structures occupied, used, derelict or potentially affected?                | Ownership, planning, demolition, contamination and heritage review. |
| Third-party access       | Do public, agricultural or utility users cross the site?                        | Rights-of-way and easement investigation.                           |
| Temporary-use areas      | Where could laydown, compounds and construction routes be located?              | Land rights, ecology, drainage and reinstatement scope.             |

Table 7.10 - Land and operational-use field review.

## 7.11 Access and Construction Logistics

Access should be reviewed as a complete logistics chain from the strategic road network to the equipment location. The most visible site entrance is not necessarily the preferred route for transformers, BESS containers, piles, trackers or heavy civil plant.

| Interface                | Inspect                                                                            | Potential Consequence                                                 |
|--------------------------|------------------------------------------------------------------------------------|-----------------------------------------------------------------------|
| Junctions and turns      | Turning geometry, islands, signs, street furniture, buildings, verges and traffic. | Temporary works, escorting, route rejection or public-road approvals. |
| Bridges and culverts     | Width, condition, barriers, approach geometry, water and ownership clues.          | Structural assessment, reinforcement or alternative route.            |
| Road width and shoulders | Passing places, edge condition, drainage, walls, trees and overhead constraints.   | Road upgrades, traffic controls and land take.                        |
| Gradients and surfaces   | Steep sections, loose material, erosion, rutting and seasonal condition.           | Vehicle limitations, maintenance and construction schedule risk.      |
| Site gates and tracks    | Gate width, alignment, farm operations, livestock and internal continuity.         | New access, rights, fencing and operational interfaces.               |
| Delivery staging         | Safe waiting, offloading and temporary storage opportunities.                      | Additional land, traffic management and enabling works.               |

Table 7.11 - Access and logistics inspection framework.

## 7.12 Terrain, Ground Conditions and Civil Constructability

Visual ground observations help target surveys and geotechnical investigations. They should not be used to select foundations or quantify earthworks without design-grade data.

| Visible Indicator                  | Possible Relevance                                                             | Required Professional Confirmation                         |
|------------------------------------|--------------------------------------------------------------------------------|------------------------------------------------------------|
| Strong or variable slopes          | Tracker articulation, grading, road gradients, drainage and layout efficiency. | Topographic survey and civil design.                       |
| Exposed rock / shallow soil        | Pile refusal, trenching, blasting and road construction risk.                  | Geotechnical investigation and trial works.                |
| Soft, wet or compressible areas    | Platform settlement, road stability, drainage and construction access.         | Geotechnical and hydrological investigation.               |
| Fill, waste or disturbed ground    | Settlement, contamination, buried obstructions and variable founding.          | Historical review, contamination and geotechnical studies. |
| Erosion or gullies                 | Concentrated runoff, slope instability and drainage maintenance.               | Topographic, hydrological and erosion assessment.          |
| Terraces, walls or farm earthworks | Layout discontinuity, heritage, drainage and removal constraints.              | Survey, land, heritage and civil review.                   |

*Table 7.12 - Ground and constructability observations.*

## 7.13 Hydrology, Drainage and Flood Indicators

A site visit should establish the visible drainage network and test whether mapped water features are present. Conditions at the time of visit must be recorded because a dry channel or absent ponding does not demonstrate low flood risk.

| Field Feature        | Evidence to Record                                                                       | Engineering Action                                |
|----------------------|------------------------------------------------------------------------------------------|---------------------------------------------------|
| Watercourse / ditch  | Alignment, dimensions, banks, vegetation, crossings, debris and apparent flow direction. | Survey and hydrology model input.                 |
| Culvert              | Location, size, material, condition, blockage, inlet/outlet and ownership context.       | Capacity and asset-responsibility review.         |
| Ponding / wet ground | Extent, soil condition, vegetation, water marks and weather history.                     | Drainage, geotechnical and seasonal verification. |
| Erosion / sediment   | Scour, deposits, rills, gullies and affected roads or fields.                            | Runoff management and erosion-control study.      |
| Upstream catchment   | Landform, roads, development, channels and flow concentration.                           | Catchment delineation and flood assessment.       |

| Field Feature      | Evidence to Record                                                            | Engineering Action                               |
|--------------------|-------------------------------------------------------------------------------|--------------------------------------------------|
| Downstream outfall | Receiving channel, property, erosion, capacity and environmental sensitivity. | Outfall rights, permitting and hydraulic design. |

Table 7.13 - Hydrology and drainage field evidence.

**COMMON MISTAKE**

Record rainfall before the visit, recent drought or storm conditions and visible seasonal limitations. A single visit should not be presented as a full hydrological baseline.

## 7.14 Environmental, Social and Heritage Context

Field reconnaissance can identify visible sensitivities and practical survey needs, but specialist status and impact significance must be determined by qualified professionals under the applicable legal framework.

| Area                    | Field Observation                                                           | Do Not Conclude Without Specialist Evidence                                            |
|-------------------------|-----------------------------------------------------------------------------|----------------------------------------------------------------------------------------|
| Habitats and vegetation | Woodland, hedgerows, wetlands, scrub, grassland, crops and disturbed areas. | Habitat classification, protected status, species absence or mitigation acceptability. |
| Fauna indicators        | Nests, burrows, tracks, livestock, carcasses or visible bird use.           | Species population, legal significance or seasonal absence.                            |
| Community receptors     | Homes, schools, roads, recreation, businesses and public gathering areas.   | Occupancy, vulnerability, acceptance or final impact.                                  |
| Noise and activity      | Existing industrial, traffic, agricultural and natural sources.             | Measured baseline or compliance with future project limits.                            |
| Heritage / archaeology  | Structures, earthworks, walls, monuments or local reports.                  | Designation, archaeological value or required mitigation.                              |
| Public access           | Paths, informal tracks, hunting, grazing or recreational use.               | Legal rights, usage frequency or closure acceptability.                                |

Table 7.14 - Environmental, social and heritage reconnaissance limits.

## 7.15 Grid, Substation, Utility and Export-Route Reconnaissance

The site visit should review physical interfaces associated with the point of interconnection and export route without implying network capacity or utility approval. Particular attention is required at crossings, route bottlenecks and third-party assets.

| Interface            | Field Questions                                                                           | Required Follow-Up                                         |
|----------------------|-------------------------------------------------------------------------------------------|------------------------------------------------------------|
| Existing substation  | Access, surroundings, apparent expansion space, drainage, receptors and route approaches? | Utility consultation, survey, land and connection studies. |
| Overhead line        | Tower locations, terrain, access, crossings, vegetation and nearby development?           | Utility data, clearance design and route survey.           |
| Underground route    | Road verges, bridges, water crossings, urban sections, utilities and work space?          | Utility search, route survey, authority and land rights.   |
| Road / rail crossing | Geometry, embankments, drainage, traffic, structures and available launch/working area?   | Authority approval and crossing design.                    |
| Watercourse crossing | Width, banks, habitat, access and floodplain context?                                     | Environmental, hydrology and trenchless/open-cut study.    |
| Third-party utility  | Visible markers, cabinets, pipelines, poles and maintenance access?                       | Formal records, detection survey and owner consultation.   |

Table 7.15 - Grid and export-route field review.

## 7.16 BESS-Specific Field Due Diligence

BESS siting requires inspection beyond a generic flat-area check. The compound must support construction, operation, emergency access, drainage, fire strategy, acoustic management, security, augmentation and decommissioning.

| BESS Topic               | Field Review                                                                                  | Potential Decision Impact                                 |
|--------------------------|-----------------------------------------------------------------------------------------------|-----------------------------------------------------------|
| Emergency access         | Multiple approaches where required, turning, all-weather surface, gates and responder access. | Compound orientation, road works and emergency plan.      |
| Receptors                | Homes, workplaces, roads, public areas and sensitive uses; record lawful location evidence.   | Noise, visual, safety and stakeholder assessment.         |
| Drainage and flood       | Low points, channels, outfalls, ponding, erosion and upstream runoff.                         | Platform elevation, drainage concept or alternative site. |
| Vegetation / wildfire    | Fuel type, continuity, slope, surrounding activity and firefighting context.                  | Clearance, landscaping, fire study and maintenance.       |
| Security                 | Public visibility, informal access, fencing interfaces and surveillance opportunities.        | Security layout and operational controls.                 |
| Utilities and services   | Auxiliary power, communications, water, drainage and maintenance routes.                      | Balance-of-plant design and cost.                         |
| Expansion / augmentation | Adjacent space, access preservation and phased construction interfaces.                       | Land rights and long-term layout.                         |

| BESS Topic      | Field Review                                       | Potential Decision Impact              |
|-----------------|----------------------------------------------------|----------------------------------------|
| Decommissioning | Heavy-equipment access, storage and removal route. | Contract, land and lifecycle strategy. |

Table 7.16 - BESS field due diligence framework.

## 7.17 Interviews and Local Knowledge

Landowners, occupiers, operators, neighbours and local authorities may provide valuable information about flooding, access, utilities, land history, fire, agricultural operations and community concerns. Interview evidence should be attributed and verified before it supports a material conclusion.

| Interview Control      | Professional Practice                                                                                           |
|------------------------|-----------------------------------------------------------------------------------------------------------------|
| Identity and authority | Record name, role, relationship to the land or asset and whether the person is authorised to speak.             |
| Question discipline    | Use open, neutral questions; avoid leading the interviewee toward a preferred project answer.                   |
| Attribution            | Record the statement as reported information, not as a verified fact.                                           |
| Consent and privacy    | Follow lawful recording, photography and personal-data requirements.                                            |
| Corroboration          | Cross-check material statements against documents, other interviews, surveys or official records.               |
| Commitments            | Do not make commercial, design or approval commitments during an information-gathering visit unless authorised. |

Table 7.17 - Interview and local-knowledge controls.

## 7.18 Using Artificial Intelligence Before, During and After the Visit

AI can substantially reduce the administrative burden of field due diligence, but only when source traceability, confidentiality and human review are preserved. The approved tool environment should reflect project information-security requirements.

| Phase        | Appropriate AI Use                                                                                                | Required Human Control                                                         |
|--------------|-------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Before visit | Extract open questions from reports; build stop schedules; prepare discipline checklists and interview questions. | Confirm current document revisions, locations, access and technical relevance. |



| Phase              | Appropriate AI Use                                                                                    | Required Human Control                                          |
|--------------------|-------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|
| During visit       | Voice-to-text notes, photo naming, form completion and map-linked observation capture where approved. | Verify transcription, coordinates, context and safe device use. |
| After visit        | Index photos, group issues, compare evidence with desktop assumptions and draft report tables.        | Review every source link, technical statement and conclusion.   |
| Quality challenge  | Identify contradictions, missing photographs, unsupported claims and unassigned actions.              | Decide materiality, professional study need and acceptance.     |
| Management summary | Convert technical findings into concise decision impacts and priority actions.                        | Preserve limitations and avoid overstating confidence.          |

Table 7.18 - Controlled AI use in site visit workflows.

#### AI TIP

Do not upload confidential maps, personal data, security-sensitive infrastructure, landowner information or geotagged records to an unapproved AI service. Remove or protect sensitive data in accordance with project policy.

## 7.19 Classifying Findings and Contradictions

The report should distinguish evidence type and decision significance. A direct field observation may be highly reliable but commercially minor; an uncertain indication may be low confidence but potentially fatal and therefore require urgent investigation.

| Classification       | Definition                                                                         | Example                                                                                |
|----------------------|------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------|
| Observed condition   | Directly visible and recorded during the visit.                                    | A concrete-lined drainage channel crosses the candidate BESS area.                     |
| Reported information | Statement from an interviewee or third party, not independently verified.          | Landowner reports that the eastern field floods every three to five years.             |
| Interpretation       | Professional meaning assigned to observed evidence.                                | Erosion pattern suggests concentrated runoff from the northern road.                   |
| Contradiction        | Field evidence conflicts with a drawing, report, imagery or stakeholder statement. | The latest layout shows an access route through a recently constructed warehouse yard. |
| Information gap      | Material question remains unanswered.                                              | Bridge load capacity is unknown.                                                       |
| Risk / issue         | Condition may affect safety, cost, programme, consent, performance or bankability. | Preferred BESS area may require relocation due to flood and receptor interfaces.       |

| Classification | Definition                                         | Example                                                                          |
|----------------|----------------------------------------------------|----------------------------------------------------------------------------------|
| Action         | Defined work required to close or manage the item. | Commission topographic and hydrological survey of the eastern drainage corridor. |

*Table 7.19 - Site visit finding classifications.*

| Priority | Decision Meaning                                                                      | Typical Response                                                            |
|----------|---------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| Critical | Potential fatal flaw, immediate safety concern or acquisition / design stop.          | Escalate immediately; suspend affected decision until evidence is obtained. |
| High     | Material impact likely on cost, schedule, permitting, layout or stakeholder strategy. | Assign owner and near-term investigation before next decision gate.         |
| Medium   | Manageable issue requiring design, survey or coordination action.                     | Track through normal development controls.                                  |
| Low      | Minor observation or optimisation opportunity.                                        | Record and address at the appropriate stage.                                |

*Table 7.20 - Priority classification for field findings.*

## 7.20 Structure of a Professional Site Visit Report

The report should be concise enough for decision-makers and detailed enough to preserve evidence. It should not become a chronological travel diary.

47. Document control, visit date, weather, participants, purpose and reliance limitations.
48. Executive summary and decision-relevant conclusions.
49. Scope, evidence reviewed, areas accessed and areas not inspected.
50. Site context and route overview with controlled maps.
51. Findings by discipline or geographic area.
52. Photograph and observation register linked to unique references.
53. Contradictions with desktop evidence and required baseline updates.
54. Risk / issue register with priority, consequence and recommended action.
55. Action plan with owner, due date and closure evidence.
56. Appendices containing field forms, interview notes, measurements and image sheets.

### ENGINEERING INSIGHT

State limitations prominently. Restricted access, dry weather, incomplete documents, unverified interviews or unavailable specialists must be visible to anyone relying on the report.

## 7.21 Worked Example - Acquisition-Stage Solar PV and BESS Site Visit

A developer is considering acquisition of a 320 MWac Solar PV project with a 160 MW / 320 MWh BESS. Desktop review indicates a generally attractive site but identifies uncertainty around

two bridge crossings, seasonal drainage, a nearby residence, western-slope earthworks and an export route through multiple agricultural parcels.

| Project Element | Desktop Assumption                                               | Field Question                                                                        |
|-----------------|------------------------------------------------------------------|---------------------------------------------------------------------------------------|
| Primary access  | Existing municipal road and farm track can support construction. | Are bridges, turns, road width and final approach compatible with heavy deliveries?   |
| Eastern lowland | Area is available for PV with standard drainage design.          | Is there visible ponding, wet vegetation, flood evidence or major channel continuity? |
| Western ridge   | Gross area can support tracker rows.                             | Are slopes, erosion, rock and terrace features more severe than mapping indicates?    |
| BESS option A   | Flat area near substation is preferred.                          | What are the actual receptor, drainage, emergency access and vegetation interfaces?   |
| BESS option B   | Alternative area is less efficient but lower social risk.        | Does drainage or cable routing outweigh the receptor advantage?                       |
| Export route    | Shortest route is commercially preferred.                        | Are crossings, work areas, land operations and road interfaces practical?             |

Table 7.21 - Worked-example pre-visit questions.

The team includes the development lead, civil engineer, electrical engineer, BESS specialist and environmental consultant. The visit is completed after two days of moderate rain, providing useful but not definitive drainage evidence. Lawful access is confirmed for the main parcels and public-road route; two private route parcels are observed only from permitted boundaries.

| Location        | Field Evidence                                                                                         | Interpretation and Limitation                                                             | Priority Action                                                                             |
|-----------------|--------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------|
| Bridge 1        | Narrow masonry bridge with tight approach, no visible load signage and parapet damage.                 | Potential abnormal-load constraint; visual condition does not establish capacity.         | Critical: commission structural and logistics route assessment; retain alternative access.  |
| Bridge 2        | Modern concrete crossing with better geometry but adjacent private wall limits turning.                | May be feasible with temporary works and land agreement.                                  | High: swept-path review and landowner engagement.                                           |
| Eastern lowland | Standing water, saturated soil, reed vegetation and multiple field drains after recent rain.           | Desktop usable-area assumption is optimistic; flood frequency remains unverified.         | High: topographic, geotechnical and hydrological investigation; protect layout contingency. |
| Western ridge   | Steeper cross-slopes, shallow exposed rock and active erosion gullies.                                 | Tracker and trenching risk higher than gross-area screen indicated.                       | High: detailed survey, grading screen and geotechnical test plan.                           |
| BESS option A   | Flat disturbed ground, good access, residence approximately 260 m away and drainage ditch at boundary. | Constructability favourable; acoustic, drainage and stakeholder risks require comparison. | High: noise baseline, receptor confirmation and drainage concept.                           |

| Location      | Field Evidence                                                                            | Interpretation and Limitation                                                 | Priority Action                                                     |
|---------------|-------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------|---------------------------------------------------------------------|
| BESS option B | Greater receptor separation but soft ground and route crossing of irrigation channel.     | Social advantage may be offset by civil and cable complexity.                 | Medium: geotechnical and route study; retain as alternative.        |
| Export route  | Shortest route crosses active orchard, concrete irrigation channel and narrow local road. | Land, agricultural and crossing impacts may exceed benefit of shorter length. | High: compare road-corridor alternative and update land priorities. |

Table 7.22 - Worked-example field findings and actions.

The site visit does not reject the project, but it materially changes the development plan. The investment recommendation becomes conditional on logistics confirmation, hydrology and geotechnical work in the eastern lowland, retention of two BESS alternatives and a comparative export-route study. The preferred layout is frozen only after these actions are closed.

| Decision                   | Before Visit                          | After Visit                                                                            |
|----------------------------|---------------------------------------|----------------------------------------------------------------------------------------|
| Acquisition recommendation | Proceed based on desktop feasibility. | Proceed conditionally with defined technical protections and investigation budget.     |
| Access strategy            | Use shortest existing approach.       | Maintain two routes until bridge and swept-path studies are complete.                  |
| Usable area                | Full eastern lowland included.        | Apply provisional exclusion / contingency pending hydrology and geotechnical evidence. |
| BESS location              | Option A preferred.                   | Compare A and B using noise, drainage, ground, route and land evidence.                |
| Export route               | Shortest route preferred.             | Re-open route selection to reduce agricultural and crossing interfaces.                |

Table 7.23 - Worked-example decision changes created by field evidence.

## 7.22 Post-Visit Reconciliation and Issue Closure

The highest risk period is immediately after the visit, when evidence is fresh but scattered across phones, notebooks, voice recordings and informal conversations. Records should be consolidated promptly under document control.

| Post-Visit Step      | Required Output                                                                                                     |
|----------------------|---------------------------------------------------------------------------------------------------------------------|
| Evidence upload      | Original photos, maps, measurements, notes and recordings stored in approved locations without destructive editing. |
| Reference assignment | Unique IDs linked consistently across maps, photo register, report and issue tracker.                               |

| Post-Visit Step        | Required Output                                                                                          |
|------------------------|----------------------------------------------------------------------------------------------------------|
| Team debrief           | Agreed observations, disagreements, urgent risks and missing evidence recorded.                          |
| Desktop reconciliation | Comparison against drawings, imagery, studies, land records and previous assumptions.                    |
| Specialist escalation  | Clear scopes for survey, geotechnical, hydrology, ecology, noise, logistics, legal or utility follow-up. |
| Action ownership       | Named owner, due date, priority, decision gate and closure evidence.                                     |
| Baseline update        | Layouts, route plans, risk register, land priorities and development schedule revised as required.       |
| Formal close           | Action accepted only when required evidence is reviewed and the decision consequence is resolved.        |

Table 7.24 - Post-visit reconciliation and closure workflow.

## 7.23 Common Mistakes

| Mistake                           | Why It Creates Risk                                                                        | Better Practice                                                            |
|-----------------------------------|--------------------------------------------------------------------------------------------|----------------------------------------------------------------------------|
| Visiting without a decision brief | Time is spent on visible but low-value features while material questions remain open.      | Link every stop and record to a defined decision or risk.                  |
| Using obsolete maps               | The team may inspect the wrong boundary, route or layout.                                  | Issue a controlled field pack with revision and date.                      |
| Entering without permission       | Creates legal, safety, stakeholder and reputational risk.                                  | Confirm lawful access and restricted areas before mobilisation.            |
| Taking unreferenced photographs   | Images cannot be linked reliably to location, orientation or issue.                        | Use unique IDs, coordinates, direction and photo register.                 |
| Writing interpretation as fact    | Uncertainty disappears and later teams may over-rely on the report.                        | Separate observation, reported information, interpretation and conclusion. |
| Ignoring season and weather       | Conditions may be materially unrepresentative.                                             | Record conditions and define seasonal verification needs.                  |
| Making specialist conclusions     | Field reconnaissance cannot replace survey, ecology, geotechnical, legal or grid evidence. | Escalate to the competent discipline with a clear scope.                   |
| Allowing AI to invent context     | Automated summaries may detach photos from sources or overstate confidence.                | Require source references and human verification for every finding.        |
| Issuing a travel diary            | Chronology obscures decision impact and actions.                                           | Report by issue, discipline and consequence.                               |

| Mistake                  | Why It Creates Risk                             | Better Practice                                         |
|--------------------------|-------------------------------------------------|---------------------------------------------------------|
| Failing to close actions | The same uncertainties reappear at later gates. | Track owner, due date, closure evidence and acceptance. |

Table 7.25 - Common site visit mistakes and controls.

## 7.24 Best Practices

- Define the decision, visit type and reliance level before selecting participants or routes.
- Use current controlled maps, imagery, land schedules and risk registers in the field pack.
- Confirm lawful access, HSE controls, weather, communications and emergency arrangements before departure.
- Prioritise stops by consequence and uncertainty, not only by geographic convenience.
- Capture neutral observations with unique references, coordinates, time, orientation and source attribution.
- Use context, medium and detail photographs for each material feature.
- Record what was not accessible, not visible or not inspected.
- Treat interviews as reported information until corroborated.
- Separate confidence from materiality and escalate low-confidence, high-consequence indicators quickly.
- Reconcile field evidence with desktop sources and update the controlled project baseline.
- Use AI for preparation and organisation while preserving confidentiality, source links and human judgement.
- Close every material issue through evidence, not merely through a change of wording in the report.

## 7.25 Engineering and Development Review Checklist

| Review Area   | Validation Question                                                                     | Check                    |
|---------------|-----------------------------------------------------------------------------------------|--------------------------|
| Objective     | Is the decision, visit type, scope and intended reliance clearly defined?               | <input type="checkbox"/> |
| Evidence pack | Are boundaries, layouts, imagery, routes, land status and risks current and controlled? | <input type="checkbox"/> |
| Team          | Are roles, competence, responsibilities and specialist limitations appropriate?         | <input type="checkbox"/> |
| Access / HSE  | Are permissions, hazards, weather, communications and emergency controls confirmed?     | <input type="checkbox"/> |
| Route         | Does the stop schedule cover all material questions efficiently and safely?             | <input type="checkbox"/> |
| Field records | Are IDs, coordinates, time, direction, measurements, photos and notes traceable?        | <input type="checkbox"/> |
| Evidence type | Are observations, reported information, interpretations and conclusions separated?      | <input type="checkbox"/> |

| Review Area          | Validation Question                                                                                       | Check                    |
|----------------------|-----------------------------------------------------------------------------------------------------------|--------------------------|
| Land / access        | Have occupation, operations, boundaries, rights questions and logistics interfaces been reviewed?         | <input type="checkbox"/> |
| Civil / hydrology    | Have terrain, ground indicators, drainage, flood evidence and crossings been recorded?                    | <input type="checkbox"/> |
| Environment / social | Have visible sensitivities, receptors, public use and specialist survey needs been identified?            | <input type="checkbox"/> |
| Grid / route         | Have substation, utilities, export routes and crossings been reviewed without assuming capacity?          | <input type="checkbox"/> |
| BESS                 | Have access, drainage, receptors, vegetation, security, emergency and expansion interfaces been assessed? | <input type="checkbox"/> |
| AI control           | Were confidentiality, transcription accuracy, source references and human validation enforced?            | <input type="checkbox"/> |
| Report               | Are limitations, contradictions, priority findings and decision impacts prominent?                        | <input type="checkbox"/> |
| Closure              | Does each material action have an owner, due date, decision gate and closure evidence?                    | <input type="checkbox"/> |

Table 7.26 - Site visit and field due diligence review checklist.

## 7.26 Prompt Toolkit

### Level 1 - Quick Prompt

#### QUICK PROMPT

Act as a Senior Solar PV and BESS Development Engineer. Using the supplied site boundary, annotated imagery and open-risk list, prepare a one-day site visit checklist. Organise it by access, land use, terrain, drainage, receptors, grid route and BESS. For each item state the question, location, evidence to capture and required follow-up. Do not make legal, ecological, geotechnical, flood, road-capacity or grid-capacity conclusions.

## Level 2 - Professional Prompt

### PROFESSIONAL PROMPT

Prepare a multidisciplinary field due diligence plan for the supplied utility-scale Solar PV and co-located BESS project. Review the current layout, site boundary, remote-imagery observations, land schedule, risk register and route options. Produce: visit objectives; controlled evidence-pack list; participants and responsibilities; HSE and lawful-access checklist; route and stop schedule; location-specific questions; photo, measurement and interview requirements; BESS-specific inspection items; and a post-visit evidence and action workflow. Clearly distinguish what can be observed in the field from matters requiring survey, legal, environmental, geotechnical, hydrological, acoustic, logistics or grid confirmation.

## Level 3 - Expert Prompt

### EXPERT PROMPT

You are acting as the Lead Owner's Engineer conducting acquisition-stage field due diligence for a utility-scale Solar PV and BESS project. Based on all supplied documents and approved field records, prepare a decision-grade site visit report. Establish source and revision control; describe visit date, weather, access and limitations; reconcile field evidence against imagery, land, design, environmental, grid and survey assumptions; classify every material item as observed condition, reported information, interpretation, contradiction, information gap, risk or action; and assess consequences for land, permitting, logistics, usable area, drainage, foundations, BESS siting, export route, CAPEX, programme and bankability. Include an executive summary, annotated finding schedule, photo register, priority risk matrix, acquisition protections, specialist scopes, action owner, due date, decision gate and required closure evidence. Do not invent observations or treat AI transcription as verified evidence.

## 7.27 Recommended Reference Framework

Field due diligence should comply with the current requirements of the project jurisdiction, land agreements and organisational procedures. The reference framework should include:

- Organisational HSE management system, travel, lone-working, fieldwork and emergency procedures.
- Land-access permissions, confidentiality obligations, photography restrictions and stakeholder protocols.
- Current cadastral, title, topographic, orthophoto, planning, environmental, heritage, flood and utility sources.
- Applicable road authority, abnormal-load, traffic, railway, watercourse and utility crossing requirements.
- Current grid-code, substation-access and network-operator safety requirements.
- Applicable BESS fire, emergency response, acoustic, electrical, environmental and occupational-safety guidance.
- Project document-control, GIS, cybersecurity, personal-data and approved-AI procedures.
- Professional survey, geotechnical, hydrology, ecology, noise, heritage and logistics standards relevant to follow-up work.

### STANDARDS REFERENCE

The site visit report should identify the evidence relied upon and the professional investigations still required. Field observations do not reduce the need to comply with current law, permits, standards and authority requirements.



## 7.28 Chapter Summary

A well-planned site visit converts desktop uncertainty into targeted field evidence. Its value comes from disciplined preparation, lawful and safe execution, traceable records, multidisciplinary interpretation and controlled follow-up. The team should know why each stop matters, what evidence is required and what professional work will be needed if the question cannot be answered in the field.

Artificial Intelligence can accelerate checklist preparation, route planning, transcription, photo indexing, contradiction review and report drafting. It must not invent observations, detach conclusions from evidence, expose sensitive information or replace competent professional judgement. The final report should make decision impacts, limitations and closure actions clear to development, investment and engineering stakeholders.

## 7.29 Key Takeaways

- Every site visit should be tied to a defined decision and a controlled evidence pack.
- Lawful access, HSE, security, weather and emergency arrangements are prerequisites, not administrative extras.
- A site visit is a snapshot and cannot replace specialist survey, legal, environmental, geotechnical, hydrological, logistics or grid work.
- Field evidence needs unique references, coordinates, time, orientation, neutral description and limitations.
- Observations, reported information, interpretations, contradictions and conclusions must be separated.
- Land, access, drainage, terrain, receptors, grid routes and BESS interfaces require dedicated inspection questions.
- Low-confidence indicators may still demand urgent action when the potential consequence is high.
- The report should focus on decision impact and issue closure rather than the chronology of the visit.
- AI is useful for preparation and evidence organisation, but every technical statement requires human validation.
- The visit is complete only when material actions have owners, deadlines and accepted closure evidence.

### LOOKING AHEAD - CHAPTER 8

The next chapter focuses on AI-Assisted Environmental and Social Constraint Screening. It will develop a structured method for identifying sensitive receptors, permitting interfaces, survey needs, mitigation hierarchy and decision-critical environmental and social risks during early project development.

END OF CHAPTER 7

## CHAPTER 8

# AI-Assisted Environmental and Social Constraint Screening for Utility-Scale Solar and BESS Projects

---

*From early receptor identification to survey strategy, mitigation hierarchy and consent-ready risk control*

*Environmental baseline, social context, permitting interfaces, BESS-specific risks and AI-enabled evidence management*

Edition v1.1 | Volume 1

*"Environmental and social screening is not a search for reasons to reject a project. It is a disciplined process for understanding where, when and under what conditions the project may proceed responsibly."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a structured method for screening environmental and social constraints during the early development of utility-scale Solar PV and Battery Energy Storage System projects. It explains how to define the area of influence, assemble a defensible evidence base, identify sensitive receptors, establish survey requirements, classify uncertainty, compare alternatives and translate findings into mitigation, permitting and investment decisions. Artificial Intelligence is used to organise sources, compare evidence, draft registers and test completeness, while qualified environmental, social, legal and engineering professionals retain responsibility for interpretation and compliance.

| Element              | Purpose                                                                                                                          |
|----------------------|----------------------------------------------------------------------------------------------------------------------------------|
| Screening basis      | Defines project configuration, study boundaries, development stage, available evidence and intended decision.                    |
| Source hierarchy     | Prioritises official designations, authority data, specialist studies, verified field evidence and controlled project documents. |
| Constraint themes    | Structures biodiversity, water, landscape, noise, heritage, land use, community, access, grid route and BESS topics.             |
| Survey strategy      | Links each material uncertainty to method, season, duration, competence, access and decision deadline.                           |
| Impact pathway       | Connects project activity, receptor, exposure, consequence, significance and mitigation.                                         |
| Mitigation hierarchy | Applies avoidance, minimisation, restoration and compensation in the correct order.                                              |
| AI workflow          | Accelerates evidence indexing, gap checks, consistency reviews, meeting preparation and register drafting.                       |
| Decision control     | Converts findings into fatal flaws, design changes, permit conditions, commitments and actions with owners.                      |

*Table 8.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Define the environmental and social screening objective, area of influence and appropriate level of reliance for the project stage.
- Build a controlled evidence base using official data, specialist studies, site evidence and stakeholder information.
- Identify environmental and social receptors without confusing mapped indicators with confirmed legal or ecological status.

- Develop proportionate survey scopes that account for seasonal windows, access, methodology and decision deadlines.
- Assess Solar PV, BESS, substation, access-road and export-route interfaces as one connected project.
- Apply the mitigation hierarchy and use alternatives analysis to influence layout and development strategy early.
- Use AI to organise and interrogate evidence while preventing fabricated certainty, unsupported significance ratings and confidentiality breaches.
- Produce a decision-ready constraint register, survey plan, action tracker and permitting narrative.

## 8.1 Introduction

Environmental and social constraints can determine whether a technically attractive site becomes a consentable and financeable project. A short distance between the project boundary and a protected area, watercourse, heritage asset, residence or community facility may be manageable—or it may fundamentally affect layout, programme, cost, reputation and acquisition value. The difference depends on evidence, impact pathways, authority requirements and the availability of credible alternatives.

Early screening is therefore not a substitute for environmental impact assessment, specialist survey or stakeholder engagement. Its purpose is to identify what is known, what may matter, what remains uncertain and what must happen before the next decision gate. A strong screen directs survey effort and design attention toward the issues that could change the project. A weak screen produces long lists of database features without explaining relevance, confidence or consequence.

Utility-scale Solar PV and BESS projects should be assessed as integrated developments. The generating area, battery compound, substation, access roads, temporary construction areas, water crossings and export route may interact with different receptors and authorities. Screening only the fenced PV area can miss the most material risks.

### ■ ENGINEERING INSIGHT

The purpose of early environmental and social screening is to influence decisions while alternatives still exist. A risk identified after layout, land rights and grid route are fixed is usually more expensive to manage.

## 8.2 What Early Screening Can and Cannot Establish

Desktop screening and reconnaissance provide strategic evidence, but their conclusions must remain proportionate to source quality and project maturity. They cannot establish final impact significance or legal compliance where specialist work is required.

| Screening Can Support                                                                                     | Screening Cannot Reliably Prove                                                                       |
|-----------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------|
| Identification of mapped designations, known receptors, apparent land uses and potential impact pathways. | Absence of protected species, archaeological remains, contamination, flood risk or community concern. |
| Comparison of site, layout, BESS and route alternatives using common criteria.                            | Final environmental or social acceptability of the preferred alternative.                             |

| Screening Can Support                                                            | Screening Cannot Reliably Prove                                                                               |
|----------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------|
| Definition of specialist survey needs, seasonal windows and authority questions. | Adequacy of a survey before its method, access, competence, timing and coverage are confirmed.                |
| Preliminary classification of constraints, confidence and potential materiality. | Final legal status, impact significance, permit outcome or lender acceptance.                                 |
| Early avoidance buffers and design contingencies.                                | Binding setback distances unless confirmed by current law, authority guidance or project-specific assessment. |
| Identification of stakeholders and engagement priorities.                        | Community consent, representation or absence of opposition.                                                   |

Table 8.2 - Appropriate limits of early environmental and social screening.

### COMMON MISTAKE

Do not report “no environmental constraints” because no designation appears in a rapid database search. The correct conclusion is limited to the sources, date, geography and topics actually reviewed.

## 8.3 Defining the Decision, Scope and Area of Influence

The screening brief should state the decision it will support, the project elements included, the geographic extent reviewed and the expected level of confidence. Acquisition, grid-route selection, planning strategy and lender review require different scopes.

| Decision Stage          | Primary Question                                                                | Typical Screening Output                                                      |
|-------------------------|---------------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| Origination             | Does the opportunity contain an obvious environmental or social fatal flaw?     | Rapid constraint map, source caveats, red flags and next-step recommendation. |
| Site shortlisting       | Which site or parcel configuration offers the strongest consent pathway?        | Comparative scoring, uncertainty register and survey priority.                |
| Acquisition             | What risks, costs, conditions and rights should be protected before commitment? | Due diligence register, conditions precedent and investigation budget.        |
| Layout development      | How should the project avoid or reduce sensitive interfaces?                    | Constraint-led layout principles, buffers, alternatives and design actions.   |
| Permit preparation      | What baseline and engagement evidence is required for submission?               | Survey plan, authority matrix, scoping questions and permit programme.        |
| Financing / transaction | Are material impacts, commitments and residual risks adequately controlled?     | Evidence matrix, compliance gaps, commitment register and lender actions.     |

Table 8.3 - Screening purpose by decision stage.

The area of influence should extend beyond the project boundary where impacts may occur. It may include access routes, temporary works, transmission corridors, drainage catchments, visual receptors, noise receptors, ecological connectivity, downstream water users and communities affected by labour or traffic.




Figure 8.1 - Establishing a decision-led environmental and social screening scope.

## 8.4 Evidence Hierarchy and Source Control

Environmental and social screening often combines sources created for different purposes, scales and dates. Each source should be recorded with its owner, date, geographic coverage, resolution, limitations and intended use.

| Evidence Tier                       | Typical Source                                                                                                      | Professional Use                                                                                              |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------|
| Tier 1 - Primary official           | Current legislation, authority registers, protected-area portals, permit decisions and official spatial datasets.   | Highest priority for legal and designation status, subject to interpretation and currency checks.             |
| Tier 2 - Project specialist         | Ecology, hydrology, noise, heritage, landscape, social, traffic and soil studies prepared by competent specialists. | Project-specific baseline and professional interpretation; verify scope, season and revision.                 |
| Tier 3 - Controlled project         | Layouts, land plans, route studies, surveys, risk registers, stakeholder records and construction assumptions.      | Defines what is proposed and how impacts may arise.                                                           |
| Tier 4 - Field / remote observation | Site photographs, orthophotos, satellite imagery, drone data and reconnaissance notes.                              | Supports visible conditions and change detection; does not establish legal status or specialist significance. |
| Tier 5 - Secondary / reported       | Academic papers, commercial databases, media, local statements and informal interviews.                             | Useful context and leads; requires verification before decision reliance.                                     |
| Tier 6 - AI-generated               | Summaries, classifications, draft tables and inferred relationships generated by AI.                                | Working material only; every factual and technical statement requires source validation.                      |

Table 8.4 - Environmental and social evidence hierarchy.

### BEST PRACTICE

Maintain a source register with retrieval date, spatial reference, revision and licence restrictions. A map screenshot without metadata is not a controlled evidence source.

## 8.5 Regulatory, Permitting and Lender Context

Screening should identify the decisions, authorities and standards that may govern the project without attempting to replace legal advice. National, regional and local requirements may differ, and lender expectations can extend beyond minimum legal compliance.

| Context                        | Questions for Early Screening                                                                                           |
|--------------------------------|-------------------------------------------------------------------------------------------------------------------------|
| Planning / development consent | Which authority determines the application, what environmental documentation is required and what consultation applies? |
| Environmental assessment       | Is screening, scoping, environmental impact assessment or another formal process likely?                                |
| Protected sites / species      | Which competent authorities and derogation, assessment or consultation processes may apply?                             |
| Water and flood                | What permits or consents apply to abstraction, discharge, crossings, drainage and works near water?                     |
| Forestry / vegetation          | Are clearance, tree protection, wildfire, restoration or compensatory planting requirements relevant?                   |
| Heritage                       | What review, survey, monitoring or chance-find obligations may apply?                                                   |
| Noise / air / traffic          | Which construction and operational limits, methods and authority reviews are relevant?                                  |
| Land and community             | What public rights, customary uses, resettlement, livelihood or engagement obligations require assessment?              |
| Financing standards            | Do investor or lender policies require additional biodiversity, labour, human-rights or stakeholder evidence?           |

Table 8.5 - Regulatory and lender questions for early screening.

## 8.6 Building the Constraint Baseline

The baseline should be assembled by theme and geography, not as an unstructured collection of maps. Each feature should be linked to the relevant project element, possible impact pathway, evidence confidence and next action.

| Baseline Theme     | Examples of Evidence                                                                                            | Output                                                      |
|--------------------|-----------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| Biodiversity       | Designations, habitats, species records, connectivity, woodland, water features and survey history.             | Constraint map, receptor register and seasonal survey plan. |
| Water / soils      | Catchments, flood data, wetlands, channels, groundwater, erosion, agricultural soils and contamination records. | Drainage and soil-risk screen with specialist scopes.       |
| Landscape / visual | Topography, settlements, roads, viewpoints, protected landscapes and screening vegetation.                      | Preliminary zone of visibility and receptor strategy.       |

| Baseline Theme          | Examples of Evidence                                                                                           | Output                                                   |
|-------------------------|----------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|
| Noise / vibration       | Residences, schools, hospitals, industrial sources, roads and proposed equipment locations.                    | Receptor register, baseline need and layout contingency. |
| Heritage                | Listed assets, archaeological records, historic landscapes and field indicators.                               | Heritage risk map and investigation sequence.            |
| Social / land use       | Population, livelihoods, rights of way, recreation, agriculture, community facilities and stakeholder records. | Social-context profile and engagement priorities.        |
| Infrastructure / routes | Roads, rail, utilities, water crossings, grid assets and construction corridors.                               | Interface register and route alternatives.               |

Table 8.6 - Core environmental and social baseline themes.

## 8.7 Biodiversity, Habitats and Ecological Connectivity

Biodiversity screening should move beyond distance to designated sites. It should consider habitats within the project, ecological connectivity, water features, woodland edges, species movement and the cumulative effect of multiple project elements.

| Screening Topic       | Questions                                                                                     | Typical Follow-Up                                                                        |
|-----------------------|-----------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------|
| Designated areas      | Is the project within, adjacent to or functionally connected to a protected or priority area? | Authority consultation and specialist assessment of impact pathways.                     |
| Habitats              | What mapped or visible habitats may be sensitive, scarce or difficult to restore?             | Phase-appropriate habitat survey and condition assessment.                               |
| Species records       | Are records relevant to current habitat, season and likely project effects?                   | Targeted surveys by competent specialists; absence of records is not absence of species. |
| Connectivity          | Could fencing, clearance, roads or lighting interrupt movement corridors?                     | Connectivity mapping and design measures such as gaps, crossings or buffers.             |
| Water-linked ecology  | Could drainage, crossings, sediment or water-quality changes affect aquatic receptors?        | Hydrology and aquatic ecology coordination.                                              |
| Invasive species      | Are invasive plants or pathogens known or visible?                                            | Biosecurity plan, survey and control strategy.                                           |
| Restoration potential | Can disturbed or low-value areas be restored or enhanced?                                     | Biodiversity management objectives and measurable commitments.                           |

Table 8.7 - Biodiversity screening questions and follow-up actions.



**COMMON MISTAKE**

AI may help organise habitat and species evidence, but it must not identify protected species or assign ecological significance from poor-quality imagery without competent specialist verification.

## 8.8 Birds, Bats and Other Mobile Species

Large Solar PV sites, overhead lines, lighting, fencing and BESS infrastructure may interact with mobile species differently across seasons. Survey strategy should be based on habitat, records, migration context, authority requirements and the proposed design—not on a standard checklist alone.

| Receptor / Pathway          | Potential Project Interaction                                                        | Early Design Response                                                         |
|-----------------------------|--------------------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| Breeding birds              | Habitat loss, disturbance, vegetation clearance and construction timing.             | Avoid high-value habitat, retain buffers and plan seasonal controls.          |
| Wintering / migratory birds | Loss of feeding or resting area, collision risk on associated lines and disturbance. | Seasonal survey and route / layout alternatives.                              |
| Raptors                     | Foraging habitat, nesting disturbance and line collision / electrocution interfaces. | Nest surveys, line design review and construction controls.                   |
| Bats                        | Roosts, commuting routes, woodland edges, water features and lighting.               | Retain corridors, control lighting and survey relevant structures / habitats. |
| Large mammals               | Fence barrier, movement disruption and vehicle interaction.                          | Crossings, fence design, route controls and habitat connectivity.             |
| Reptiles / amphibians       | Ground disturbance, drainage and habitat fragmentation.                              | Micro-siting, seasonal methods and habitat management.                        |

Table 8.8 - Mobile species impact pathways and early responses.

## 8.9 Water, Wetlands, Flooding and Erosion

Water-related impacts often connect environmental, civil and permitting risk. A drainage design that protects equipment may still transfer peak flow or sediment downstream. Screening should consider the catchment, not only mapped channels inside the boundary.

| Topic                     | Potential Risk                                                          | Evidence / Action                                                              |
|---------------------------|-------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Floodplain and flow paths | Equipment exposure, access loss, displaced flow and downstream impact.  | Official flood data, topography, hydrology and climate-sensitivity assessment. |
| Wetlands / riparian zones | Habitat loss, hydrological change and permit complexity.                | Delineation, seasonal review and avoidance buffers.                            |
| Crossings                 | Channel disturbance, fish passage, erosion and maintenance constraints. | Crossing inventory, authority consultation and alternatives assessment.        |

| Topic                | Potential Risk                                                      | Evidence / Action                                                    |
|----------------------|---------------------------------------------------------------------|----------------------------------------------------------------------|
| Construction runoff  | Sediment, pollution and channel instability.                        | Erosion and sediment-control concept linked to phasing.              |
| Groundwater          | Dewatering, contamination pathways and foundation / trench effects. | Hydrogeological review and geotechnical coordination.                |
| Operational drainage | Concentrated runoff from roads, pads and BESS compound.             | Integrated drainage concept and discharge / infiltration assessment. |

Table 8.9 - Water and erosion screening framework.

## 8.10 Landscape, Visual Effects, Glint and Lighting

Visual effects depend on topography, receptor sensitivity, viewing direction, distance, duration and the character of the existing landscape. Screening should identify where visibility may matter and how layout, setbacks, vegetation and equipment placement can reduce effects.

| Interface                     | Screening Question                                                              | Potential Mitigation                                                    |
|-------------------------------|---------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| Settlements / residences      | Which receptors may have open, elevated or close views?                         | Setbacks, lower-profile equipment, planting and micro-siting.           |
| Roads / rail / aviation       | Could reflections or visibility create distraction or safety concerns?          | Glint-and-glare assessment, orientation review and screening.           |
| Protected / valued landscapes | Does the project affect landscape character, scenic routes or designated views? | Alternative layout, reduced extent and landscape strategy.              |
| BESS / substation             | Are taller, brighter or industrial elements prominent from sensitive locations? | Compound location, enclosure, colour, lighting and planting.            |
| Night lighting                | Is continuous or poorly controlled lighting proposed?                           | Task-based, shielded, low-spill and emergency-only lighting principles. |

Table 8.10 - Landscape, visual, glint and lighting screening.

## 8.11 Noise, Vibration and Air Quality

Operational noise is often most material for BESS HVAC, inverters, transformers and substations, while construction introduces traffic, piling, earthworks, dust and temporary plant. Early screening should preserve layout options until receptor and source data are sufficient.

| Source / Phase            | Relevant Receptors                                                 | Early Action                                                                                |
|---------------------------|--------------------------------------------------------------------|---------------------------------------------------------------------------------------------|
| BESS HVAC and auxiliaries | Residences, schools, care facilities and quiet recreational areas. | Confirm receptor locations, preliminary source assumptions and acoustic design contingency. |
| Transformers / inverters  | Nearby dwellings and sensitive land uses.                          | Cluster and orientation review, low-noise options and setback sensitivity.                  |

| Source / Phase       | Relevant Receptors                                                  | Early Action                                                             |
|----------------------|---------------------------------------------------------------------|--------------------------------------------------------------------------|
| Construction traffic | Villages, schools, narrow roads, junctions and roadside properties. | Traffic route study, timing controls and community engagement.           |
| Piling / civil works | Close receptors, livestock, structures and sensitive fauna.         | Construction method options, working-hour controls and monitoring needs. |
| Dust / exhaust       | Residents, crops, roads, water and habitat.                         | Dust-control plan, route surfacing and weather limits.                   |
| Vibration            | Heritage assets, fragile structures and nearby utilities.           | Method review, condition surveys and monitoring thresholds.              |

Table 8.11 - Noise, vibration and air-quality interfaces.

## 8.12 Cultural Heritage and Archaeology

Heritage screening should include designated assets, archaeological potential, historic landscapes, buried remains and intangible or community-valued places. Distance alone may not determine impact, particularly where setting and views are important.

| Heritage Topic           | Screening Question                                                            | Follow-Up                                                                            |
|--------------------------|-------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| Designated assets        | Could the project affect the asset physically or through its setting?         | Specialist setting assessment and authority consultation.                            |
| Archaeological potential | Do records, landform, soil marks or historic mapping indicate buried remains? | Desk-based assessment, geophysics, trial trenching or watching brief as appropriate. |
| Historic landscape       | Would large-scale change alter important patterns or relationships?           | Landscape-heritage coordination and alternatives review.                             |
| Built heritage           | Could traffic, vibration, drainage or access works affect structures?         | Condition survey and method controls.                                                |
| Chance finds             | Are construction teams prepared for unexpected discoveries?                   | Chance-find procedure, training and stop-work protocol.                              |

Table 8.12 - Heritage and archaeology screening framework.

## 8.13 Land Use, Agriculture, Soils and Livelihoods

Land may have technical, economic, cultural and livelihood value that is not visible in ownership records. Screening should consider current and seasonal use, agricultural quality, irrigation, grazing, forestry, public access and the distribution of project benefits and impacts.

| Topic              | Questions                                                                    | Potential Development Response                                                 |
|--------------------|------------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Agricultural value | What crops, grazing, soil quality, irrigation and seasonal operations occur? | Avoid highest-value areas, adapt layout, maintain access and plan restoration. |

| Topic                      | Questions                                                                   | Potential Development Response                                    |
|----------------------------|-----------------------------------------------------------------------------|-------------------------------------------------------------------|
| Tenants / users            | Who uses the land and who may experience loss or disruption?                | Verify rights, livelihoods and engagement needs before agreement. |
| Soil resources             | Could stripping, compaction, erosion or contamination reduce soil function? | Soil management plan and construction controls.                   |
| Forestry / vegetation use  | Are woodland, fuelwood, grazing or community collection important?          | Alternative siting and access / compensation assessment.          |
| Recreation / public access | Are tracks, trails, hunting, tourism or informal uses present?              | Route continuity, safety controls and engagement.                 |
| Decommissioning            | Can land function be restored and commitments enforced?                     | Restoration criteria, security and long-term management.          |

Table 8.13 - Land-use, soils and livelihood screening.

## 8.14 Communities, Stakeholders and Social Context

Stakeholder screening should identify who may be affected, who can influence the project, what information is already public and what engagement is appropriate at the current stage. It should not assume that formal organisations represent every affected person.

| Stakeholder Group                      | Potential Interest / Impact                                             | Early Engagement Objective                                                  |
|----------------------------------------|-------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| Landowners and occupiers               | Rights, payments, access, operations and long-term obligations.         | Confirm authority, use, expectations and grievance route.                   |
| Nearby residents                       | Views, noise, traffic, safety, property access and trust.               | Understand concerns, explain process and record commitments.                |
| Local authorities                      | Planning, roads, drainage, emergency response and community priorities. | Clarify procedure, evidence expectations and interfaces.                    |
| Environmental / heritage bodies        | Protected receptors, survey methods and mitigation.                     | Confirm data, consultation and assessment requirements.                     |
| Community organisations                | Local services, recreation, employment and cumulative change.           | Map interests without assuming universal representation.                    |
| Emergency services                     | BESS response, access, water, isolation and communication.              | Identify information and design coordination needs.                         |
| Vulnerable or under-represented groups | Potential unequal access to information, benefits or remedy.            | Use inclusive methods and avoid relying only on digital or formal channels. |

Table 8.14 - Stakeholder groups and early engagement objectives.

### ENGINEERING INSIGHT

Engagement is not evidence that impacts are acceptable. It is a process for obtaining information, understanding perspectives, improving design and establishing accountable communication.

## 8.15 Labour, Human Rights, Security and Supply-Chain Interfaces

Even at development stage, project choices influence labour, security, accommodation, procurement and community risks. Screening should identify material interfaces and the governance required later, without making unsupported claims about suppliers or contractors.

| Interface                   | Potential Risk                                                                        | Early Control                                                               |
|-----------------------------|---------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| Construction labour         | Influx, accommodation pressure, worker welfare, discrimination and grievance gaps.    | Workforce-management principles and contractor requirements.                |
| Security                    | Excessive force, conflict with land users, privacy and poor complaint handling.       | Proportionate security strategy, training and incident process.             |
| Supply chain                | Forced labour, unsafe work, environmental harm or traceability gaps.                  | Supplier due diligence and contractual evidence requirements.               |
| Community health and safety | Traffic, open excavations, electrical hazards, fire and restricted access.            | Design, construction and communication controls.                            |
| Data and privacy            | Unauthorised recording, personal-data exposure and misuse of stakeholder information. | Consent, access controls, retention limits and approved systems.            |
| Grievance mechanism         | Concerns escalate because there is no accessible route for response and remedy.       | Documented, transparent and trackable process appropriate to project stage. |

*Table 8.15 - Labour, human-rights, security and supply-chain interfaces.*

## 8.16 BESS-Specific Environmental and Social Considerations

BESS compounds introduce concentrated equipment, auxiliary loads, cooling, fire and emergency-response requirements. Early siting should compare alternatives using environmental, social and engineering criteria rather than selecting the area closest to the substation by default.

| BESS Topic                  | Screening Questions                                                                      | Required Coordination                                          |
|-----------------------------|------------------------------------------------------------------------------------------|----------------------------------------------------------------|
| Fire and emergency response | Are access, separation, water strategy, isolation and responder information practicable? | Fire engineer, authority, emergency services and OEM inputs.   |
| Noise                       | What are the nearest sensitive receptors and cumulative sources?                         | Acoustic baseline, source data, layout and operating strategy. |
| Drainage / water            | Could firefighting water, contaminated runoff or flood exposure create impact?           | Drainage, containment, hydrology and emergency planning.       |

| BESS Topic                   | Screening Questions                                                        | Required Coordination                                               |
|------------------------------|----------------------------------------------------------------------------|---------------------------------------------------------------------|
| Hazardous materials / waste  | What batteries, coolants, fuels and end-of-life materials require control? | Inventory, spill response, transport, recycling and waste planning. |
| Thermal / ventilation        | Could heat rejection or plume pathways affect receptors or vegetation?     | OEM design, fire analysis and micro-siting.                         |
| Visual / lighting / security | Is the compound prominent or close to community routes?                    | Enclosure, planting, controlled lighting and security design.       |
| Expansion / augmentation     | Is sufficient land and environmental contingency retained?                 | Long-term layout, permitting and land-rights review.                |

Table 8.16 - BESS-specific environmental and social screening.

## 8.17 Access Roads, Substations and Export Routes

Linear and off-site infrastructure can create more environmental and social complexity than the generation site. Route comparison should include construction work areas, crossings, land use, sensitive receptors, authority interfaces and restoration—not only route length.

| Route Criterion          | Questions for Comparison                                                                               |
|--------------------------|--------------------------------------------------------------------------------------------------------|
| Biodiversity / water     | How many sensitive habitats, channels, wetlands, woodland edges and connectivity features are crossed? |
| Land / livelihoods       | How many parcels, occupiers, high-value crops and operational accesses are affected?                   |
| Community / traffic      | Which settlements, schools, public roads and recreational routes experience disruption?                |
| Heritage / landscape     | Could trenching, towers, roads or substations affect assets or important views?                        |
| Constructability         | What temporary width, compounds, crossings, slopes and restoration are required?                       |
| Permitting / authority   | How many agencies and separate permissions are triggered?                                              |
| Resilience / maintenance | Can the route be inspected, repaired and accessed without recurring impact?                            |

Table 8.17 - Environmental and social criteria for infrastructure route comparison.

## 8.18 Alternatives, Cumulative Effects and Climate Resilience

Alternatives analysis is strongest when completed before the preferred option becomes commercially entrenched. It should compare sites, layouts, technology, routes, construction methods and timing using transparent criteria.

| Assessment Area           | Key Question                                                                                                       |
|---------------------------|--------------------------------------------------------------------------------------------------------------------|
| Site / parcel alternative | Can a different land configuration avoid the most sensitive receptor or reduce fragmentation?                      |
| Layout alternative        | Can equipment, roads, BESS or substation be repositioned without undermining project viability?                    |
| Technology alternative    | Would fixed tilt, tracker choice, foundation type, cable method or quieter equipment reduce impacts?               |
| Route alternative         | Does a longer route avoid materially greater land, ecology, heritage or community risk?                            |
| Timing alternative        | Can construction avoid breeding, harvest, tourism, flood or community-sensitive periods?                           |
| Cumulative effects        | How does the project interact with existing and planned developments, traffic, grid works and landscape change?    |
| Climate resilience        | Could future heat, wildfire, flood, drought, erosion or water scarcity change baseline and mitigation performance? |

Table 8.18 - Alternatives, cumulative effects and climate-resilience questions.

## 8.19 Survey Strategy and Seasonal Windows

A survey plan should be a decision programme, not a list of disciplines. Each survey should state why it is required, what question it will answer, when it must occur, how much land access is needed and what decision depends on the result.

| Survey / Study         | Decision Question                                                          | Timing / Dependency                                                               |
|------------------------|----------------------------------------------------------------------------|-----------------------------------------------------------------------------------|
| Habitat / ecology      | What receptors and avoidance areas should shape the layout?                | Season and methodology defined by habitat, species and authority requirements.    |
| Bird / bat             | Could construction, operation or associated lines create material effects? | May require multiple seasons; begin early where risk indicators exist.            |
| Hydrology / flood      | What areas, crossings and drainage concepts are viable?                    | Needs topography, catchment and design assumptions; consider climate sensitivity. |
| Noise                  | Can BESS and electrical equipment comply at sensitive receptors?           | Requires reliable receptor coordinates and source / operating assumptions.        |
| Landscape / visual     | Where are significant views and what mitigation is credible?               | Depends on layout, topography and agreed representative viewpoints.               |
| Heritage / archaeology | Is avoidance, investigation or monitoring required?                        | Sequence desk study, geophysics and intrusive work with land access.              |
| Traffic / logistics    | Which routes and construction assumptions are acceptable?                  | Coordinate with abnormal-load, bridge and community evidence.                     |

| Survey / Study               | Decision Question                                                  | Timing / Dependency                                              |
|------------------------------|--------------------------------------------------------------------|------------------------------------------------------------------|
| Social baseline / engagement | Who is affected and how should impacts and commitments be managed? | Begin before irreversible choices; maintain through development. |

Table 8.19 - Decision-led survey and study strategy.

### COMMON MISTAKE

Missing a seasonal survey window can delay a project by a year. Survey procurement, land access, method approval and weather contingency should be treated as critical-path development activities.

## 8.20 Applying the Mitigation Hierarchy

The mitigation hierarchy should be applied in sequence. Avoidance usually provides the greatest certainty and lowest long-term management burden. Compensation should not be used to justify avoidable impacts.



Figure 8.2 - Mitigation hierarchy and adaptive management sequence.

| Hierarchy Step      | Application to Solar PV / BESS                                                                            |
|---------------------|-----------------------------------------------------------------------------------------------------------|
| Avoid               | Exclude sensitive habitat, move BESS from a receptor, reroute access or retain an ecological corridor.    |
| Minimise            | Reduce footprint, control lighting, lower noise, time works and use less disruptive construction methods. |
| Restore             | Reinstate temporary work areas, soils, drainage and vegetation after construction.                        |
| Compensate / offset | Provide approved measures for residual impacts only where permitted and credible.                         |
| Monitor             | Measure whether commitments and performance objectives are achieved.                                      |
| Adapt               | Trigger corrective actions when monitoring shows unexpected or unacceptable outcomes.                     |

Table 8.20 - Applying the mitigation hierarchy to project development.

## 8.21 AI-Assisted Environmental and Social Workflow

AI is valuable when it operates inside a controlled evidence process. It can accelerate indexing, comparison and drafting, but it should never create unreferenced facts or replace specialist significance assessment.





Figure 8.3 - Human-controlled AI workflow for environmental and social screening.

| AI Task                   | Useful Output                                                                      | Mandatory Human Control                                             |
|---------------------------|------------------------------------------------------------------------------------|---------------------------------------------------------------------|
| Document triage           | Source register, topic tags, dates, revisions and missing documents.               | Verify document identity, completeness and currency.                |
| Requirement extraction    | Draft authority / permit matrix and evidence checklist.                            | Validate against current official requirements and legal advice.    |
| Cross-document comparison | Contradictions in boundaries, receptor distances, survey coverage and commitments. | Check drawings, coordinates, methodology and source context.        |
| Risk drafting             | Structured issue, impact pathway, action and owner fields.                         | Specialists assign significance, adequacy and acceptance.           |
| Meeting preparation       | Questions for authorities, consultants, landowners and emergency services.         | Ensure appropriate disclosure and engagement strategy.              |
| Report drafting           | Executive summary, tables and action tracker.                                      | Remove unsupported claims and confirm every statement is traceable. |

Table 8.21 - Appropriate AI uses and professional controls.

#### AI TIP

Do not upload sensitive biodiversity records, personal stakeholder data, privileged legal advice or confidential land information to an unapproved AI system.

## 8.22 Evidence Confidence, Constraint Severity and Action Priority

Confidence and severity should be assessed separately. An uncertain indication may justify urgent action if the potential consequence is high. A confirmed feature may be low priority if it can be readily avoided.

| Evidence Class | Definition                                                                                   |
|----------------|----------------------------------------------------------------------------------------------|
| Verified       | Confirmed by an authoritative current source or competent project-specific study.            |
| Corroborated   | Supported by multiple independent sources but not fully confirmed for the project.           |
| Indicative     | Plausible signal from remote data, records, field reconnaissance or stakeholder information. |

| Evidence Class | Definition                                                                    |
|----------------|-------------------------------------------------------------------------------|
| Assumed        | Working assumption required for planning; not supported by adequate evidence. |
| Unknown        | Material information has not been obtained or cannot yet be determined.       |

Table 8.22 - Environmental and social evidence-confidence classes.

| Constraint Level     | Decision Meaning                                                                                     | Typical Response                                                           |
|----------------------|------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------|
| Potential fatal flaw | Could prevent consent, financing or responsible development with no credible alternative identified. | Escalate; obtain specialist and legal evidence before commitment.          |
| Major                | Likely material layout, cost, programme, stakeholder or permit consequence.                          | Protect alternatives and complete priority investigation before next gate. |
| Moderate             | Manageable through design, survey, mitigation and commitments.                                       | Track with owner, timing and acceptance criteria.                          |
| Minor / opportunity  | Limited adverse effect or potential enhancement / optimisation.                                      | Record and integrate at the appropriate design stage.                      |

Table 8.23 - Constraint severity and decision response.

## 8.23 Worked Example - Early Environmental and Social Screen

A developer is evaluating a 300 MWac Solar PV project with a 150 MW / 300 MWh BESS. The site comprises agricultural plateaus, an eastern seasonal drainage corridor, a western woodland edge and a preferred BESS area near an existing substation. The shortest export route crosses an orchard, a local road and a stream. Several residences and a village lie within the wider area of influence.

| Topic         | Available Evidence                                                             | Initial Uncertainty                                                                                  |
|---------------|--------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------|
| Biodiversity  | Official designations, habitat mapping, imagery and one spring reconnaissance. | Seasonal species use and woodland / drainage connectivity not established.                           |
| Water         | Regional flood mapping and coarse terrain model.                               | Local flow paths, wet-season extent and crossing design unknown.                                     |
| Noise         | Preliminary equipment schedule and mapped residences.                          | Receptor coordinates, background levels and OEM sound data incomplete.                               |
| Heritage      | National records and historic mapping.                                         | Buried archaeological potential in plateau areas not tested.                                         |
| Land / social | Owner schedule and municipal statistics.                                       | Tenant use, orchard operations, village traffic concerns and community facilities need confirmation. |

| Topic          | Available Evidence                            | Initial Uncertainty                                                                      |
|----------------|-----------------------------------------------|------------------------------------------------------------------------------------------|
| BESS emergency | Concept compound and generic OEM information. | Responder access, water / containment strategy and authority expectations not confirmed. |

Table 8.24 - Worked-example evidence and uncertainty baseline.

| Finding                                                                                     | Impact Pathway                                                                     | Confidence / Severity       | Recommended Action                                                                           |
|---------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------|-----------------------------|----------------------------------------------------------------------------------------------|
| Eastern drainage corridor contains wet vegetation and connects to a downstream watercourse. | PV rows, roads and trenches may alter runoff, sediment and habitat connectivity.   | Corroborated / Major        | Apply provisional avoidance corridor; commission topographic, hydrology and habitat surveys. |
| Western woodland edge may provide bat and bird movement habitat.                            | Clearance, lighting and fencing may disrupt connectivity.                          | Indicative / Moderate-Major | Retain setback contingency; complete habitat and seasonal species assessment.                |
| Preferred BESS area is approximately 280 m from nearest mapped residence.                   | HVAC, transformer and emergency operations may create noise / perception concerns. | Indicative / Major          | Verify receptor; obtain source data; compare alternative compound and complete noise study.  |
| Shortest export route crosses active orchard and stream.                                    | Livelihood disruption, water crossing, temporary works and restoration risk.       | Verified / Major            | Compare road-corridor alternative and engage occupier before route commitment.               |
| Plateau has archaeological records within wider landscape but no project survey.            | Ground disturbance may affect buried remains and programme.                        | Indicative / Moderate       | Desk-based heritage assessment followed by agreed field investigation.                       |
| Village access road passes school and narrow residential section.                           | Construction traffic may create safety, noise and community opposition.            | Verified / Major            | Traffic route alternatives, school-hour controls and early authority / community engagement. |

Table 8.25 - Worked-example constraints and actions.

The screening does not identify a confirmed fatal flaw. It changes the preferred development strategy by creating provisional exclusion areas, retaining two BESS alternatives, reopening the export-route comparison and treating ecology, hydrology, noise, heritage and traffic surveys as programme-critical activities. Acquisition approval is conditioned on survey access, budget and the ability to maintain layout and route alternatives.

| Decision Area  | Before Screening                                      | After Screening                                                                         |
|----------------|-------------------------------------------------------|-----------------------------------------------------------------------------------------|
| PV usable area | Full plateau and eastern lowland assumed developable. | Drainage and woodland-edge contingencies reduce near-term design envelope.              |
| BESS siting    | Nearest-to-substation option preferred.               | Two options retained pending noise, drainage, access and emergency-response assessment. |
| Export route   | Shortest route assumed optimal.                       | Alternative along existing transport corridor progressed in parallel.                   |

| Decision Area        | Before Screening                              | After Screening                                                                                            |
|----------------------|-----------------------------------------------|------------------------------------------------------------------------------------------------------------|
| Survey programme     | Studies planned after acquisition.            | Seasonal and authority-critical surveys mobilised before commitment where possible.                        |
| Stakeholder strategy | General consultation planned at permit stage. | Targeted early engagement with roads authority, emergency services, occupiers and village representatives. |

Table 8.26 - Worked-example decision changes created by screening.

## 8.24 Common Mistakes

| Mistake                                       | Why It Fails                                                        | Better Practice                                                            |
|-----------------------------------------------|---------------------------------------------------------------------|----------------------------------------------------------------------------|
| Screening only the fenced site                | Misses access, grid route, drainage, visual and community impacts.  | Assess the complete project and area of influence.                         |
| Treating database absence as receptor absence | Records may be incomplete, old or spatially coarse.                 | State source limitations and plan proportionate verification.              |
| Using fixed generic buffers                   | May be over- or under-protective and lack legal basis.              | Use provisional buffers pending current authority and specialist evidence. |
| Starting surveys without decision logic       | Creates data that may not answer permit or layout questions.        | Link each survey to receptor, method, decision and deadline.               |
| Fixing layout before baseline work            | Removes avoidance options and increases mitigation cost.            | Maintain design contingency until material constraints are understood.     |
| Ignoring social and livelihood use            | Ownership records do not capture every affected user or value.      | Verify occupiers, seasonal use and stakeholder context.                    |
| Letting AI assign significance                | AI lacks project-specific competence and accountability.            | Use AI for organisation; specialists determine significance and adequacy.  |
| Failing to track commitments                  | Promised mitigation becomes disconnected from design and contracts. | Maintain a controlled commitment register with owners and evidence.        |

Table 8.27 - Common environmental and social screening mistakes.

## 8.25 Best Practices

- Begin with the decision and project configuration, not with a generic list of environmental topics.
- Assess the full area of influence, including roads, routes, drainage, temporary works, BESS and substation interfaces.
- Record every source with date, owner, revision, scale, limitations and permitted use.
- Separate verified facts, corroborated evidence, indications, assumptions and unknowns.
- Protect layout, route and technology alternatives until material constraints are resolved.
- Procure surveys early enough to meet seasonal windows and decision deadlines.

- Coordinate ecology, hydrology, civil, acoustic, heritage, land, grid and stakeholder workstreams.
- Apply avoidance before minimisation, restoration and compensation.
- Translate every material finding into an owner, due date, decision gate and closure evidence.
- Use AI only in approved systems and require traceability and specialist validation.

## 8.26 Environmental and Social Review Checklist

| Review Area             | Validation Question                                                                                   | Check                    |
|-------------------------|-------------------------------------------------------------------------------------------------------|--------------------------|
| Decision / scope        | Is the screening decision, project configuration, stage and area of influence defined?                | <input type="checkbox"/> |
| Evidence                | Are sources current, controlled, traceable and appropriate for the conclusion?                        | <input type="checkbox"/> |
| Regulatory              | Are relevant authorities, permits, assessment procedures and lender requirements identified?          | <input type="checkbox"/> |
| Biodiversity            | Are designations, habitats, connectivity, water features and seasonal survey needs considered?        | <input type="checkbox"/> |
| Water / soils           | Are flood, drainage, wetlands, erosion, groundwater and soil impacts screened?                        | <input type="checkbox"/> |
| Landscape / noise       | Are sensitive visual and acoustic receptors and equipment assumptions reviewed?                       | <input type="checkbox"/> |
| Heritage                | Are designated assets, setting and archaeological potential addressed?                                | <input type="checkbox"/> |
| Land / livelihoods      | Are occupiers, agricultural operations, rights of way and livelihood impacts considered?              | <input type="checkbox"/> |
| Stakeholders            | Are affected and influential groups mapped with an appropriate engagement approach?                   | <input type="checkbox"/> |
| BESS                    | Are fire, emergency, noise, drainage, waste, lighting, security and augmentation interfaces included? | <input type="checkbox"/> |
| Routes / off-site works | Are access, substations, export routes, crossings and temporary works assessed?                       | <input type="checkbox"/> |
| Alternatives            | Have credible site, layout, route, technology and timing alternatives been preserved and compared?    | <input type="checkbox"/> |

| Review Area | Validation Question                                                                           | Check                    |
|-------------|-----------------------------------------------------------------------------------------------|--------------------------|
| Surveys     | Does every material gap have a method, season, owner, access requirement and deadline?        | <input type="checkbox"/> |
| Mitigation  | Is the hierarchy applied in sequence and linked to design / contractual commitments?          | <input type="checkbox"/> |
| AI control  | Are confidentiality, source attribution, factual verification and specialist review enforced? | <input type="checkbox"/> |
| Decision    | Are fatal flaws, major constraints, conditions and actions explicit for the next gate?        | <input type="checkbox"/> |

Table 8.28 - Environmental and social screening review checklist.

## 8.27 Prompt Toolkit

### Level 1 - Quick Prompt

#### QUICK PROMPT

Act as a Senior Environmental and Social Development Advisor for utility-scale Solar PV and BESS. Using the supplied boundary, concept layout, route plan and source list, prepare an early constraint checklist covering biodiversity, water, landscape, noise, heritage, land use, community, access and BESS. For each topic state the available evidence, uncertainty, potential project consequence and next professional action. Do not infer legal status, protected species presence or impact significance without verified specialist evidence.

### Level 2 - Professional Prompt

#### PROFESSIONAL PROMPT

Prepare a structured environmental and social screening report for the supplied utility-scale Solar PV and co-located BESS project. Establish the project elements and area of influence; create a source and revision register; identify receptors and impact pathways; classify evidence as verified, corroborated, indicative, assumed or unknown; compare PV, BESS, substation, access and export-route alternatives; define provisional avoidance areas; develop a seasonal survey and authority-engagement plan; and produce a priority action register with owner, deadline, decision gate and closure evidence. Clearly separate environmental observation from legal, ecological, social and engineering conclusions requiring specialist validation.

## Level 3 - Expert Prompt

### EXPERT PROMPT

You are acting as the Lead Environmental and Social Technical Advisor supporting acquisition and early permitting of a utility-scale Solar PV and BESS project. Review all supplied controlled evidence, including official spatial data, layouts, land information, field records, specialist studies, stakeholder records and grid / route assumptions. Prepare a decision-grade report covering regulatory context, area of influence, biodiversity, water, soils, landscape, glint, noise, air, heritage, land use, livelihoods, community health and safety, labour, security, supply chain, BESS emergency interfaces, routes, cumulative effects and climate resilience. For each material issue define receptor, project activity, impact pathway, evidence confidence, potential severity, credible alternatives, mitigation hierarchy, survey / consultation requirement, programme implication, CAPEX contingency and acquisition or investment condition. Do not fabricate survey findings, assign final significance outside professional competence or treat AI-generated text as evidence.

## 8.28 Recommended Reference Framework

The reference framework must be adapted to the current laws, authorities, lender requirements and project jurisdiction. It should include:

- Current national, regional and local planning, environmental-assessment, biodiversity, water, heritage, forestry, waste, noise and public-consultation requirements.
- Official protected-area, species, flood, water, land-use, heritage, population, road and planning datasets with documented metadata.
- Competent-authority guidance on assessment scope, survey methods, seasonal coverage, mitigation and monitoring.
- Applicable lender or investor environmental and social policies, performance standards and exclusion requirements.
- Current BESS fire, emergency-response, hazardous-material, acoustic, waste, transport and occupational-safety guidance.
- Project land agreements, stakeholder protocols, grievance procedures, data-protection rules and approved AI / cybersecurity policies.
- Professional ecology, hydrology, landscape, acoustic, heritage, social, traffic and soil standards relevant to the specialist work.

### STANDARDS REFERENCE

Always verify the current official source and competent authority. Regulations, designation boundaries, survey guidance and lender requirements can change during the development period.

## 8.29 Chapter Summary

Environmental and social constraint screening converts broad uncertainty into a controlled development strategy. It defines the complete project and area of influence, assembles traceable evidence, identifies receptors and impact pathways, preserves alternatives and directs specialist work toward the decisions that matter. The strongest screens influence land, layout, route, BESS siting, programme and acquisition conditions before those choices become difficult to change.

Artificial Intelligence can accelerate source indexing, evidence comparison, contradiction checks, prompt preparation, register drafting and management reporting. It cannot establish species presence, legal compliance, impact significance, community acceptance or permit outcome. These conclusions require current official evidence and competent professional judgement.

## 8.30 Key Takeaways

- Screen the complete project and area of influence—not only the PV boundary.
- Define the decision, level of reliance and evidence limitations before beginning analysis.
- Use official and project-specific sources, and maintain a controlled source register.
- Separate mapped indicators from confirmed legal, ecological and social conclusions.
- Treat survey timing, land access and authority agreement as programme-critical activities.
- Preserve site, layout, BESS and route alternatives while material uncertainties remain.
- Apply the mitigation hierarchy with avoidance first and maintain a controlled commitment register.
- Integrate environmental, social and engineering workstreams, especially for drainage, access, noise, routes and BESS emergency planning.
- Use confidence and severity separately so uncertain but high-consequence issues receive appropriate attention.
- Use AI for organisation and drafting only under approved governance and specialist validation.

### LOOKING AHEAD - CHAPTER 9

The next chapter focuses on the AI-Assisted Initial Project Risk Register. It will consolidate technical, environmental, social, land, grid, permitting, commercial and programme findings into a decision-controlled risk system with causes, consequences, ownership, mitigation, residual exposure and escalation rules.

## END OF CHAPTER 8



## CHAPTER 9

# AI-Assisted Initial Project Risk Register for Utility-Scale Solar and BESS Projects

---

*From dispersed findings to accountable, decision-controlled risk management*

*Risk taxonomy, cause-event-consequence logic, ownership, mitigation, residual exposure, escalation and AI-enabled governance*

Edition v1.1 | Volume 1

*"A risk register is useful only when it changes a decision, assigns an owner or triggers an action. A long list without accountability is project history—not risk management."*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a practical method for creating and controlling an Initial Project Risk Register for utility-scale Solar PV and Battery Energy Storage System projects. It explains how to convert findings from site screening, land review, imagery, field due diligence, environmental and social assessment, grid work, permitting, engineering, commercial analysis and programme planning into clear risk statements with accountable owners and measurable treatment actions. Artificial Intelligence is used to organise evidence, detect duplication, draft risk narratives, test completeness and prepare management reporting, while project leadership retains responsibility for probability, impact, acceptance, escalation and closure.

| Element        | Purpose                                                                                                            |
|----------------|--------------------------------------------------------------------------------------------------------------------|
| Risk basis     | Defines project stage, decision context, risk appetite, rating method, review date and boundaries of the register. |
| Risk statement | Uses cause-event-consequence logic so the risk is specific, testable and connected to project value.               |
| Classification | Organises risks by workstream, source, project objective, time horizon, evidence confidence and exposure type.     |
| Assessment     | Separates inherent exposure, existing controls, treatment actions and residual exposure.                           |
| Ownership      | Assigns one accountable risk owner and named action owners with deadlines and closure evidence.                    |
| Escalation     | Defines thresholds, triggers, decision gates and authority levels for acceptance or intervention.                  |
| AI workflow    | Accelerates consolidation, consistency checks, duplicate detection, meeting packs and narrative reporting.         |
| Governance     | Maintains review cadence, version control, change history and connection to schedule, cost, design and decisions.  |

*Table 9.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Define the purpose, scope, rating methodology and governance of an Initial Project Risk Register.
- Write decision-useful risks using cause-event-consequence logic rather than vague issue descriptions.
- Distinguish risks, issues, assumptions, opportunities, actions, dependencies and information gaps.
- Assess inherent and residual exposure using probability, impact, evidence confidence and time horizon.
- Assign accountable risk owners, action owners, deadlines, triggers and closure evidence.
- Integrate land, grid, permitting, environmental, social, technical, BESS, commercial and programme risks.

- Use AI to consolidate and challenge a risk register without delegating risk acceptance or management judgement.
- Prepare concise risk reporting for development teams, executives, Investment Committees and technical advisers.

## 9.1 Introduction

Early project development produces risk information in many forms: site-screening notes, land exceptions, environmental constraints, grid assumptions, survey gaps, design comments, meeting actions, cost contingencies and schedule warnings. Unless these findings are consolidated into one controlled system, the development team can lose sight of which uncertainties are most material, who owns them and when they must be resolved.

The Initial Project Risk Register creates that system. It does not predict every event that may affect the project. Its purpose is to capture the material uncertainties that could change safety, consentability, land control, grid access, energy production, cost, programme, bankability, reputation or investment value—and to connect each uncertainty to a responsible owner and a management response.

A strong register is dynamic. Risks evolve as evidence improves, designs change, contracts are negotiated and decisions are taken. Some risks become issues, some are retired, some reduce through mitigation and others escalate because their decision window is closing. The register must therefore be integrated with project governance rather than maintained as a static spreadsheet.

### ENGINEERING INSIGHT

A risk is not managed because it appears in a spreadsheet. It is managed when an accountable person has authority, resources, a deadline and objective evidence for closure.

## 9.2 What the Initial Risk Register Is For

The register should be designed around the decisions and behaviours it must support. Different audiences need different levels of detail, but they should all draw from the same controlled source.

| Use                     | Decision Supported                                               | Required Output                                                                      |
|-------------------------|------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| Origination / screening | Should the opportunity progress, pause or be rejected?           | Fatal flaws, major uncertainties, next evidence and conditions for progression.      |
| Acquisition             | What protections, price adjustments or conditions are required?  | Transaction red flags, quantified exposure where possible and conditions precedent.  |
| Development management  | Where should time, budget and specialist effort be focused?      | Prioritised actions, owners, due dates, triggers and decision-gate impacts.          |
| Investment approval     | Is residual exposure acceptable relative to return and strategy? | Top risks, trend, mitigation status, cost / schedule range and acceptance authority. |

| Use                                  | Decision Supported                                         | Required Output                                                        |
|--------------------------------------|------------------------------------------------------------|------------------------------------------------------------------------|
| Engineering / procurement            | Which design or contract provisions are required?          | Technical requirements, contingencies, interfaces and risk allocation. |
| Financing / technical adviser review | Are material risks identified, controlled and transparent? | Evidence traceability, residual risk, sensitivities and closure plan.  |

Table 9.2 - Principal uses of the Initial Project Risk Register.

## 9.3 Risk, Issue, Assumption, Opportunity and Action

These terms are often mixed together, which creates weak ownership and misleading reporting. The register should classify each entry correctly before it is rated.

| Record Type     | Definition                                                                               | Management Response                                                                 |
|-----------------|------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| Risk            | An uncertain future event or condition that may affect a project objective.              | Assess probability and impact; define controls, treatment, owner and trigger.       |
| Issue           | A condition or event that has already occurred or is currently true.                     | Resolve through an issue / action process; assess consequential risks separately.   |
| Assumption      | A statement treated as true for planning despite incomplete confirmation.                | Record basis, owner, validation date and consequence if false.                      |
| Information gap | Evidence required for a decision is missing, incomplete, stale or contradictory.         | Issue an information request or specialist scope; identify resulting decision risk. |
| Dependency      | An activity or decision relies on another party, event or deliverable.                   | Link to programme, interface owner, trigger and contingency.                        |
| Opportunity     | An uncertain event or condition that may improve a project objective.                    | Assess likelihood and benefit; assign action to increase probability or value.      |
| Action          | A defined activity required to treat a risk, resolve an issue or validate an assumption. | Assign owner, due date, deliverable and closure evidence.                           |

Table 9.3 - Distinguishing the principal project-control records.

### COMMON MISTAKE

Do not rate a confirmed issue as though it were still uncertain. Manage the issue directly, then record the risks created by delay, incomplete resolution or consequence.

## 9.4 Establishing the Risk-Management Basis

Before populating the register, the project should approve the rules by which risks will be described, rated, escalated and accepted. Without a common basis, ratings reflect personal preference rather than project governance.

| Basis Element         | Definition Required                                                                                                    |
|-----------------------|------------------------------------------------------------------------------------------------------------------------|
| Project objectives    | Safety, compliance, consent, land, grid, energy, CAPEX, OPEX, programme, revenue, financing and reputation objectives. |
| Register boundary     | Project elements, workstreams, geographies, contracts and time horizon included.                                       |
| Rating scales         | Probability and impact scales, impact dimensions and scoring logic.                                                    |
| Risk appetite         | Types and levels of exposure the organisation is willing to pursue or retain.                                          |
| Tolerance / threshold | Maximum acceptable variation or exposure before escalation or intervention.                                            |
| Review cadence        | Routine, gate-based and trigger-based review frequency.                                                                |
| Authority             | Who may accept, escalate, close or transfer risk at each level.                                                        |
| Evidence standard     | Minimum source, confidence and closure evidence required.                                                              |
| Reporting date        | The status date against which probability, impact, actions and trend are assessed.                                     |

*Table 9.4 - Minimum approved basis for the project risk register.*

## 9.5 Risk Identification Sources

Risk identification should be systematic and evidence-led. It should combine multidisciplinary review, structured workshops and continuous capture from project activities.

| Source                 | Examples of Risk Inputs                                                                                         |
|------------------------|-----------------------------------------------------------------------------------------------------------------|
| Site screening         | Fatal-flaw candidates, geometry limitations, resource uncertainty, access and route constraints.                |
| Land and rights        | Title gaps, parcel fragmentation, access, easements, mortgages, tenants and option conditions.                  |
| Imagery and fieldwork  | Observed drainage, informal land use, road limitations, neighbouring receptors and contradictions.              |
| Environmental / social | Survey windows, permitting pathways, sensitive receptors, stakeholder concerns and mitigation commitments.      |
| Grid                   | Connection availability, reinforcement, studies, curtailment, compliance, securities and programme.             |
| Engineering            | Design maturity, technology interfaces, constructability, geotechnical, hydrology, fire safety and operability. |

| Source                   | Examples of Risk Inputs                                                                              |
|--------------------------|------------------------------------------------------------------------------------------------------|
| Commercial / procurement | Price volatility, supplier capability, warranties, lead times, contractual gaps and risk allocation. |
| Programme / governance   | Critical-path dependencies, authority delays, decision latency, resources and document control.      |
| External context         | Policy change, market conditions, competing projects, extreme weather and supply-chain disruption.   |

Table 9.5 - Principal sources for project-risk identification.

## 9.6 Writing a Decision-Useful Risk Statement

A useful risk statement explains why the uncertainty exists, what uncertain event may occur and how the project would be affected. The preferred structure is cause-event-consequence.




Figure 9.1 - Cause-event-consequence structure for risk statements.

| Quality       | Weak Statement                      | Improved Statement                                                                                                                                                                                         |
|---------------|-------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Specificity   | "Grid risk."                        | Because network capacity is unconfirmed, the requested connection may require reinforcement, causing additional CAPEX and delay to commercial operation.                                                   |
| Uncertainty   | "The access road is narrow."        | Because the preferred access route contains unverified width and bridge-capacity constraints, abnormal-load delivery may require route upgrades or an alternative corridor, increasing cost and programme. |
| Consequence   | "Environmental surveys incomplete." | Because the required seasonal bird survey window may be missed, the consent application may be delayed by one year, affecting land-option duration and investment timing.                                  |
| Decision link | "BESS fire concerns."               | Because the current BESS compound lacks confirmed separation and emergency-access requirements, the layout may require relocation or additional land before design freeze.                                 |

Table 9.6 - Improving vague entries into decision-useful risk statements.

### BEST PRACTICE

Write one principal uncertainty per risk. If a statement contains several unrelated causes or consequences, split it so ownership and treatment remain clear.

## 9.7 Risk Taxonomy and Coding

A common taxonomy enables filtering, trend analysis, ownership and reporting across a portfolio. It should be detailed enough to support action without becoming administratively burdensome.

| Category                    | Typical Subcategories                                                                                          |
|-----------------------------|----------------------------------------------------------------------------------------------------------------|
| Strategic / market          | Development strategy, route-to-market, policy, revenue model, competitor and portfolio concentration.          |
| Land / property             | Ownership, title, boundaries, options, leases, access, easements, third-party rights and decommissioning.      |
| Permitting / legal          | Planning route, permit sequence, authority scope, appeals, compliance and contractual obligations.             |
| Environmental / social      | Biodiversity, water, landscape, heritage, noise, community, livelihood, labour and human rights.               |
| Grid / electrical           | Capacity, reinforcement, studies, grid code, protection, harmonics, curtailment, securities and energisation.  |
| PV / BESS technology        | Performance, degradation, safety, integration, warranties, augmentation, obsolescence and supplier capability. |
| Civil / constructability    | Terrain, geotechnical, drainage, earthworks, roads, foundations, logistics and temporary works.                |
| Commercial / financial      | CAPEX, OPEX, tax, inflation, foreign exchange, financing, insurance and contingency.                           |
| Procurement / contracts     | Scope gaps, interfaces, lead times, liquidated damages, guarantees and risk allocation.                        |
| Programme / resources       | Critical path, seasonal windows, approvals, resources, governance and decision delay.                          |
| HSE / security / reputation | Construction and operational safety, BESS emergency, cybersecurity, physical security and stakeholder trust.   |

*Table 9.7 - Suggested utility-scale Solar PV and BESS risk taxonomy.*

## 9.8 Probability Assessment

Probability should be estimated for the defined risk event over a stated time horizon. Teams should avoid giving a probability to the cause or consequence instead of the event itself.

| Rating | Descriptor | Indicative Interpretation                                              |
|--------|------------|------------------------------------------------------------------------|
| 1      | Rare       | The event is not expected and would require exceptional circumstances. |

| Rating | Descriptor     | Indicative Interpretation                                               |
|--------|----------------|-------------------------------------------------------------------------|
| 2      | Unlikely       | The event could occur but is not the expected outcome.                  |
| 3      | Possible       | The event has a realistic chance of occurring under current conditions. |
| 4      | Likely         | The event is more likely than not unless treatment succeeds.            |
| 5      | Almost certain | The event is expected or already showing strong leading indicators.     |

*Table 9.8 - Example qualitative probability scale.*

Where sufficient evidence exists, quantitative ranges may be added, but false precision should be avoided. The basis for the rating—such as authority feedback, study status, historical data, supplier evidence or expert judgement—should be recorded.

## 9.9 Impact Assessment Across Multiple Objectives

Impact should be assessed across the project objectives that matter. The overall impact rating may be the highest credible dimension, a weighted result or another approved method. The selected logic should be documented and consistently applied.

| Impact Dimension               | Examples of Assessment Criteria                                                                          |
|--------------------------------|----------------------------------------------------------------------------------------------------------|
| Health, safety and environment | Injury potential, fire / thermal event, environmental harm, legal breach and emergency consequence.      |
| Consent / compliance           | Permit refusal, additional assessment, condition burden, appeal or loss of compliance.                   |
| Land / rights                  | Loss of critical parcel, access, route, option validity or operational right.                            |
| Programme                      | Delay to survey, application, grid milestone, financing, notice to proceed or commercial operation.      |
| CAPEX / OPEX                   | Additional development cost, redesign, mitigation, equipment, construction, insurance or operating cost. |
| Energy / revenue               | Reduced capacity, yield, availability, market participation or contracted revenue.                       |
| Quality / performance          | Failure to meet design, warranty, grid-code, availability or lifecycle requirements.                     |
| Reputation / stakeholder       | Community opposition, lender concern, authority confidence or public controversy.                        |

*Table 9.9 - Project objectives for impact assessment.*



## 9.10 Risk Matrix, Exposure and Priority

A probability-impact matrix provides a common language for prioritisation, but the numerical score should not replace judgement. Low-probability, high-consequence events, legal obligations and safety risks may require escalation regardless of score.

| Probability \ Impact | 1 - Minor | 2 - Low | 3 - Moderate | 4 - Major | 5 - Severe |
|----------------------|-----------|---------|--------------|-----------|------------|
| 5 - Almost certain   | 5         | 10      | 15           | 20        | 25         |
| 4 - Likely           | 4         | 8       | 12           | 16        | 20         |
| 3 - Possible         | 3         | 6       | 9            | 12        | 15         |
| 2 - Unlikely         | 2         | 4       | 6            | 8         | 10         |
| 1 - Rare             | 1         | 2       | 3            | 4         | 5          |

Table 9.10 - Example 5 x 5 risk-scoring matrix.

| Score Band | Indicative Classification | Typical Governance Response                                                            |
|------------|---------------------------|----------------------------------------------------------------------------------------|
| 1-4        | Low                       | Manage within routine workstream controls and monitor for change.                      |
| 5-9        | Moderate                  | Define treatment, owner and deadline; review at project cadence.                       |
| 10-14      | High                      | Senior review, active treatment and decision-gate visibility required.                 |
| 15-25      | Critical                  | Immediate escalation; progression may require pause, alternative or formal acceptance. |

Table 9.11 - Example risk-priority bands and governance response.

### COMMON MISTAKE

A score is a prioritisation aid, not an objective truth. Report the underlying event, evidence, consequence, timing and uncertainty so decision-makers can challenge the rating.

## 9.11 Evidence Confidence and Uncertainty

Risk exposure and evidence confidence are different. A project may face a potentially severe risk supported by limited evidence; that uncertainty is itself relevant to the management response.

| Confidence | Description                                                         | Management Implication                                               |
|------------|---------------------------------------------------------------------|----------------------------------------------------------------------|
| High       | Current, authoritative and project-specific evidence is consistent. | Rating can support decisions, subject to normal professional review. |

| Confidence | Description                                                             | Management Implication                                                              |
|------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| Medium     | Evidence is partly project-specific or contains manageable limitations. | Maintain assumptions and targeted verification before material commitment.          |
| Low        | Evidence is indicative, stale, incomplete or contradictory.             | Prioritise investigation; avoid irreversible decisions or use explicit contingency. |
| Unknown    | No reliable evidence is available for the conclusion.                   | Treat as an information gap and define the earliest credible verification route.    |

Table 9.12 - Evidence-confidence classifications for risk assessment.

**ENGINEERING INSIGHT**

A low-confidence risk should not automatically receive a low rating. When the credible downside is material, uncertainty may justify stronger contingency, faster investigation or a conditional decision.

## 9.12 Inherent Risk, Existing Controls and Residual Risk

Inherent risk is the exposure before existing controls are considered. Residual risk is the expected exposure after current and planned treatment. These concepts should not be confused with optimistic assumptions about future success.

| Field                  | Question                                                                              |
|------------------------|---------------------------------------------------------------------------------------|
| Inherent risk          | What is the credible exposure if no effective control or treatment exists?            |
| Existing controls      | What approved, implemented and demonstrably effective measures are already operating? |
| Control effectiveness  | Is each control designed appropriately, implemented and evidenced?                    |
| Treatment action       | What additional action will reduce probability, impact or uncertainty?                |
| Residual risk          | What exposure is expected after treatment, assuming the action succeeds?              |
| Treatment failure risk | What happens if the action is late, incomplete or ineffective?                        |
| Fallback / contingency | What alternative response protects the project if the preferred treatment fails?      |

Table 9.13 - Separating inherent exposure, controls and residual exposure.

## 9.13 Risk-Treatment Strategies

Treatment should be selected according to the nature of the risk and the project objective. A single risk may require several coordinated strategies.

| Strategy            | Application                                                     | Solar / BESS Example                                                            |
|---------------------|-----------------------------------------------------------------|---------------------------------------------------------------------------------|
| Avoid               | Change the plan so the risk event no longer arises.             | Relocate BESS away from a flood pathway or sensitive receptor.                  |
| Reduce probability  | Lower the chance that the event occurs.                         | Secure route rights early and complete abnormal-load survey before procurement. |
| Reduce impact       | Limit the consequence if the event occurs.                      | Maintain schedule float, cost contingency or alternative connection design.     |
| Transfer / allocate | Assign defined exposure contractually or through insurance.     | EPC performance guarantees, warranty terms or insurance for specified events.   |
| Share               | Distribute responsibility or exposure between parties.          | Joint grid-infrastructure development with clear interface agreements.          |
| Accept              | Retain exposure within approved appetite and monitor it.        | Accept moderate commodity-price uncertainty within approved contingency.        |
| Exploit opportunity | Act to increase the probability or value of a positive outcome. | Advance hybrid controls to access additional market revenue.                    |

Table 9.14 - Risk-treatment and opportunity-response strategies.

## 9.14 Ownership, Accountability and Authority

Every risk should have one accountable risk owner. Actions may have different owners, but fragmented accountability makes escalation and acceptance unclear.

| Role                               | Responsibility                                                                                                            |
|------------------------------------|---------------------------------------------------------------------------------------------------------------------------|
| Risk owner                         | Owns the risk statement, rating, treatment strategy, monitoring, escalation and recommendation for acceptance or closure. |
| Action owner                       | Delivers a specific treatment or verification action by the agreed date and provides closure evidence.                    |
| Workstream lead                    | Ensures related risks are complete, consistent and integrated with workstream plans.                                      |
| Project manager / development lead | Maintains cross-workstream governance, prioritisation, escalation and decision-gate integration.                          |
| Approver / risk acceptor           | Has delegated authority to accept the residual exposure at the relevant level.                                            |
| Assurance reviewer                 | Provides independent technical, commercial, legal, HSE or governance challenge where required.                            |

Table 9.15 - Roles within project-risk governance.

**AI TIP**

The risk owner should be the person best positioned to influence the risk and escalate the decision—not simply the person who discovered it or entered it into the register.

## 9.15 Actions, Due Dates and Closure Evidence

A treatment action should describe a deliverable, not an intention. “Review grid risk” is not a controlled action. “Obtain written network-operator confirmation of study scope and reinforcement assumptions by 30 September” is measurable.

| Action Field             | Required Content                                                                            |
|--------------------------|---------------------------------------------------------------------------------------------|
| Action description       | Specific deliverable or decision required.                                                  |
| Owner                    | Named accountable person, not only a department.                                            |
| Due date                 | Date aligned with the risk trigger and project decision gate.                               |
| Predecessor / dependency | Input, access, authority response or decision required before completion.                   |
| Budget / resource        | Approved specialist, internal effort or contingency required.                               |
| Closure evidence         | Document, survey, design, agreement, approval or verified control demonstrating completion. |
| Effect on rating         | Expected change to probability, impact, confidence or time horizon.                         |
| Status / forecast        | Current progress, forecast completion and reason for variance.                              |

Table 9.16 - Minimum fields for risk-treatment actions.

## 9.16 Triggers, Early-Warning Indicators and Escalation

Risk reviews become more useful when they monitor leading indicators rather than waiting for consequences. Triggers should identify when the exposure has changed enough to require escalation, contingency or a new decision.

| Risk Area  | Example Trigger / Indicator                                                   | Escalation Response                                                     |
|------------|-------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| Land       | Critical option remains unsigned within 60 days of grid application.          | Activate alternative parcel / route and escalate transaction condition. |
| Permitting | Authority requests a full seasonal survey not included in baseline programme. | Rebaseline consent schedule and review land-option extension.           |
| Grid       | Study indicates reinforcement beyond approved CAPEX or target date.           | Review capacity, alternative POI, phasing or project configuration.     |

| Risk Area   | Example Trigger / Indicator                                                 | Escalation Response                                                          |
|-------------|-----------------------------------------------------------------------------|------------------------------------------------------------------------------|
| BESS safety | Supplier design cannot demonstrate required separation or emergency access. | Pause design freeze and evaluate alternative product / compound location.    |
| CAPEX       | Benchmark variance exceeds approved contingency.                            | Update economics and seek approval before procurement commitment.            |
| Programme   | Critical-path action forecast exceeds float or gate date.                   | Issue recovery plan, management escalation and decision on scope / sequence. |
| Stakeholder | Formal objection or organised campaign emerges.                             | Activate engagement and reputation response under approved governance.       |

Table 9.17 - Example early-warning indicators and escalation responses.

## 9.17 Interdependencies and Risk Chains

Material project risks rarely exist in isolation. One event may create several secondary risks, and several causes may converge on one consequence. The register should identify these relationships so the team does not treat symptoms independently.




Figure 9.2 - Example chain of dependent development risks.

| Primary Risk        | Potential Secondary Effects                                                                         |
|---------------------|-----------------------------------------------------------------------------------------------------|
| Delayed land access | Late surveys, incomplete layout, consent delay, tender uncertainty and option expiry.               |
| Grid redesign       | Changed capacity, BESS duty, land requirement, cable route, CAPEX, permit amendment and revenue.    |
| Flood finding       | Reduced buildable area, drainage redesign, BESS relocation, yield loss, cost and schedule delay.    |
| Supplier change     | Design rework, certification review, warranty change, logistics impact and updated grid compliance. |
| Community objection | Additional assessment, layout change, delay, reputation exposure and lender scrutiny.               |

Table 9.18 - Examples of cross-workstream risk chains.

## 9.18 Time Horizon and Risk Urgency

Two risks with the same probability and impact may require different priority because their decision windows differ. Risk urgency should reflect when the event may occur and when effective treatment must begin.

| Time Classification | Interpretation                                                               | Management Focus                                                        |
|---------------------|------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| Immediate           | Action or decision required before the next routine review or gate.          | Executive visibility and active intervention.                           |
| Near term           | Treatment must begin within the next development period or quarter.          | Fund, resource and sequence the action now.                             |
| Medium term         | Exposure occurs later, but enabling work or monitoring is required.          | Maintain triggers and protect alternatives.                             |
| Long term           | Primarily construction, operation, augmentation or decommissioning exposure. | Embed requirements in design, contracts, financing and lifecycle plans. |

Table 9.19 - Time horizon and urgency classifications.

## 9.19 Quantification and Decision Sensitivities

Where evidence supports it, qualitative ratings should be supplemented by ranges for cost, delay, energy or revenue. Quantification improves decision quality but should preserve uncertainty and correlation.

| Exposure Type | Possible Quantification                                                                        |
|---------------|------------------------------------------------------------------------------------------------|
| CAPEX         | Expected range, contingency draw, redesign cost, mitigation cost or reinforcement cost.        |
| Programme     | Earliest / most likely / latest delay, seasonal-window effect and commercial-operation impact. |
| Energy        | MW reduction, yield loss, clipping, curtailment, availability or degradation sensitivity.      |
| Revenue       | Price, capacity, delay, market-access or contracted-payment sensitivity.                       |
| Land          | Additional hectares, rent, purchase, route compensation or option-extension cost.              |
| Financing     | Debt sizing, interest during construction, reserve, insurance or covenant effect.              |

Table 9.20 - Examples of risk quantification for decision support.

### COMMON MISTAKE

Do not convert weak evidence into a single precise number. Use transparent ranges, scenarios, basis dates and correlations, then update them as design and commercial evidence mature.

## 9.20 Opportunity Register and Upside Management

Positive uncertainty should be managed with the same discipline as downside risk. Opportunities can improve capacity, yield, programme, CAPEX, revenue, biodiversity, community value or portfolio strategy.

| Opportunity               | Enabling Action                                               | Potential Benefit                                                  |
|---------------------------|---------------------------------------------------------------|--------------------------------------------------------------------|
| Additional land parcel    | Secure option and confirm grid / environmental suitability.   | Improved layout, BESS flexibility or future expansion.             |
| Alternative grid solution | Advance technical concept and operator engagement.            | Earlier connection, reduced reinforcement or lower losses.         |
| Hybrid optimisation       | Refine PV / BESS controls and market strategy.                | Higher asset utilisation and revenue diversity.                    |
| Design standardisation    | Align portfolio equipment and specifications.                 | Lower engineering effort, procurement leverage and O&M efficiency. |
| Early biodiversity design | Integrate habitat and drainage measures before layout freeze. | Reduced consent risk and measurable environmental value.           |
| Supplier competition      | Maintain qualified alternatives and common data requirements. | Improved pricing, warranty and schedule resilience.                |

Table 9.21 - Examples of opportunity management in Solar PV and BESS development.

## 9.21 AI-Assisted Risk-Register Workflow

AI can accelerate the mechanics of risk management when it operates on controlled evidence and an approved taxonomy. It should not determine risk appetite, acceptance or final ratings without responsible human review.



Figure 9.3 - Human-controlled AI-assisted risk-register workflow.

| AI-Supported Task                                              | Required Human Control                                                            |
|----------------------------------------------------------------|-----------------------------------------------------------------------------------|
| Extract findings from reports, minutes and registers           | Verify every material statement against the original source and revision.         |
| Convert findings into draft cause-event-consequence statements | Confirm the uncertainty, consequence, materiality and project objective affected. |
| Identify duplicate or overlapping risks                        | Decide whether to merge, link or retain separate ownership.                       |
| Suggest taxonomy, actions and missing fields                   | Approve classification, feasibility, owner, budget and deadline.                  |

| AI-Supported Task                           | Required Human Control                                                         |
|---------------------------------------------|--------------------------------------------------------------------------------|
| Compare current and previous registers      | Validate trend, closure and reasons for rating change.                         |
| Prepare dashboards and management summaries | Ensure material nuance, dissent and uncertainty are not hidden by compression. |
| Challenge completeness                      | Use multidisciplinary workshops and professional review to confirm coverage.   |

*Table 9.22 - Appropriate uses and controls for AI-assisted risk management.*

#### AI TIP

AI may draft a risk statement or identify a missing field. It must not silently change ratings, close actions, accept exposure or replace accountable review.

## 9.22 Minimum Register Fields

The register should contain enough information to support decisions and accountability without becoming unreadable. Detailed evidence may remain in linked documents, but the principal logic should be visible.

| Field Group    | Minimum Fields                                                                       |
|----------------|--------------------------------------------------------------------------------------|
| Identity       | Unique ID, title, category, subcategory, project element and date raised.            |
| Risk statement | Cause, uncertain event, consequence and objective affected.                          |
| Evidence       | Source, revision, status date, confidence, assumptions and links.                    |
| Assessment     | Inherent probability, impact dimensions, overall impact, score and urgency.          |
| Controls       | Existing controls and control-effectiveness assessment.                              |
| Treatment      | Strategy, actions, owners, due dates, resources and dependencies.                    |
| Residual       | Residual probability, impact, score, expected completion and acceptor.               |
| Monitoring     | Trigger, indicator, trend, review date and comments.                                 |
| Closure        | Closure rationale, evidence, date, approver and related residual / transferred risk. |

*Table 9.23 - Recommended minimum fields for the Initial Project Risk Register.*



## 9.23 Risk Review Meetings and Challenge Process

The quality of a register depends on the quality of the review discussion. Meetings should focus on changed exposure, overdue treatment, emerging triggers and decisions—not on reading every row.

| Agenda Element            | Key Questions                                                                        |
|---------------------------|--------------------------------------------------------------------------------------|
| Changes since last review | Which risks increased, decreased, emerged, became issues or were closed—and why?     |
| Top exposure              | Are the highest residual risks receiving sufficient authority, budget and attention? |
| Actions                   | Which actions are late, forecast late or unlikely to reduce exposure as expected?    |
| Triggers                  | Have leading indicators or decision windows changed?                                 |
| Interdependencies         | Could a change in one workstream alter several ratings or critical-path assumptions? |
| Acceptance                | Which residual risks require formal acceptance at the next gate?                     |
| Assurance                 | Where is independent technical, legal, commercial, HSE or lender challenge required? |

*Table 9.24 - Recommended risk-review meeting agenda.*

## 9.24 Executive Reporting and Dashboards

Executive reporting should compress the register without hiding uncertainty. A useful dashboard explains what changed, why it matters, what decision is required and whether treatment is on track.

| Dashboard Element    | Content                                                                                                |
|----------------------|--------------------------------------------------------------------------------------------------------|
| Exposure profile     | Count and distribution by severity, category, owner, project stage and trend.                          |
| Top risks            | Concise statement, consequence, residual rating, treatment status and decision required.               |
| Trend                | New, increasing, stable, decreasing, issue, closed or transferred.                                     |
| Action health        | Overdue actions, forecast slippage, resource constraints and closure confidence.                       |
| Decision-gate impact | Risks that may prevent or condition acquisition, application, design freeze, tender, financing or NTP. |

| Dashboard Element      | Content                                                                     |
|------------------------|-----------------------------------------------------------------------------|
| Quantified sensitivity | Material CAPEX, programme, MW, yield or revenue ranges where supported.     |
| Management ask         | Approval, budget, escalation, risk acceptance or strategic choice required. |

Table 9.25 - Core components of executive risk reporting.

## 9.25 Worked Example: 300 MWac Solar PV + 150 MW / 300 MWh BESS

The following example illustrates how multidisciplinary findings can be consolidated into an acquisition-stage Initial Project Risk Register. The project is assumed to be at shortlisted-site stage with preliminary land control, an indicative grid solution, incomplete seasonal environmental surveys and a concept layout.

| Project Parameter | Working Basis                                                                                    |
|-------------------|--------------------------------------------------------------------------------------------------|
| PV capacity       | 300 MWac utility-scale Solar PV.                                                                 |
| BESS capacity     | 150 MW / 300 MWh co-located BESS.                                                                |
| Land status       | Options signed over most parcels; one access parcel and export-route easement outstanding.       |
| Grid status       | Connection application submitted; network reinforcement and curtailment assumptions unconfirmed. |
| Environment       | Desktop screening complete; bird and hydrology work incomplete.                                  |
| Design            | Concept layout based on preliminary topography and indicative equipment.                         |
| Commercial stage  | Acquisition decision and next-year development budget under review.                              |

Table 9.26 - Worked-example project basis.

| ID    | Draft Risk Statement                                                                                                                                                                       | Inherent            | Treatment / Owner                                                                | Residual           |
|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|----------------------------------------------------------------------------------|--------------------|
| R-001 | Because the only feasible abnormal-load route crosses an unverified bridge, equipment delivery may require strengthening or a different route, increasing CAPEX and delaying construction. | $P4 \times I4 = 16$ | Commission structural / route survey; Logistics Lead; before supplier shortlist. | $P2 \times I3 = 6$ |

| ID    | Draft Risk Statement                                                                                                                                                    | Inherent            | Treatment / Owner                                                                     | Residual            |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------------------------------------------------------------------------------------|---------------------|
| R-002 | Because a critical access parcel option is unsigned, the project may lose the preferred construction entrance and require layout / route redesign.                      | $P3 \times I5 = 15$ | Agree option or secure alternative access; Land Lead; before acquisition close.       | $P2 \times I4 = 8$  |
| R-003 | Because the required seasonal bird survey may not be completed before application, the consent programme may slip by up to one year.                                    | $P4 \times I4 = 16$ | Confirm authority scope and mobilise survey immediately; E&S Lead.                    | $P2 \times I4 = 8$  |
| R-004 | Because network reinforcement and curtailment are unconfirmed, connection CAPEX, COD and project revenue may differ materially from the investment case.                | $P4 \times I5 = 20$ | Advance operator studies, alternative POI / phasing and sensitivity cases; Grid Lead. | $P3 \times I4 = 12$ |
| R-005 | Because the BESS compound is located near a drainage low point and separation basis is preliminary, relocation or additional land may be required before design freeze. | $P3 \times I4 = 12$ | Hydrology and fire-layout review; Technical Lead; before land plan freeze.            | $P2 \times I3 = 6$  |
| R-006 | Because geotechnical conditions are unverified, tracker foundation and road quantities may exceed the concept estimate.                                                 | $P3 \times I3 = 9$  | Ground investigation and cost range; Civil Lead; before EPC budget approval.          | $P2 \times I2 = 4$  |
| R-007 | Because the export-route easement is not secured, the preferred cable corridor may be unavailable, creating permit, land and programme impacts.                         | $P3 \times I5 = 15$ | Secure easement and maintain alternative corridor; Land / Grid Leads.                 | $P2 \times I4 = 8$  |
| R-008 | Because the CAPEX estimate uses indicative BESS and transformer pricing, project returns may be overstated at acquisition.                                              | $P4 \times I4 = 16$ | Obtain budget quotes, escalation range and contingency; Commercial Lead.              | $P3 \times I3 = 9$  |

Table 9.27 - Worked-example initial risk register extract.

**ENGINEERING INSIGHT**

The highest-rated risks are not necessarily the only transaction conditions. R-002 and R-007 may deserve conditions precedent because they concern critical rights, while R-004 requires a quantified commercial sensitivity and strategic decision on acceptable grid uncertainty.

## 9.26 Worked Example: Prioritised Action and Decision Plan

| Priority | Action                                                                                            | Decision / Gate Protected                       | Closure Evidence                                     |
|----------|---------------------------------------------------------------------------------------------------|-------------------------------------------------|------------------------------------------------------|
| 1        | Secure critical access parcel and export-route rights or approved alternatives.                   | Acquisition close and land-control sufficiency. | Executed option / easement and updated land plan.    |
| 2        | Confirm environmental survey scope and seasonal programme with competent specialists / authority. | Consent strategy and acquisition schedule.      | Approved scope, mobilisation evidence and programme. |
| 3        | Advance grid studies and quantify reinforcement, curtailment and COD sensitivities.               | Investment case and project configuration.      | Operator evidence, study output and updated model.   |
| 4        | Review BESS compound against hydrology, separation, access and emergency needs.                   | Layout and land-plan freeze.                    | Approved concept layout and design-basis note.       |
| 5        | Complete logistics route and bridge assessment.                                                   | Equipment shortlist and construction strategy.  | Route report, constraints and priced mitigation.     |
| 6        | Update CAPEX benchmark using supplier and civil evidence.                                         | Acquisition price and development budget.       | Basis-of-estimate, quote log, range and contingency. |

*Table 9.28 - Worked-example risk-treatment and decision plan.*

The acquisition recommendation would therefore be “proceed with conditions” rather than an unconditional approval. The risk register should identify the rights, surveys, grid evidence, layout changes and commercial sensitivities that must be completed or protected contractually.

## 9.27 Common Mistakes

| Mistake                           | Why It Fails                                                                 | Better Practice                                                         |
|-----------------------------------|------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| Recording topics instead of risks | “Grid,” “land” or “environment” does not explain uncertainty or consequence. | Use cause-event-consequence logic linked to an objective.               |
| Mixing issues and risks           | Confirmed conditions are hidden inside probability ratings.                  | Manage issues directly and record consequential uncertainty separately. |

| Mistake                                       | Why It Fails                                                           | Better Practice                                          |
|-----------------------------------------------|------------------------------------------------------------------------|----------------------------------------------------------|
| Rating without a common basis                 | Scores reflect personality and workstream culture.                     | Approve scales, thresholds, appetite and evidence rules. |
| Assigning a department as owner               | No individual is accountable for escalation or closure.                | Name one risk owner and named action owners.             |
| Treating planned actions as existing controls | Residual exposure becomes artificially low.                            | Only credit implemented and evidenced controls.          |
| Using one score for all decisions             | Timing, legal obligation and low-probability severe events are missed. | Report dimensions, urgency, confidence and triggers.     |
| Closing risks when an action completes        | The action may not have reduced exposure as intended.                  | Verify outcome and residual risk before closure.         |
| Letting AI auto-rate or close entries         | Governance and accountability are bypassed.                            | Use AI for drafting and challenge under human approval.  |

Table 9.29 - Common risk-register failure modes.

## 9.28 Best Practices

- Design the register around project decisions, risk appetite and stage gates.
- Use one clear uncertainty per risk and preserve cause-event-consequence logic.
- Separate risks, issues, assumptions, information gaps, dependencies, opportunities and actions.
- Assess multiple impact dimensions and record the basis for probability and impact.
- Report evidence confidence, urgency and time horizon alongside the score.
- Distinguish inherent risk, existing controls, treatment and residual risk.
- Assign one accountable risk owner and measurable actions with closure evidence.
- Use triggers and early-warning indicators to act before consequences occur.
- Link risks to schedule, cost, design, land, permits, contracts and decision gates.
- Challenge top risks through multidisciplinary review and independent assurance where material.
- Track opportunities with the same ownership and action discipline as downside risks.
- Use AI only on approved data and require source verification, version control and human approval.

## 9.29 Engineering Review Checklist

| Review Area | Validation Question                                                                          | Check                    |
|-------------|----------------------------------------------------------------------------------------------|--------------------------|
| Basis       | Are objectives, scope, scales, thresholds, appetite, status date and authority approved?     | <input type="checkbox"/> |
| Definitions | Are risks separated from issues, assumptions, gaps, dependencies, opportunities and actions? | <input type="checkbox"/> |
| Statements  | Does every risk state cause, uncertain event, consequence and objective affected?            | <input type="checkbox"/> |

| Review Area    | Validation Question                                                                          | Check                    |
|----------------|----------------------------------------------------------------------------------------------|--------------------------|
| Evidence       | Is the rating supported by current, traceable evidence and an explicit confidence level?     | <input type="checkbox"/> |
| Assessment     | Are probability, impact dimensions, urgency and time horizon applied consistently?           | <input type="checkbox"/> |
| Controls       | Are existing controls implemented, evidenced and assessed for effectiveness?                 | <input type="checkbox"/> |
| Treatment      | Are strategies feasible and actions specific, funded, owned and time-bound?                  | <input type="checkbox"/> |
| Residual       | Is residual exposure realistic and conditional on successful treatment?                      | <input type="checkbox"/> |
| Ownership      | Is one accountable owner named for each risk and one owner for each action?                  | <input type="checkbox"/> |
| Triggers       | Are early-warning indicators, escalation thresholds and fallback actions defined?            | <input type="checkbox"/> |
| Interfaces     | Are risk chains and cross-workstream dependencies identified?                                | <input type="checkbox"/> |
| Quantification | Are cost, programme, MW, yield or revenue ranges transparent and evidence-based?             | <input type="checkbox"/> |
| Governance     | Are review cadence, approval, acceptance, closure and change history controlled?             | <input type="checkbox"/> |
| AI control     | Were AI outputs checked against original evidence and approved by responsible professionals? | <input type="checkbox"/> |
| Decision       | Are top risks, management asks and conditions for the next gate explicit?                    | <input type="checkbox"/> |

Table 9.30 - Initial Project Risk Register review checklist.

## 9.30 Prompt Toolkit

### Level 1 - Quick Prompt

#### QUICK PROMPT

Act as a Senior Solar PV and BESS Project Development Engineer. Using the supplied findings, prepare a draft list of the ten most material project risks. Write each risk using cause-event-consequence logic and state the project objective affected, evidence available, information gap and next action. Do not assign final probability, impact or acceptance without project-team review.

## Level 2 - Professional Prompt

### PROFESSIONAL PROMPT

Prepare an Initial Project Risk Register for the supplied utility-scale Solar PV and co-located BESS project. Consolidate findings from land, site, imagery, fieldwork, permitting, environmental and social, grid, engineering, commercial and programme sources. Separate risks, issues, assumptions, information gaps, dependencies, opportunities and actions. For each risk provide unique ID, category, cause-event-consequence statement, objective affected, source, confidence, proposed inherent rating, existing controls, treatment strategy, risk owner, action owner, due date, trigger, residual-rating proposal and decision-gate impact. Clearly mark all ratings and ownership assignments for human approval.

## Level 3 - Expert Prompt

### EXPERT PROMPT

You are acting as the Lead Technical Advisor supporting acquisition and development governance for a utility-scale Solar PV and BESS project. Review all supplied controlled evidence and existing registers. Establish the risk-management basis, taxonomy, status date, scoring method and evidence-confidence rules. Consolidate duplicate findings; identify omitted cross-workstream and lifecycle risks; write decision-grade cause-event-consequence statements; assess potential impacts across HSE, consent, land, grid, programme, CAPEX, OPEX, energy, revenue, quality, reputation and financing; and propose inherent exposure, controls, treatment, residual exposure, triggers, action owners, risk owners, acceptance authority and closure evidence. Include a top-risk executive summary, risk heat map data, trend analysis, overdue-action review, interdependency map, quantified sensitivities, acquisition / investment conditions and a 90-day treatment plan. Do not fabricate evidence, accept risk, alter approved ratings or close items without accountable human authorisation.

## 9.31 Recommended Reference Framework

The risk-management framework should be aligned with current organisational governance, project contracts and applicable professional guidance. The reference framework should include:

- Current organisational risk-management policy, delegated authorities, investment criteria and project stage-gate procedures.
- Current international risk-management guidance, including the principles and process set out in ISO 31000 where adopted by the organisation.
- Project development plan, schedule, cost estimate, design basis, land plan, permit strategy, grid strategy and commercial model.
- Controlled land, environmental, social, field, technical, grid, supplier, insurance, legal and contractual evidence.
- Applicable HSE, environmental, electrical, fire-safety, cybersecurity and emergency-management requirements.
- Current lender, investor, insurer and technical-adviser requirements relevant to risk disclosure and residual exposure.
- Project document-control, change-control, confidentiality, personal-data and approved-AI governance procedures.
- Current cost-risk and schedule-risk methodologies appropriate to the project maturity and decision.

**■ STANDARDS REFERENCE**

Use the current approved organisational method and verify the latest applicable guidance. A generic risk matrix should not override legal duties, safety obligations, contractual requirements or delegated authority.

## 9.32 Chapter Summary

The Initial Project Risk Register converts dispersed project uncertainty into a controlled system for decision-making and accountability. It begins with an approved risk basis, distinguishes the different record types, writes risks using cause-event-consequence logic and assesses exposure against the project objectives that matter. It then connects each material risk to evidence, ownership, treatment, triggers, residual exposure and an acceptance authority.

Artificial Intelligence can accelerate consolidation, duplicate detection, statement drafting, gap analysis, trend comparison and reporting. It cannot determine risk appetite, approve ratings, assign accountability, accept residual exposure or close risks. Those decisions require project authority and professional judgement.

## 9.33 Key Takeaways

- A risk register is a decision-and-accountability system, not a list of concerns.
- Risks, issues, assumptions, gaps, dependencies, opportunities and actions must be classified separately.
- Use cause-event-consequence logic and connect each risk to a project objective.
- Assess probability, multidimensional impact, evidence confidence, urgency and time horizon.
- Separate inherent risk, existing controls, treatment and residual risk.
- Assign one accountable risk owner and measurable action owners with closure evidence.
- Use triggers and escalation thresholds to intervene before consequences occur.
- Link risk management to schedule, cost, design, land, permits, contracts and decision gates.
- Quantify material exposure using transparent ranges and scenarios where evidence supports it.
- Manage opportunities actively and preserve alternatives where uncertainty remains material.
- Use AI to organise and challenge the register only under source control and accountable human approval.

### LOOKING AHEAD - CHAPTER 10

The next chapter focuses on the AI-Assisted Initial CAPEX Benchmark. It will translate early design, site, grid, land, environmental, logistics and risk assumptions into a transparent cost basis, benchmark range, contingency strategy and investment sensitivity.

## END OF CHAPTER 9



## CHAPTER 10

# AI-Assisted Initial CAPEX Benchmark for Utility-Scale Solar and BESS Projects

---

*From early project assumptions to a transparent, decision-ready capital-cost range*

*Estimate basis, scope boundaries, normalization, equipment and balance-of-plant costs, contingency, sensitivities and AI-enabled cost governance*

Edition v1.1 | Volume 1

*“An early CAPEX benchmark is not a price. It is a controlled statement of scope, assumptions, evidence, uncertainty and decision exposure.”*

## CHAPTER AT A GLANCE

## What this chapter establishes

This chapter presents a practical method for preparing an Initial CAPEX Benchmark for utility-scale Solar PV and Battery Energy Storage System projects. It explains how to define the estimate purpose and maturity, establish scope boundaries, normalize benchmark data, structure PV, BESS, grid and owner cost packages, distinguish allowances from contingency, and communicate a realistic cost range to development and investment stakeholders. Artificial Intelligence is used to organise source data, compare cost structures, test completeness, draft assumption registers and prepare sensitivities, while accountable professionals retain responsibility for quantities, rates, commercial judgement, risk treatment and approval.

| Element                 | Purpose                                                                                                                         |
|-------------------------|---------------------------------------------------------------------------------------------------------------------------------|
| Estimate basis          | Defines the project configuration, status date, estimate class, currency, location, commercial strategy and decision supported. |
| Scope boundary          | States what is included, excluded, owner-supplied, provisional, shared or outside the estimate.                                 |
| Cost breakdown          | Separates Solar PV, BESS, grid, civil, electrical, EPC, owner, development and contingency packages.                            |
| Benchmark normalization | Adjusts reference data for date, currency, geography, capacity definition, scope and technical configuration.                   |
| Risk and contingency    | Links uncertainty and risk exposure to transparent allowances, ranges and management reserve.                                   |
| Sensitivity analysis    | Shows how major assumptions affect total CAPEX, unit cost, funding need and investment headroom.                                |
| AI workflow             | Accelerates data extraction, comparison, completeness checks, scenario drafting and management reporting.                       |
| Governance              | Maintains source traceability, version control, approval, change history and reconciliation to later estimates.                 |

*Table 10.1 - Chapter structure and intended outcome.*

## Learning Objectives

After completing this chapter, you will be able to:

- Define the purpose, scope, maturity, base date and decision context of an Initial CAPEX Benchmark.
- Separate project capacity definitions and select appropriate normalization metrics for Solar PV and BESS.
- Build a transparent cost breakdown covering equipment, balance of plant, grid, EPC, owner and development costs.
- Normalize external benchmarks for scope, geography, currency, time, technology and commercial structure.

- Distinguish quantity allowances, pricing allowances, design development, contingency and management reserve.
- Prepare low, base and high scenarios with explicit sensitivities and uncertainty drivers.
- Use AI to organise cost evidence and challenge estimate completeness without fabricating prices or quantities.
- Present early CAPEX information responsibly to development teams, executives, investors and technical advisers.

## 10.1 Introduction

An early capital-cost view is required long before the project has a complete design, firm grid connection, final land rights or executable supplier quotations. Development teams need a cost range to screen opportunities, compare sites, assess funding needs, structure land and grid decisions, test investment returns and determine whether additional development expenditure is justified.

The Initial CAPEX Benchmark provides that early view. It is not intended to replace a quantity-based estimate, contractor bid or approved investment budget. Its purpose is to translate the best available project definition into a transparent range that can be challenged, updated and reconciled as the project matures.

The most damaging early estimates are not necessarily the ones with the widest range. They are the ones that appear precise while hiding incomplete scope, stale benchmarks, incompatible capacity definitions, optimistic grid assumptions or unquantified project-specific risks. A professional benchmark makes those limitations visible.

### ■ ENGINEERING INSIGHT

Precision should never exceed evidence. A benchmark with a clear range and traceable assumptions is more decision-useful than a single number built on hidden uncertainty.

## 10.2 What the Initial CAPEX Benchmark Is For

The estimate should be designed around the decision it must support. The same project may require different cost presentations for origination, acquisition, development funding, design optimization and investment approval.

| Decision Context    | Primary Question                                                  | Required CAPEX Output                                                                         |
|---------------------|-------------------------------------------------------------------|-----------------------------------------------------------------------------------------------|
| Site screening      | Is the opportunity broadly competitive and affordable to develop? | High-level range, unit metrics, unusual cost drivers and fatal cost exposures.                |
| Acquisition         | What price, protections or conditions are justified?              | Scope-adjusted benchmark, downside scenario, transaction exclusions and cost-risk conditions. |
| Development funding | How much capital is required before the next gate?                | Development budget, survey and permit spend, grid securities and staged cash requirements.    |

| Decision Context     | Primary Question                                                    | Required CAPEX Output                                                          |
|----------------------|---------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Concept selection    | Which configuration provides the best technical-commercial balance? | Comparable alternatives using consistent scope, capacity and risk assumptions. |
| Investment screening | Can the project meet return and funding thresholds?                 | Low/base/high CAPEX, sensitivity ranges, contingency and residual uncertainty. |
| Procurement planning | Which packages need early market testing or risk allocation?        | Package-level cost basis, long-lead exposure and quote strategy.               |

Table 10.2 - Typical decisions supported by an Initial CAPEX Benchmark.

## 10.3 Estimate Maturity and Classification

The estimate maturity should be stated explicitly. Project teams should use their approved organisational or professional cost-estimating classification, because terminology and expected accuracy ranges differ by sector and organisation.

| Development Stage         | Typical Definition Available                                                          | Appropriate Estimate Character                                                              |
|---------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------|
| Origination               | Approximate capacity, broad site area, conceptual connection and limited constraints. | Order-of-magnitude benchmark with wide range and material exclusions.                       |
| Shortlist / acquisition   | Preliminary layout, route options, desk studies, early land and grid information.     | Scope-adjusted benchmark with identified project-specific adders and downside case.         |
| Concept / pre-FEED        | Selected configuration, preliminary quantities, survey inputs and connection concept. | Hybrid benchmark and quantity-based estimate with package allowances.                       |
| FEED / tender preparation | Developed design basis, quantities, specifications and interface definition.          | Detailed cost estimate suitable for procurement strategy and budget approval.               |
| Bid / contract            | Tendered scope, commercial terms, schedule and risk allocation.                       | Evaluated contract price plus owner costs, exclusions, escalation and residual contingency. |

Table 10.3 - Estimate character by project maturity.

### COMMON MISTAKE

Do not describe an estimate as “accurate” without defining its maturity, scope, evidence and uncertainty. A narrow range is not credible merely because the spreadsheet contains many line items.

## 10.4 Establishing the Estimate Basis

The estimate basis is the controlled narrative that explains what has been priced and why. It should be approved before the benchmark is used for investment decisions.

| Basis Item            | Minimum Definition                                                                                       |
|-----------------------|----------------------------------------------------------------------------------------------------------|
| Project configuration | PV DC capacity, export AC capacity, BESS MW/MWh, coupling architecture, voltage and operating objective. |
| Location              | Country, region, site context, altitude, climate, access, labour market and logistics assumptions.       |
| Status date           | Date against which quantities, rates, currency, market evidence and design assumptions are valid.        |
| Commercial basis      | EPC, multi-contract, owner-supplied equipment, local content, tax and risk-allocation assumptions.       |
| Technical basis       | Module, inverter, mounting, BESS chemistry, duration, augmentation, substation and export-route concept. |
| Programme basis       | Notice to proceed, construction period, energisation, phased COD and escalation treatment.               |
| Cost boundary         | Included, excluded, provisional, shared, reimbursable and owner-held cost categories.                    |
| Source hierarchy      | Firm quotes, budget quotes, recent bids, internal benchmarks, market studies and engineering judgement.  |
| Uncertainty method    | Range, allowances, contingency, management reserve and sensitivity approach.                             |

Table 10.4 - Minimum content of the CAPEX estimate basis.

## 10.5 Scope Boundary and Cost Responsibility

A benchmark is only comparable when its scope boundary is clear. Scope omissions and ownership interfaces are among the largest causes of apparent cost differences between projects and supplier offers.

| Scope Status       | Meaning                                                         | Required Treatment                                                |
|--------------------|-----------------------------------------------------------------|-------------------------------------------------------------------|
| Included           | Cost is within the benchmark and assigned to a defined package. | State quantity/rate basis and responsibility.                     |
| Excluded           | Cost is outside the approved estimate boundary.                 | State reason and identify where it is assessed.                   |
| Provisional        | Scope is expected but definition or price is immature.          | Include allowance, uncertainty and closure action.                |
| Owner-supplied     | Owner procures equipment or service outside EPC scope.          | Include procurement price, logistics, integration and owner risk. |
| Shared / interface | Responsibility crosses EPC, utility, landowner or third party.  | Define split, avoid double count and assign interface owner.      |

| Scope Status                | Meaning                                               | Required Treatment                                         |
|-----------------------------|-------------------------------------------------------|------------------------------------------------------------|
| Pass-through / reimbursable | Final amount may be paid at actual cost.              | Include expected value and downside exposure.              |
| Contingent                  | Cost arises only if a defined event or option occurs. | Show scenario or risk allowance, not hidden in base rates. |

Table 10.5 - Scope-status classifications for benchmark control.

## 10.6 Capacity Definitions and Normalization Metrics

Solar PV and BESS projects contain several capacity measures. Mixing them can produce misleading unit costs and invalid comparisons.

| Metric          | Definition                                                                          | Typical Use                                                         |
|-----------------|-------------------------------------------------------------------------------------|---------------------------------------------------------------------|
| MWp DC          | Aggregate module nameplate capacity under specified test conditions.                | Module, DC balance-of-system and whole-plant PV normalization.      |
| MWac inverter   | Aggregate inverter active-power rating under defined conditions.                    | Inverter and conversion-system comparison.                          |
| MWac export     | Maximum active power permitted or designed at the point of interconnection.         | Grid, revenue and project-level comparison.                         |
| BESS MW         | Charge/discharge power at a stated boundary and operating condition.                | PCS, grid service and power-component comparison.                   |
| BESS MWh gross  | Installed cell or enclosure energy before operational limitations.                  | Equipment procurement reference when clearly defined.               |
| BESS MWh usable | Energy available within stated SOC, degradation, temperature and efficiency limits. | Commercial operation and warranty comparison.                       |
| €/Wp or \$/Wp   | Cost divided by PV DC nameplate capacity.                                           | PV benchmark, provided included scope is consistent.                |
| €/kWh           | Cost divided by clearly defined BESS energy capacity.                               | Battery benchmark, provided gross/usable and boundary are explicit. |
| €/kW            | Cost divided by BESS or export power.                                               | Power-dominant systems and grid-support comparison.                 |

Table 10.6 - Capacity definitions and normalization metrics.

### BEST PRACTICE

Show the denominator beside every unit cost. “€ per kWh” is incomplete unless the estimate states whether the capacity is gross, usable, beginning-of-life, end-of-life and measured at DC or AC boundary.

## 10.7 Cost Breakdown Structure

The cost breakdown structure should be stable enough to support comparisons and detailed enough to expose material drivers. It should also reconcile to the project work breakdown, procurement plan and financial model.

| Level 1 Package             | Typical Level 2 Components                                                                                      |
|-----------------------------|-----------------------------------------------------------------------------------------------------------------|
| Solar PV equipment          | Modules, trackers/fixed structures, inverters, transformers, switchgear, combiner and monitoring equipment.     |
| PV balance of plant         | DC cable, AC/MV cable, trenches, roads, drainage, fencing, buildings, foundations and installation.             |
| BESS equipment              | Cells/modules, racks, containers, thermal management, PCS, transformers, switchgear, controls and fire systems. |
| BESS balance of plant       | Platform, roads, foundations, cable, drainage, security, auxiliary power, integration and commissioning.        |
| Grid interconnection        | Collector substation, export cable/line, bays, metering, protection, telecommunications and utility works.      |
| EPC indirects               | Mobilisation, temporary facilities, engineering, management, HSE, QA/QC, testing, insurance, bonds and margin.  |
| Owner costs                 | Development, advisers, surveys, permits, owner engineering, land, project management, insurance and spares.     |
| Other financial / statutory | Duties, unrecoverable taxes, connection charges, securities and specified financing-related costs.              |
| Contingency / reserve       | Design development, quantity, pricing, execution and residual project risk according to approved method.        |

*Table 10.7 - Suggested high-level cost breakdown structure.*

## 10.8 Benchmark Source Hierarchy

Not all cost evidence has equal relevance. The benchmark should prioritize sources that are recent, comparable, traceable and commercially understood.

| Source                         | Strength                                     | Principal Limitation                                                    |
|--------------------------------|----------------------------------------------|-------------------------------------------------------------------------|
| Executed contract / recent bid | Project-specific scope and commercial terms. | May contain strategic pricing, exclusions or different risk allocation. |
| Firm supplier quotation        | Current product and delivery basis.          | Validity, volume, payment terms and integration scope may differ.       |
| Budget quotation               | Useful early market indication.              | Non-binding, incomplete engineering and limited commercial detail.      |

| Source                          | Strength                                 | Principal Limitation                                                |
|---------------------------------|------------------------------------------|---------------------------------------------------------------------|
| Internal completed-project data | Actual cost and execution lessons.       | Historical date, country, contract and scope require normalization. |
| Independent market database     | Broad market coverage and trend context. | May aggregate unlike projects and conceal scope assumptions.        |
| Public report / announcement    | Useful directional evidence.             | Often incomplete, non-comparable or based on headline value.        |
| Engineering judgement           | Fills gaps where evidence is limited.    | Must be transparent, reviewed and carried with higher uncertainty.  |

Table 10.8 - Indicative hierarchy of cost evidence.

## 10.9 Normalizing Benchmark Data

Raw benchmark values should not be copied directly into the estimate. They must be normalized to the target project basis so that apparent differences reflect real cost drivers rather than inconsistent definitions.




Figure 10.1 - Benchmark-normalization sequence.

| Normalization Factor | Questions to Resolve                                                                                        |
|----------------------|-------------------------------------------------------------------------------------------------------------|
| Scope                | Does the source include grid, land, tax, owner costs, contingency, logistics, commissioning and spares?     |
| Capacity             | Is cost normalized by DC, inverter AC, export AC, gross MWh or usable MWh?                                  |
| Date                 | What is the quote/base date and what escalation index or market adjustment is appropriate?                  |
| Currency             | Which exchange rate, hedge assumption and exposure date are used?                                           |
| Geography            | How do labour, productivity, logistics, permitting, local content and site conditions differ?               |
| Technology           | Are module, tracker, inverter, BESS chemistry, duration, cooling, fire and warranty assumptions comparable? |
| Commercial model     | Are risk allocation, liquidated damages, bonds, warranties, payment terms and margin comparable?            |
| Programme            | Do schedule, seasonality, phasing, working hours and acceleration requirements differ?                      |



Table 10.9 - Benchmark-normalization checklist.

## 10.10 Solar PV Equipment Benchmark

The PV equipment benchmark should distinguish the principal supply packages and the technical assumptions that affect each rate.

| Package                 | Material Cost Drivers                                                                                     | Evidence Required                                                               |
|-------------------------|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|
| PV modules              | Technology, efficiency, bifaciality, dimensions, volume, warranty, tariff, freight and delivery schedule. | Supplier quote, incoterms, warranty, logistics and quality requirements.        |
| Mounting / tracker      | Configuration, wind/snow, terrain tolerance, steel, foundation concept, row length and control system.    | Concept layout, design loads, geotechnical assumptions and supplier budget.     |
| Inverters / MV stations | String vs central architecture, power density, grid functions, transformer and switchgear scope.          | Electrical concept, equipment datasheets, grid requirements and supplier quote. |
| DC equipment            | Cable size/length, connectors, combiner architecture, trenching and installation method.                  | Preliminary quantities, routing and design assumptions.                         |
| Monitoring / controls   | SCADA, PPC, weather stations, cybersecurity, communications and integration boundary.                     | Functional architecture and employer requirements.                              |

Table 10.10 - Solar PV equipment cost drivers.

## 10.11 BESS Equipment Benchmark

BESS cost comparisons require particular care because energy boundary, duration, degradation, augmentation, safety scope and warranty can change the apparent unit rate materially.

### STANDARDS REFERENCE

Compliance scope against NFPA 855, UL 9540A and IEC 62933-5-2 (or the applicable local equivalent) directly affects BESS enclosure spacing, fire-detection and suppression provision, and augmentation strategy, and should therefore be confirmed before benchmark figures are treated as comparable across vendors or projects.

| BESS Element            | Key Cost Drivers                                                                                | Benchmark Control                                                                |
|-------------------------|-------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| Battery system          | Chemistry, cell format, duration, energy boundary, usable SOC window, degradation and warranty. | State gross/usable MWh, beginning/end-of-life basis and augmentation assumption. |
| Containers / enclosures | Energy density, thermal management, environmental rating, fire detection and suppression.       | Define included auxiliaries, certification and site conditions.                  |

| BESS Element               | Key Cost Drivers                                                                           | Benchmark Control                                                      |
|----------------------------|--------------------------------------------------------------------------------------------|------------------------------------------------------------------------|
| PCS and transformer        | MW rating, overload, reactive power, grid forming/following, voltage and efficiency.       | Separate power and energy components where possible.                   |
| EMS / controls             | Dispatch logic, plant controller, market interface, cybersecurity and data requirements.   | Define software licences, integration, testing and long-term support.  |
| Fire and emergency systems | Separation, detection, suppression, ventilation, water, access and authority requirements. | Identify site-specific civil and utility scope outside vendor package. |
| Augmentation / replacement | Degradation target, throughput, warranty and operational strategy.                         | State whether initial CAPEX includes future augmentation or reserve.   |

Table 10.11 - BESS equipment cost drivers and benchmark controls.

**COMMON MISTAKE**

A low battery-system rate may exclude PCS, transformer, controls, fire systems, freight, commissioning, warranty extensions or augmentation. Compare complete functional scope, not headline cell price.

## 10.12 Civil and Structural Balance of Plant

Civil cost uncertainty is often underestimated during early development because quantities depend on terrain, ground conditions, drainage, access and environmental constraints that are not yet fully surveyed.

| Civil Package         | Early Cost Basis                                                          | Principal Uncertainty                                                         |
|-----------------------|---------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| Earthworks            | Indicative cut/fill, grading philosophy and terrain class.                | Topographic accuracy, mass balance, unsuitable material and design evolution. |
| Roads and hardstands  | Length, width, pavement class and material source.                        | Ground strength, abnormal loads, drainage and borrow availability.            |
| Drainage              | Catchment screening, channels, culverts, attenuation and erosion control. | Hydrology, flood levels, discharge consent and climate resilience.            |
| Foundations           | Pile, screw, ballast or concrete concept by equipment type.               | Geotechnical conditions, corrosion, refusal and pull-out performance.         |
| Fencing / security    | Perimeter length, gates, CCTV and lighting concept.                       | Final boundary, public interface, wildlife and security requirements.         |
| Buildings / compounds | Control room, warehouse, workshop and welfare assumptions.                | Operational philosophy, code requirements and shared facilities.              |

Table 10.12 - Civil balance-of-plant benchmark basis.

## 10.13 Electrical Balance of Plant

Electrical cost should be linked to the preliminary single-line concept, equipment spacing, cable routing, voltage level, grid-code requirements and interface boundary.

| Electrical Package      | Typical Content                                                          | Material Drivers                                                                 |
|-------------------------|--------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| DC collection           | String cable, connectors, combiner boxes, trench/management and testing. | DC/AC ratio, layout density, cable length, voltage drop and installation method. |
| LV/MV collection        | AC cable, MV cable, switchgear, joints, terminations and earthing.       | Architecture, circuit length, conductor price and fault rating.                  |
| Auxiliary systems       | Station service, UPS, backup generation, lighting and small power.       | Operational resilience and BESS cooling/fire demand.                             |
| Protection / control    | Relays, metering, PPC, SCADA, telecoms and cybersecurity.                | Grid code, redundancy, utility protocol and interface complexity.                |
| Testing / commissioning | Factory/site testing, energisation support and performance tests.        | Contract requirements, phased COD and utility witness scope.                     |

Table 10.13 - Electrical balance-of-plant cost structure.

## 10.14 Grid Interconnection and Network Costs

Grid cost can dominate project uncertainty at early stage. The benchmark should separate the owner connection facilities from utility reinforcement, application charges, securities and contingent network works.

| Grid Cost Category              | Typical Scope                                                                      | Control Requirement                                                        |
|---------------------------------|------------------------------------------------------------------------------------|----------------------------------------------------------------------------|
| Collector / main substation     | Transformers, switchgear, busbars, protection, control, civil works and buildings. | Voltage, rating, redundancy, fault level and utility specification.        |
| Export circuit                  | Overhead line or cable, route civil works, joints, crossings and terminations.     | Length, route, land rights, terrain, crossings and conductor/cable design. |
| POI bay / extension             | Utility bay, bus extension, metering, protection and telecoms.                     | Network-owner scope, estimate, standards and outage requirements.          |
| Network reinforcement           | Remote line, transformer, reactive, stability or system-strength works.            | Formal study, allocation basis, sharing and refundability.                 |
| Connection charges / securities | Application fees, deposits, guarantees and milestone payments.                     | Current utility terms, timing and recoverability.                          |
| Compliance systems              | STATCOM, harmonic filters, synchronous support or advanced controls.               | Study-driven requirement and performance specification.                    |

Table 10.14 - Grid and network cost categories.

**ENGINEERING INSIGHT**

Do not hide unconfirmed grid reinforcement inside general contingency. Show the base connection concept, the credible downside scenario and the decision or study required to resolve the difference.

## 10.15 EPC Indirects, Overheads and Margin

Two projects with similar equipment quantities can receive very different EPC prices because schedule, risk allocation, bonding, temporary works, insurance and margin differ. The benchmark should expose these indirect components where possible.

| Indirect Cost              | Examples                                                                                        |
|----------------------------|-------------------------------------------------------------------------------------------------|
| Engineering                | Design management, calculations, drawings, studies, permits support and as-built documentation. |
| Project management         | Site management, controls, planning, commercial management and reporting.                       |
| Temporary facilities       | Offices, welfare, utilities, laydown, warehouses, temporary roads and fencing.                  |
| HSE and quality            | Personnel, systems, inspections, testing, laboratories and documentation.                       |
| Construction plant         | Cranes, piling rigs, trenchers, lifting, transport and temporary equipment.                     |
| Insurance / bonds          | Construction insurance, performance security, advance-payment bonds and warranties.             |
| Schedule premium           | Acceleration, multiple shifts, restricted hours, winter working and phased energisation.        |
| Contractor risk and margin | Pricing of retained risks, corporate overhead and profit.                                       |

Table 10.15 - Principal EPC indirect cost categories.

## 10.16 Owner, Development and Third-Party Costs

A project-level CAPEX benchmark should normally extend beyond the EPC price. The included owner and development costs must be stated clearly so the estimate reconciles to the funding plan and financial model.

| Owner Cost Category | Typical Inclusions                                                                                       |
|---------------------|----------------------------------------------------------------------------------------------------------|
| Development         | Land options, permits, environmental work, grid applications, surveys, legal and stakeholder engagement. |

| Owner Cost Category       | Typical Inclusions                                                                              |
|---------------------------|-------------------------------------------------------------------------------------------------|
| Owner engineering         | Technical advisers, design review, procurement support, construction monitoring and acceptance. |
| Project management        | Owner team, office, travel, document systems, controls and governance.                          |
| Land and rights           | Purchase/lease premiums, easements, wayleaves, compensation and temporary rights.               |
| Insurance / statutory     | Owner policies, fees, licences, charges, taxes and duties where applicable.                     |
| Spares / tools / training | Initial spares, special tools, training, manuals and operational readiness.                     |
| Utility and third party   | Connection fees, road/rail/water crossings, relocations and authority works.                    |
| Pre-COD operations        | Early staffing, energy imports, test energy, market registration and startup support.           |

Table 10.16 - Owner and development cost categories.

## 10.17 Currency, Escalation, Inflation and Tax

The estimate must distinguish real project cost from financing and currency effects. A common base date and currency are required for consistent comparison.

| Adjustment            | Required Basis                                                                           |
|-----------------------|------------------------------------------------------------------------------------------|
| Currency conversion   | Source currency, target currency, exchange rate date and hedge assumption.               |
| Price escalation      | Index, package exposure, timing, fixed-price period and procurement schedule.            |
| Commodity exposure    | Steel, copper, aluminium, lithium-related materials and fuel sensitivity where material. |
| Freight and logistics | Origin, incoterms, shipping mode, port, inland route and insurance.                      |
| Tariffs and duties    | Country of origin, customs classification, trade measures and exemptions.                |
| Taxes                 | Recoverable vs unrecoverable VAT/sales tax, withholding and local taxes.                 |
| Financing costs       | State whether interest during construction, fees and hedging are included or excluded.   |

Table 10.17 - Cost-base adjustments requiring explicit treatment.

## 10.18 Allowances, Contingency and Management Reserve

These terms should not be used interchangeably. Each addresses a different source of uncertainty and should be visible in the estimate structure.

| Cost Provision               | Purpose                                                                     | Example                                                                     |
|------------------------------|-----------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| Quantity allowance           | Covers expected scope where quantity is not yet measured.                   | Preliminary drainage length or substation earthworks.                       |
| Pricing allowance            | Provides an estimated rate where market evidence is incomplete.             | Budget rate for utility telecoms interface.                                 |
| Design-development allowance | Covers expected evolution within the approved concept.                      | Cable growth as layout and routing mature.                                  |
| Contingency                  | Covers uncertain events and variability within defined estimate scope.      | Productivity, quantity and market variability assessed by risk.             |
| Management reserve           | Held outside the controlled base for major unknowns or strategic decisions. | Alternative grid route or major scope change subject to executive approval. |
| Escalation                   | Covers expected price movement between base date and expenditure.           | Package-specific inflation to procurement date.                             |

Table 10.18 - Distinguishing allowances, contingency and reserve.

## 10.19 Developing the Cost Range

The benchmark should normally communicate a range rather than a single point. The low, base and high cases should reflect coherent scenarios, not arbitrary percentages.

| Scenario          | Typical Assumptions                                                                                                      |
|-------------------|--------------------------------------------------------------------------------------------------------------------------|
| Low / opportunity | Favourable market, limited grid works, straightforward ground, competitive logistics and successful design optimization. |
| Base / expected   | Most likely concept, current benchmark rates, defined allowances and risk-adjusted contingency.                          |
| High / downside   | Adverse grid, civil, logistics, market, programme or scope outcomes that remain credible at the decision date.           |
| Stress case       | Specific severe scenario used to test funding or investment resilience; not necessarily included in approved range.      |

Table 10.19 - Scenario structure for early CAPEX reporting.

## 10.20 Sensitivity Analysis

Sensitivity analysis identifies which assumptions matter most. It helps the team prioritize surveys, commercial engagement and risk treatment according to value at stake.

| Sensitivity Driver    | Illustrative Test                                                              |
|-----------------------|--------------------------------------------------------------------------------|
| Module price          | Change €/Wp or \$/Wp over the expected procurement range.                      |
| BESS system price     | Change €/kWh or \$/kWh on stated gross/usable basis.                           |
| PV DC/AC ratio        | Compare module and DC BOS increase against fixed AC/grid costs.                |
| BESS duration         | Compare 1h, 2h, 4h or selected duration with power components held separately. |
| Grid reinforcement    | No reinforcement, expected works and credible downside package.                |
| Export route          | Preferred route vs longer/crossing-intensive alternative.                      |
| Ground / foundations  | Standard piling vs refusal, corrosion or concrete/ballast response.            |
| Schedule / escalation | COD delay, extended preliminaries and later procurement price.                 |
| FX                    | Currency movement on imported equipment exposure.                              |
| Contingency           | Alternative risk confidence levels or estimate maturity.                       |

Table 10.20 - Typical CAPEX sensitivity drivers.

## 10.21 Cost Model, Assumption Register and Source Log

The benchmark should be supported by controlled records that make every material input traceable and updateable.

| Control Record      | Minimum Fields                                                                                        |
|---------------------|-------------------------------------------------------------------------------------------------------|
| Cost model          | Package, quantity, unit, rate, currency, base date, amount, low/high, source and formula.             |
| Assumption register | Assumption, rationale, owner, source, validation action, due date and cost consequence if false.      |
| Source log          | Document/quote, provider, revision, date, validity, confidentiality, scope and normalization applied. |
| Exclusion register  | Excluded item, reason, responsible budget, estimated exposure and decision owner.                     |

| Control Record | Minimum Fields                                                                                                  |
|----------------|-----------------------------------------------------------------------------------------------------------------|
| Change log     | Revision, change, cause, amount, range, approval and impact on financial model.                                 |
| Reconciliation | Previous estimate, current estimate, scope change, quantity change, rate change, FX/escalation and risk change. |

Table 10.21 - Minimum cost-governance records.

## 10.22 AI-Assisted CAPEX Benchmark Workflow

AI can reduce the administrative burden of extracting, structuring and comparing cost information. It should operate inside a controlled workflow with approved sources and human validation.



Figure 10.2 - Human-controlled AI-assisted CAPEX workflow.

| Workflow Step     | AI Contribution                                                    | Human Control                                                     |
|-------------------|--------------------------------------------------------------------|-------------------------------------------------------------------|
| Basis definition  | Draft basis checklist and identify missing inputs.                 | Approve project, commercial and scope assumptions.                |
| Source extraction | Extract line items, dates, currencies, inclusions and exclusions.  | Verify against original quote/document and confidentiality rules. |
| Normalization     | Prepare comparison table and flag incompatible denominators.       | Approve adjustments, indices, FX and comparability.               |
| Cost structure    | Map source items to approved cost breakdown and detect duplicates. | Confirm package boundaries and quantities.                        |
| Gap review        | Identify unpriced scope, stale data and unsupported assumptions.   | Define allowances, market tests and specialist actions.           |
| Scenarios         | Draft low/base/high cases and sensitivity narratives.              | Approve scenario logic, probability and decision relevance.       |
| Reporting         | Draft executive summary, variance analysis and action list.        | Approve benchmark, range, caveats and use restrictions.           |

Table 10.22 - AI contribution and professional control by workflow step.

### AI TIP

AI may reorganize and compare approved cost data. It must not invent supplier prices, quantities, tax rates, indices, exchange rates or grid charges. Every material value must trace to evidence or an explicit professional assumption.



## 10.23 Data Quality and Confidence Classification

Each material cost input should carry a confidence classification so the decision-maker can distinguish quoted values from broad allowances.

| Confidence | Typical Evidence                                                      | Required Treatment                                |
|------------|-----------------------------------------------------------------------|---------------------------------------------------|
| High       | Recent comparable firm quote or measured quantity with verified rate. | Use in base estimate; monitor validity and scope. |
| Medium     | Budget quote, recent normalized bid or preliminary quantity.          | Use with explicit adjustment and uncertainty.     |
| Low        | Historic benchmark, public source or broad parametric assumption.     | Use range, sensitivity and closure action.        |
| Unverified | Claim, informal indication or AI-generated value without source.      | Do not use as cost evidence until verified.       |

Table 10.23 - Cost-input confidence classification.

## 10.24 Worked Example - Initial CAPEX Benchmark for a 300 MWac Solar PV and 150 MW / 300 MWh BESS Project

A developer is evaluating a hybrid project in southern Spain. The concept comprises approximately 390 MWp of single-axis-tracker Solar PV, a 300 MWac export limit and a 150 MW / 300 MWh AC-coupled BESS. The point of interconnection is an existing 400 kV substation approximately 11 km from the site. Land control, grid capacity and survey evidence remain incomplete. Management requires a preliminary cost range for development funding and an initial investment screen.

All values in this worked example are fictional and illustrative. They are not current market quotations and must not be used for a real project without project-specific market testing, design development and professional review.

| Estimate Basis         | Illustrative Assumption                                                             |
|------------------------|-------------------------------------------------------------------------------------|
| Status date / currency | Q2 illustrative base date; EUR, excluding recoverable VAT and financing costs.      |
| PV configuration       | 390 MWp DC, single-axis tracker, string-inverter architecture.                      |
| BESS configuration     | 150 MW / 300 MWh AC-coupled; beginning-of-life gross energy basis.                  |
| Grid concept           | New collector substation, approximately 11 km export circuit and utility bay works. |
| Commercial basis       | Turnkey EPC benchmark plus owner/development costs; no firm bids.                   |

| Estimate Basis    | Illustrative Assumption                                                                                                             |
|-------------------|-------------------------------------------------------------------------------------------------------------------------------------|
| Estimate maturity | Acquisition / early concept benchmark with preliminary scope and wide range.                                                        |
| Exclusions        | Land purchase price, recoverable VAT, financing fees, interest during construction and future augmentation beyond stated allowance. |

Table 10.24 - Worked-example estimate basis.

| Cost Package                    | Low (€m) | Base (€m) | High (€m) | Base Benchmark                                        |
|---------------------------------|----------|-----------|-----------|-------------------------------------------------------|
| PV modules                      | 65       | 72        | 82        | Illustrative supply and delivery allowance.           |
| Trackers / mounting             | 24       | 28        | 34        | Preliminary layout and standard ground assumption.    |
| Inverters / MV stations         | 20       | 24        | 29        | String inverter and integrated MV concept.            |
| PV DC / electrical BOS          | 17       | 20        | 25        | Cable, connectors, MV collection and earthing.        |
| PV civil / installation         | 21       | 25        | 34        | Roads, drainage, piling and installation.             |
| PV SCADA / security / buildings | 4        | 5         | 7         | Plant controls, met stations, fencing and facilities. |
| BESS battery system             | 42       | 48        | 57        | Illustrative 300 MWh gross supply basis.              |
| BESS PCS / MV / controls        | 18       | 22        | 28        | PCS, transformers, EMS, fire and auxiliaries.         |
| BESS civil / integration        | 10       | 16        | 23        | Platform, roads, drainage, cabling and commissioning. |
| Collector substation            | 18       | 22        | 29        | Preliminary 400 kV concept and plant-side scope.      |
| Export circuit and crossings    | 13       | 18        | 28        | 11 km conceptual route with unresolved interfaces.    |
| Utility bay / connection works  | 8        | 12        | 25        | Unconfirmed utility scope and reinforcement exposure. |

| Cost Package              | Low (€m) | Base (€m) | High (€m) | Base Benchmark                                              |
|---------------------------|----------|-----------|-----------|-------------------------------------------------------------|
| EPC indirects / margin    | 17       | 22        | 30        | Engineering, management, temporary works, bonds and margin. |
| Owner / development costs | 14       | 18        | 24        | Development, advisers, surveys, owner team and spares.      |
| Contingency               | 20       | 28        | 40        | Risk-adjusted provision for stated estimate scope.          |
| TOTAL                     | 311      | 380       | 495       | Illustrative project CAPEX range.                           |

Table 10.25 - Illustrative low/base/high CAPEX benchmark.

| Metric                | Illustrative Base Result | Interpretation                                                                           |
|-----------------------|--------------------------|------------------------------------------------------------------------------------------|
| Total project CAPEX   | €380 million             | Includes the stated EPC, grid, owner and contingency boundary.                           |
| PV direct subtotal    | €174 million             | Modules, trackers, inverter/MV, PV BOS, civil, controls and facilities.                  |
| PV direct unit cost   | Approximately €0.45/Wp   | Uses 390 MWp denominator and excludes shared/grid/owner/contingency.                     |
| BESS direct subtotal  | €86 million              | Battery, PCS/MV/controls and BESS civil/integration.                                     |
| BESS direct unit cost | Approximately €287/kWh   | Uses 300 MWh gross beginning-of-life denominator.                                        |
| Grid direct subtotal  | €52 million              | Collector substation, export circuit and utility connection works.                       |
| Total range           | €311m to €495m           | Reflects coherent opportunity and downside scenarios, not statistical confidence limits. |

Table 10.26 - Worked-example normalized cost metrics.

| Sensitivity               | Illustrative CAPEX Effect          | Priority Action                                                  |
|---------------------------|------------------------------------|------------------------------------------------------------------|
| Utility reinforcement     | +€0m to +€18m above base allowance | Obtain formal network scope and cost responsibility.             |
| Export-route change       | +€5m to +€14m                      | Complete route survey, rights and crossing strategy.             |
| Difficult piling / ground | +€4m to +€12m                      | Perform preliminary geotechnical investigation and pile testing. |

| Sensitivity                  | Illustrative CAPEX Effect                                              | Priority Action                                                    |
|------------------------------|------------------------------------------------------------------------|--------------------------------------------------------------------|
| Module price movement        | Approximately $\pm\text{€}3.9\text{m}$ per $\pm\text{€}0.01/\text{Wp}$ | Market test and procurement timing strategy.                       |
| BESS price movement          | Approximately $\pm\text{€}3.0\text{m}$ per $\pm\text{€}10/\text{kWh}$  | Obtain comparable vendor budgets with common scope.                |
| Six-month schedule delay     | $+\text{€}4\text{m}$ to $+\text{€}10\text{m}$                          | Assess escalation, preliminaries, land and grid milestone impacts. |
| BESS fire / spacing redesign | $+\text{€}2\text{m}$ to $+\text{€}8\text{m}$ plus land impact          | Confirm authority and insurer requirements before design freeze.   |

Table 10.27 - Worked-example CAPEX sensitivities and closure actions.

**ENGINEERING INSIGHT**

The €380 million base case is suitable only as an early decision benchmark. The principal uncertainty is not equipment price alone; it is the combined exposure from grid scope, export route, ground conditions, BESS safety requirements and commercial risk allocation. Management should approve a range, not a point budget, and fund the evidence needed to narrow it.

## 10.25 Executive CAPEX Reporting

Executive reporting should summarize the basis, range, major changes, top sensitivities and decisions required. It should not conceal uncertainty behind excessive line-item detail.

| Executive Element | Minimum Content                                                                 |
|-------------------|---------------------------------------------------------------------------------|
| Headline range    | Low/base/high total and unit metrics with base date and currency.               |
| Estimate maturity | Development stage, classification and limitations.                              |
| Scope statement   | Principal inclusions, exclusions and owner/EPC boundary.                        |
| Top drivers       | Largest packages and reasons for difference from benchmark or prior estimate.   |
| Risk exposure     | Grid, ground, route, market, schedule and BESS-specific downside.               |
| Sensitivity       | Value impact of the assumptions most likely to change the decision.             |
| Actions           | Market tests, surveys, studies and design decisions needed to narrow the range. |
| Decision ask      | Approve, hold, re-scope, fund next stage or impose investment conditions.       |

Table 10.28 - Minimum executive CAPEX reporting content.

## 10.26 Reconciliation and Estimate Evolution

Every new estimate should reconcile to the previous approved version. This prevents scope growth, market changes and risk movements from being hidden inside a new total.

| Variance Category     | Examples                                                                      |
|-----------------------|-------------------------------------------------------------------------------|
| Scope change          | Added BESS duration, larger substation, new road or environmental mitigation. |
| Quantity change       | Cable length, module count, road length, earthworks or foundation quantities. |
| Rate change           | Supplier price, labour productivity, logistics or contractor margin.          |
| Currency / escalation | FX movement, inflation and procurement-date shift.                            |
| Risk / contingency    | Improved evidence, new exposure, mitigation or changed estimate maturity.     |
| Boundary transfer     | Cost moved between EPC, owner, utility or land package.                       |
| Correction            | Duplicate, omission, formula or unit error identified during review.          |

Table 10.29 - Estimate reconciliation categories.

## 10.27 Common Mistakes

| Mistake                             | Why It Fails                                                       | Better Practice                                                    |
|-------------------------------------|--------------------------------------------------------------------|--------------------------------------------------------------------|
| Using one headline €/Wp             | Scope, grid, owner cost and project conditions disappear.          | Use a cost breakdown and multiple defined metrics.                 |
| Mixing DC, AC and export capacity   | Unit rates become incomparable.                                    | State every denominator and plant boundary.                        |
| Copying stale benchmarks            | Market, technology and scope may have changed.                     | Normalize date, currency, location and configuration.              |
| Ignoring grid downside              | A major cost exposure is hidden in general contingency.            | Show base and downside connection scenarios.                       |
| Double counting EPC indirects       | Package rates and percentage adders overlap.                       | Map included scope before applying indirects.                      |
| Treating known scope as contingency | Base estimate is artificially low.                                 | Price known scope explicitly; reserve contingency for uncertainty. |
| Comparing BESS headline prices      | Energy boundary, PCS, warranty and augmentation differ.            | Compare complete functional scope and defined MWh basis.           |
| Reporting false precision           | Decision-makers assume a confidence the evidence does not support. | Use coherent ranges, confidence and caveats.                       |

| Mistake                  | Why It Fails                                                | Better Practice                                           |
|--------------------------|-------------------------------------------------------------|-----------------------------------------------------------|
| Letting AI create prices | Unsupported values enter the model with apparent authority. | Require traceable source or explicit reviewed assumption. |

Table 10.30 - Common CAPEX benchmark failure modes.

## 10.28 Best Practices

- Define the estimate purpose, stage, status date, capacity and commercial basis before collecting benchmarks.
- Use an approved cost breakdown that reconciles to procurement, schedule and financial-model structures.
- State inclusions, exclusions, owner-supplied scope and interface boundaries explicitly.
- Normalize all benchmark data for scope, date, currency, location, technology and contract model.
- Separate Solar PV, BESS, grid, EPC indirect, owner and contingency packages.
- Use multiple capacity metrics and state each denominator beside the unit cost.
- Distinguish quantity allowance, pricing allowance, design development, contingency and management reserve.
- Develop coherent low, base and high scenarios linked to real project drivers.
- Use sensitivity analysis to prioritize studies, market tests and design decisions by value at stake.
- Maintain source, assumption, exclusion, change and reconciliation registers.
- Reconcile every new estimate to the prior approved version.
- Use AI only to structure and challenge approved evidence under accountable professional review.

## 10.29 Engineering Review Checklist

| Review Area   | Validation Question                                                                                   | Check                    |
|---------------|-------------------------------------------------------------------------------------------------------|--------------------------|
| Purpose       | Is the decision, audience, stage and required estimate maturity clear?                                | <input type="checkbox"/> |
| Basis         | Are configuration, capacity, location, date, currency, programme and commercial assumptions approved? | <input type="checkbox"/> |
| Scope         | Are inclusions, exclusions, owner-supplied items and interfaces explicit?                             | <input type="checkbox"/> |
| Capacity      | Are DC, AC, export, BESS MW and gross/usable MWh definitions consistent?                              | <input type="checkbox"/> |
| Structure     | Does the cost breakdown cover PV, BESS, grid, EPC, owner, development and risk provisions?            | <input type="checkbox"/> |
| Sources       | Can every material rate be traced to a current source or explicit assumption?                         | <input type="checkbox"/> |
| Normalization | Have scope, date, FX, location, technology and commercial differences been adjusted?                  | <input type="checkbox"/> |

| Review Area      | Validation Question                                                                        | Check                    |
|------------------|--------------------------------------------------------------------------------------------|--------------------------|
| Quantities       | Are quantity bases, measurement maturity and growth allowances stated?                     | <input type="checkbox"/> |
| Grid             | Are connection, utility, reinforcement, securities and route costs treated transparently?  | <input type="checkbox"/> |
| BESS             | Are energy boundary, PCS, warranty, fire, augmentation and integration scope defined?      | <input type="checkbox"/> |
| Indirects        | Are EPC preliminaries, overhead, margin, bonds and insurance included without duplication? | <input type="checkbox"/> |
| Owner costs      | Are development, land, advisers, spares, fees and operational-readiness costs addressed?   | <input type="checkbox"/> |
| Escalation / tax | Are base date, inflation, FX, duties, taxes and financing exclusions clear?                | <input type="checkbox"/> |
| Risk provisions  | Are allowances, contingency and reserve distinguished and evidence-based?                  | <input type="checkbox"/> |
| Scenarios        | Do low, base and high cases reflect coherent project outcomes?                             | <input type="checkbox"/> |
| Sensitivity      | Are the largest value drivers quantified and linked to closure actions?                    | <input type="checkbox"/> |
| Reconciliation   | Is the change from the previous estimate explained by category?                            | <input type="checkbox"/> |
| AI control       | Were all AI-extracted values checked against original evidence and approved?               | <input type="checkbox"/> |
| Issue            | Are range, caveats, use restrictions and accountable approvals stated?                     | <input type="checkbox"/> |

Table 10.31 - Initial CAPEX Benchmark review checklist.

## 10.30 Prompt Toolkit

### Level 1 - Quick Prompt

#### QUICK PROMPT

Act as a Senior Solar PV and BESS Project Development Engineer. Using the supplied project configuration and approved benchmark sources, prepare a high-level CAPEX breakdown for Solar PV, BESS, grid, EPC indirects, owner costs and contingency. State all capacity denominators, assumptions, exclusions, evidence confidence and the three most material cost uncertainties. Do not invent market prices.

## Level 2 - Professional Prompt

### PROFESSIONAL PROMPT

Prepare an Initial CAPEX Benchmark for the supplied utility-scale Solar PV and co-located BESS project. Establish the estimate basis, base date, currency, commercial model, capacity definitions and scope boundary. Normalize all supplied quotations and benchmarks for scope, date, FX, location, technology and contract differences. Produce a low/base/high cost breakdown covering PV equipment, PV balance of plant, BESS equipment, BESS integration, grid connection, EPC indirects, owner/development costs, escalation and contingency. Include unit metrics, source/confidence register, exclusions, sensitivities, key cost risks, closure actions and executive recommendation. Clearly identify every professional assumption and do not create unsupported rates or quantities.

## Level 3 - Expert Prompt

### EXPERT PROMPT

You are acting as the Lead Cost and Technical Advisor supporting acquisition and investment screening for a utility-scale Solar PV and BESS project. Review all controlled design, land, grid, survey, programme, commercial, quotation and benchmark evidence. Establish the approved cost-estimating basis and classification; reconcile capacity and energy boundaries; map all costs to a controlled work breakdown; normalize benchmarks by scope, date, currency, geography, technology, schedule and risk allocation; and prepare low, base, high and selected stress scenarios. Quantify PV, BESS, grid, EPC, owner, development, statutory, logistics, escalation and contingency components; distinguish allowances, contingency and management reserve; identify exclusions and double-counting; calculate defined unit metrics; perform sensitivity and variance analysis; and produce a source log, assumption register, cost-risk register, reconciliation, executive summary and prioritized evidence-closure plan. Do not fabricate quotations, current indices, tax rates, exchange rates, quantities or utility charges. Mark all values requiring accountable human approval.

## 10.31 Recommended Reference Framework

The CAPEX benchmark should be aligned with the project organisation's approved estimating method, commercial governance and current market evidence. The reference framework should include:

- Current organisational cost-estimating, investment, procurement, delegated-authority and project-stage procedures.
- Current professional cost-estimate classification and recommended practices adopted by the organisation, including AACE or equivalent frameworks where applicable.
- Approved project design basis, layout, single-line concept, grid strategy, land plan, environmental requirements, schedule and risk register.
- Current supplier quotations, contractor budgets, recent comparable bids and completed-project cost data with controlled scope and commercial terms.
- Official currency, inflation, commodity, freight, tax, tariff and duty sources appropriate to the base date and jurisdiction.
- Current utility connection offers, network study outputs, charges, securities and responsibility boundaries.
- Applicable PV, BESS, electrical, civil, fire-safety, environmental, grid-code and commissioning requirements affecting cost scope.



- Project document-control, confidentiality, cybersecurity, personal-data and approved-AI governance procedures.

#### ■ STANDARDS REFERENCE

Market rates, tax rules, tariffs, exchange rates and utility charges are time-sensitive. Verify the current approved source and effective date before issuing any estimate.

## 10.32 Chapter Summary

The Initial CAPEX Benchmark converts an immature project definition into a transparent capital-cost range that can support development and investment decisions. It begins with a controlled estimate basis and scope boundary, uses consistent capacity definitions, separates the principal cost packages and normalizes external evidence before comparison. It then applies allowances, contingency, scenarios and sensitivities according to the uncertainty that remains.

Artificial Intelligence can accelerate source extraction, cost mapping, normalization tables, assumption tracking, completeness checks, sensitivity drafting and executive reporting. It cannot determine a real market price, approve scope, select commercial risk allocation or authorize an investment budget. Those responsibilities remain with qualified engineering, cost, commercial and investment professionals.

## 10.33 Key Takeaways

- An early CAPEX benchmark is a controlled cost range, not a contractor price or approved budget.
- Estimate precision must remain consistent with project definition and evidence maturity.
- Scope boundaries and capacity denominators are prerequisites for valid comparison.
- Normalize benchmarks for date, currency, geography, technology, programme and commercial structure.
- Separate PV, BESS, grid, EPC indirects, owner costs and risk provisions.
- For BESS, define power, gross/usable energy, operating boundary, warranty and augmentation basis.
- Treat known scope explicitly; do not hide omissions inside contingency.
- Build coherent low, base and high scenarios and quantify the assumptions that drive value.
- Use sensitivity analysis to prioritize evidence closure and protect investment headroom.
- Maintain source, assumption, exclusion, change and reconciliation records.
- Use AI to organize and challenge cost evidence only under source control and human approval.

#### LOOKING AHEAD - VOLUME 2, CHAPTER 11

Volume 2 begins with Selecting the Optimal PV Technology for Utility-Scale Solar Projects. It applies the evidence, workflow and cost-control principles from Volume 1 to the first major engineering design decision: choosing a technology strategy that balances performance, constructability, supply chain, bankability and lifecycle value.

END OF CHAPTER 10 | END OF VOLUME 1

## Volume 1 Closing Note

---

Volume 1 has established the controlled foundation for AI-assisted utility-scale Solar PV and BESS project development. The methods are intentionally reusable: define the decision, control the evidence, structure the task, make assumptions explicit, separate facts from interpretation, identify uncertainty and retain qualified human review.

The completed early-stage outputs should not be treated as isolated reports. Together they form a connected development system. Site constraints affect land strategy; land and environmental conditions affect layout and schedule; grid and technical assumptions affect risk and CAPEX; every material finding should flow into ownership, actions and decision gates.

Volume 2 will build on this foundation by applying the same professional methodology to more advanced technical engineering, design coordination, procurement, project controls and delivery activities.

### **Final principle**

Use AI to increase the quality, consistency and traceability of engineering work. Never use it to bypass evidence, professional review or accountability.